

DO NOT DAMAGE OR CUT LEADER

TWO HEAVY-DUTY GAUGE 'T' BARS PER TREE, 2400mm LONG, LOCATED AWAY FROM ALL BRANCHES, ONE ON THE SIDE OF PREVAILING WIND, THE OTHER ON THE OPPOSITE SIDE. DO NOT DRIVE STAKES THROUGH ROOT BALL.

TIES TO BE FLEXIBLE TIE SYSTEM THAT ALLOWS THE TREE A REASONABLE DEGREE OF MOVEMENT (50mm BURLAP STRIPS OR PROPRIETARY SYSTEM.) WIRE OR WIRE ENCASED HOSE IS NOT ACCEPTABLE. TIES TO BE REMOVED 1 YEAR AFTER PLANTING.

BURLAP STRIP TIES LOOPED IN A LOOSE FIGURE '8' AROUND TRUNK AND SECURED TO STAKE WITH WIRE (OR AS SPECIFIED BY MANUFACTURER OF PROPRIETARY SYSTEM)

TRUNK GUARD INSTALLED AS PER MANUFACTURER'S RECOMMENDATIONS. OMIT IN PLANTING BEDS

CROWN OF ROOT BALL

75mm SHREDDED CEDAR BARK MULCH (NOT DYED)

CREATE 150mm SAUCER AROUND TREE 300mm BEYOND ROOTBALL

CLEAN SHARP EDGE BETWEEN SAUCER AND FINISHED GRADE

SOD / PAVING / SPECIFIED GROUNDCOVER

FINISHED GRADE

TRIPLE MIX OR SCREENED, AMENDED TOPSOIL, FREE OF STONES

150mm SCARIFIED SOIL

CUT AND REMOVE TOP 1/3 OF BURLAP, REMOVE ALL SIDES OF WIRE BASKET AND ALL TIES

COMPACTED SUBGRADE

AT GRADE

SOD / PAVING / SPECIFIED GROUNDCOVER

150mm SCARIFIED SOIL

75mm SHREDDED CEDAR BARK MULCH (NOT DYED)

CREATE 150mm SAUCER AROUND TREE, 300 mm BEYOND ROOTBALL

FINISHED GRADE

TRIPLE MIX OR SCREENED, AMENDED TOPSOIL, FREE OF STONES

VARIES WITH SLOPE

SLOPE PIT BOTTOM FOR DRAINAGE

COMPACTED SUBGRADE

ON A SLOPE

NOTES

1. DO NOT ALLOW AIR POCKETS WHEN BACKFILLING.
2. POSITION CROWN OF ROOT BALL 50mm ABOVE FINISHED GRADE TO ALLOW FOR SETTLING.
3. DO CORRECTIVE PRUNING TO RETAIN NATURAL FORM OF TREE.
4. FOR TREES PLANTED WITHIN PLANTING OR SHRUB BEDS, DELETE SAUCER AROUND BASE OF TREE.
5. NO TREE PITS SHALL BE LEFT OPEN OVERNIGHT.
6. ALL DIMENSIONS ARE IN MILLIMETRES.

NO.	REVISION	APR'D	DATE
1	PLANTING METHODOLOGY	EN	JUL/04
2	PLANTING METHODOLOGY	DW	JUN/07

TOWN OF COLLINGWOOD

APR'D: DW

DATE: JAN/03

DRAWN: AB

SCALE: NTS

DECIDUOUS TREE PLANTING

STD. No.

1101

DO NOT DAMAGE OR CUT LEADER


TIES TO BE FLEXIBLE TIE SYSTEM THAT ALLOWS THE TREE A REASONABLE DEGREE OF MOVEMENT (50mm BURLAP STRIPS OR PROPRIETARY SYSTEM.) WIRE OR WIRE ENCASED HOSE IS NOT ACCEPTABLE. TIES TO BE REMOVED 1 YEAR AFTER PLANTING.

BURLAP STRIP TIES LOOPED IN A LOOSE FIGURE '8' AROUND TRUNK AND SECURED TO STAKE WITH WIRE (OR AS SPECIFIED BY MANUFACTURER OF PROPRIETARY SYSTEM)

TWO HEAVY-DUTY GAUGE 'T' BARS PER TREE, 2400mm LONG, CLEAR OF ALL BRANCHES, ONE ON THE SIDE OF PREVAILING WIND, THE OTHER ON THE OPPOSITE SIDE. DO NOT DRIVE STAKES THROUGH ROOT BALL.


NOTES

1. DO NOT ALLOW AIR POCKETS WHEN BACKFILLING.
2. POSITION CROWN OF ROOT BALL 50mm ABOVE FINISHED GRADE TO ALLOW FOR SETTLING.
3. FOR TREES PLANTED WITHIN PLANTING OR SHRUB BEDS, DELETE SAUCER AROUND BASE OF TREE.
4. NO TREE PITS SHALL BE LEFT OPEN OVERNIGHT.
5. ALL DIMENSIONS IN MILLIMETRES.




SOD/ PAVING/ SPECIFIED GROUNDCOVER

150mm SCARIFIED SOIL




NO.	REVISION	APR'D	DATE
1	PLANTING METHODOLOGY	EN	JUL/04
2	PLANTING METHODOLOGY	DW	JUN/07

TOWN OF COLLINGWOOD	APR'D: DW	DATE: JAN/03
	DRAWN: AB	SCALE: NTS
CONIFEROUS TREE PLANTING	STD. No.	1102



TYPICAL SHRUB PLANTING



PLANTING ON 3:1 SLOPE DETAIL

NOTES

1. DO NOT ALLOW AIR POCKETS WHEN BACKFILLING.
2. POSITION CROWN OF ROOT BALL 25mm ABOVE FINISH GRADE TO ALLOW FOR SETTLING.
3. ALL DIMENSIONS IN MILLIMETRES.

NO.	REVISION	APR'D	DATE
1	PLANTING METHODOLOGY	EN	JUL/04
2	PLANTING METHODOLOGY	DW	JUN/07

TOWN OF COLLINGWOOD	APR'D: DW	DATE: JAN/03
	DRAWN: AB	SCALE: NTS
SHRUB PLANTING	STD. No.	1103