

BLACKMOOR COMMUNITY
CENTRE



WWW.JASPERDESIGN.CA

(705) 888-6300

279 STE. MARIE STREET COLLINGWOOD, ON.

L9Y 3K6

BCIN SIGNATURE:

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS DESIGN, AND HAS THE QUALIFICATIONS AND MEETS THE REQUIREMENTS SET OUT IN THE ONTARIO BUILDING CODE AS A QUALIFIED DESIGNER UNDER DIVISION C SECTION 3.2.4.

JAMES SCHNEIDER IND. BCIN# 228 JASPER DESIGN FIRM BCIN# 10

SIGNATURE:

DATE:

CODE DESIGNATION:

PART 9 0.B.C.

REVISIONS:

DATE:	SUMMARY:

NOTES:

NOTE:
CONTRACTOR IS TO VERIFY ALL
DIMENSIONS PRIOR TO CONSTRUCTION, AND
REPORT ANY DISCREPANCIES TO JASPER
DESIGN

NOTE:
CONTRACTOR IS RESPONSIBLE TO INSTALL
ANY AND ALL REQUIRED TEMPORARY
BRACING DURING CONSTRUCTION, AND ALL
BRACING THAT MAY BE REQUIRED FOR
ROOF TRUSSES AS PER TRUSS
MANUFACTURER

DRAWINGS ARE NOT TO BE SCALED

NOTE: THE MINIMUM REQUIRED SOIL BEARING CAPACITY IS TO BE 1500 P.S.F UNLESS OTHERWISE SPECIFIED

DATE:

2020-02-27

PROJECT:

BLACKMOOR COMMUNITY CENTRE

PROJECT LOCATION:

COLLINGWOOD, ON


SCALE:

NOT TO SCALE

SHEET NO.



FRONT ELEVATION



REAR ELEVATION



WWW.JASPERDESIGN.CA

279 STE. MARIE STREET

COLLINGWOOD, ON.

L9Y 3K6 (705) 888-6300

BCIN SIGNATURE:

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS DESIGN, AND HAS THE QUALIFICATIONS AND MEETS THE REQUIREMENTS SET OUT IN THE ONTARIO BUILDING CODE AS A QUALIFIED DESIGNER UNDER DIVISION C SECTION 3.2.4.

JAMES SCHNEIDER JASPER DESIGN IND. BCIN# 22823 FIRM BCIN# 101098

SIGNATURE:

DATE:

CODE DESIGNATION:

PART 9 0.B.C.

REVISIONS: DATE: SUMMARY:

NOTES:

NOTE:
CONTRACTOR IS TO VERIFY ALL
DIMENSIONS PRIOR TO CONSTRUCTION, AND
REPORT ANY DISCREPANCIES TO JASPER

NOTE:
CONTRACTOR IS RESPONSIBLE TO INSTALL
ANY AND ALL REQUIRED TEMPORARY
BRACING DURING CONSTRUCTION, AND ALL
BRACING THAT MAY BE REQUIRED FOR
ROOF TRUSSES AS PER TRUSS
MANUFACTURER

DRAWINGS ARE NOT TO BE SCALED

NOTE: THE MINIMUM REQUIRED SOIL BEARING CAPACITY IS TO BE 1500 P.S.F UNLESS OTHERWISE SPECIFIED

DATE:

2020-02-27

PROJECT:

BLACKMOOR COMMUNITY CENTRE


PROJECT LOCATION:

COLLINGWOOD, ON

SCALE:

1/4" = 1 FOOT

SHEET NO.



RIGHT ELEVATION



LEFT ELEVATION



WWW.JASPERDESIGN.CA

279 STE. MARIE STREET

COLLINGWOOD, ON.

L9Y 3K6 (705) 888-6300

BCIN SIGNATURE:

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS DESIGN, AND HAS THE QUALIFICATIONS AND MEETS THE REQUIREMENTS SET OUT IN THE ONTARIO BUILDING CODE AS A QUALIFIED DESIGNER UNDER DIVISION C SECTION 3.2.4.

JAMES SCHNEIDER IND. BCIN# 228 JASPER DESIGN FIRM BCIN# 101

SIGNATURE: ___

DATE:

CODE DESIGNATION:

PART 9 O.B.C.

DATE: SUMMARY:

NOTES:

NOTE:
CONTRACTOR IS TO VERIFY ALL
DIMENSIONS PRIOR TO CONSTRUCTION, AND
REPORT ANY DISCREPANCIES TO JASPER
DESIGN

NOTE:
CONTRACTOR IS RESPONSIBLE TO INSTALL
ANY AND ALL REQUIRED TEMPORARY
BRACING DURING CONSTRUCTION, AND ALL
BRACING THAT MAY BE REQUIRED FOR
ROOF TRUSSES AS PER TRUSS
MANUFACTURER

NOTE: DRAWINGS ARE NOT TO BE SCALED

NOTE: THE MINIMUM REQUIRED SOIL BEARING CAPACITY IS TO BE 1500 P.S.F UNLESS OTHERWISE SPECIFIED

DATE:

2020-02-27

PROJECT:

BLACKMOOR COMMUNITY CENTRE


PROJECT LOCATION:

COLLINGWOOD, ON

SCALE:

1/4" = 1 FOOT

SHEET NO.



WWW.JASPERDESIGN.CA

279 STE. MARIE STREET

COLLINGWOOD, ON. L9Y 3K6 (705) 888-6300

2020-02-27

CENTRE

SHEET NO.


A - 4

=1 FOOT

IND. BCIN# 22823

FIRM BCIN# 101098


5 TANKLESS HOT WATER HEATER (AS PER SB-12 COMPLINACE PACKAGE PROVIDED) 6 6 INSTALLED AS PER MANUFACTURER SUMP PUMP INSTALLED AS PER MANUFACTURER SPECE 5 7 8 8 6 FLOOR DRAIN ⊚_{FD}. 9 9



TRUSS MANUFACTURER TO SITE MEASURE SPAN, HEEL HEIGHT, AND OVERHANG TO VERIFY DIMENSIONS (PRIOR TO PRODUCTION)

ALL EXTERIOR WALLS SUBJECT TO SNOW ACCUMULATION DUE TO ROOF CONDITIONS ARE TO BE FLASHED AS PER O.B.C. 9.26.4

TRUSS MANUFACTURER IS TO DROP THE TOP CHORD ON ALL HIP END TRUSSES TO ALLOW FOR THE INSTALLATION OF 1 1/2"x31/2" PURLINS PRIOR TO SHEATHING



TRUSS LAYOUT

ROOF PLAN

H-?	HEADER SCHEDULE	dB-?	BEAM SCH	HEDULE
#	MEMBER SIZE	UD .	MEMBER SI	IZE
1	2 PLY 2"x10" SPF. NO. 1 OR 2	#	dB=DROPPED	fB=FLUSH
	(AS PER D.B.C. PART 9 TABLE A-15)	1	4 PLY 2"x10" SPF. NO	. 1 OR 2
2			(AS PER O.B.C. PART 9 T	ABLE A-12)
		2		
3				
4		3		
5		4		
6				
		5		
7				
8		6		
9				

C-?∑	COLUMN SCHEDULE
#	MEMBER SIZE
1	8"x8" ROUGH SAWN TIMBER COLUMN
2	
3	
4	
5	
6	
7	
8	
9	

UTILITY LEGEND

HIGH EFFICENCY GAS FURNACE, DIRECT VENT/ SEALED COMBUSTION (AS PER SB-12 COMPLIANCE PACKAGE PROVIDED) EXHAUST RANGE HOOD TO EXTERIOR TO 0.B.C. 9.32.3. AND MANUFACTURER SPECS.



GAS FURNACE

HOT WATER HEATER (AS PER SB-12 COMPLINACE PACKAGE PROVIDED) INSTALLED AS PER MANUFACTURER SPECS.



TANKLESS HOT WATER HEATER (AS PER SB-12 COMPLINACE PACKAGE PROVIDED) SB-12 CUMPLINAGE FASION -INSTALLED AS PER MANUFACTURER



SUMP PUMP INSTALLED AS PER MANUFACTURER SPECE FLOOR DRAIN

LEGEND

EXHAUST RANGE HOOD TO EXTERIOR TO O.B.C. 9.32.3. AND MANUFACTURER SPECS. EXHAUST CEILING FAN TO O.B.C. 9.32 SMOKE/CO-2 DETECTOR HARDWIRED & INTERCONNECTED W/ BATTERY BACKUP

NOTES:

NOTE:

TRUSS MANUFACTURER TO SITE MEASURE SPAN, HEEL HEIGHT, AND OVERHANG TO VERIFY DIMENSIONS (PRIOR TO PRODUCTION)

NOTE:

ALL EXTERIOR WALLS SUBJECT TO SNOW ACCUMULATION DUE TO ROOF CONDITIONS ARE TO BE FLASHED AS PER O.B.C. 9.26.4



WWW.JASPERDESIGN.CA

279 STE. MARIE STREET

COLLINGWOOD, ON.

L9Y 3K6 (705) 888-6300

BCIN SIGNATURE:

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS
DESIGN, AND HAS THE QUALIFICATIONS
AND MEETS THE REQUIREMENTS SET OUT IN THE ONTARIO BUILDING CODE AS A QUALIFIED DESIGNER UNDER DIVISION C SECTION 3.2.4.

JAMES SCHNEIDER IND. BCIN# 22823 JASPER DESIGN FIRM BCIN# 101098

SIGNATURE:

DATE:

CODE DESIGNATION:

PART 9 0.B.C.

REVISIONS:				
DATE:	SUMMARY:			

NOTES:

CONTRACTOR IS TO VERIFY ALL
DIMENSIONS PRIOR TO CONSTRUCTION, AND
REPORT ANY DISCREPANCIES TO JASPER NOTE: CONTRACTOR IS RESPONSIBLE TO INSTALL

ANY AND ALL REQUIRED TEMPORARY
BRACING DURING CONSTRUCTION, AND ALL
BRACING THAT MAY BE REQUIRED FOR ROOF TRUSSES AS PER TRUSS MANUFACTURER

DRAWINGS ARE NOT TO BE SCALED

THE MINIMUM REQUIRED SOIL BEARING CAPACITY IS TO BE 1500 P.S.F UNLESS OTHERWISE SPECIFIED

DATE:

2020-02-27

PROJECT:

BLACKMOOR COMMUNITY CENTRE


PROJECT LOCATION:


COLLINGWOOD, ON

SCALE:

=1 FOOT

SHEET NO.





WWW.JASPERDESIGN.CA

279 STE. MARIE
STREET
COLLINGWOOD, ON.

L9Y 3K6 (705) 888-6300

BCIN SIGNATURE:

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS DESIGN, AND HAS THE QUALIFICATIONS AND MEETS THE REQUIREMENTS SET OUT IN THE ONTARIO BUILDING CODE AS A QUALIFIED DESIGNER UNDER DIVISION C SECTION 3.2.4.

JAMES SCHNEIDER IND. BCIN# 22823 JASPER DESIGN FIRM BCIN# 101098

SIGNATURE:

NOTE:

NOTE:

TO PRODUCTION)

TRUSS MANUFACTURER TO SITE MEASURE SPAN, HEEL HEIGHT, AND OVERHANG TO VERIFY DIMENSIONS (PRIOR

DATE: ___

CODE DESIGNATION:

PART 9 0.B.C.

REVISIONS:

DATE: SUMMARY:

NOTES:

NOTE:
CONTRACTOR IS TO VERIFY ALL
DIMENSIONS PRIOR TO CONSTRUCTION, AND
REPORT ANY DISCREPANCIES TO JASPER
DESIGN
NOTE:

NOTE:
CONTRACTOR IS RESPONSIBLE TO INSTALL
ANY AND ALL REQUIRED TEMPORARY
BRACING DURING CONSTRUCTION, AND ALL
BRACING THAT MAY BE REQUIRED FOR
ROOF TRUSSES AS PER TRUSS
MANUFACTURER

DRAWINGS ARE NOT TO BE SCALED

NOTE: THE MINIMUM REQUIRED SOIL BEARING CAPACITY IS TO BE 1500 P.S.F UNLESS OTHERWISE SPECIFIED

DATE:

2020-02-27

PROJECT:

BLACKMOOR COMMUNITY CENTRE

PROJECT LOCATION:

COLLINGWOOD, ON


SCALE:


AS NOTED

SHEET NO.

A - 6

CROSS SECTIONS





D-1 AIR/ VAPOUR BARRIER @ T/O FND. WALL
A-8 SCALE: 1" = 1'-0"

DETAILS

	DOOR SCHEDULE								
NUMBER	ELEV.	QTY	FLOOR	WIDTH	HEIGHT	R/O	DESCRIPTION	COMMENTS	
D01		1	1	68 "	80 "	69"X81"	MULLED UNIT-LHL/RHR		
D02		1	1	71 1/2 "	80 "	74"X82 1/2"	GARAGE-GARAGE DOOR CHD06		
D03		1	1	71 1/2 "	80 "	74"X82 1/2"	4 DR. BIFOLD-DOOR P05		

	WINDOW SCHEDULE									
NUMBER	ELEV.	QTY	FLOOR	WIDTH	HEIGHT	R/O	DESCRIPTION	COMMENTS		
W01		4	1	24 "	60 "	25"X61"	SINGLE CASEMENT-HR			
W02		1	1	48 "	36 "	49"X37"	DOUBLE CASEMENT-LHL/RHR			

NOTE:

THE WINDOW AND DOOR STYLES THAT ARE SHOWN ARE RECOMMENDATIONS AND THE CLIENT AND CONTRACTOR ARE TO DETERMINE THE FINAL CHOICES PRIOR TO ORDERING.



WWW.JASPERDESIGN.CA

279 STE. MARIE STREET

L9Y 3K6 (705) 888-6300

BCIN SIGNATURE:

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS DESIGN, AND HAS THE QUALIFICATIONS AND MEETS THE REQUIREMENTS SET OUT IN THE ONTARIO BUILDING CODE AS A QUALIFIED DESIGNER UNDER DIVISION C SECTION 3.2.4.

JAMES SCHNEIDER IND. BCIN# 22823 JASPER DESIGN FIRM BCIN# 101098

SIGNATURE: __

DATE:

CODE DESIGNATION:

PART 9 O.B.C.

REVISIONS:

DATE: SUMMARY:

NOTES:

NOTE:
CONTRACTOR IS TO VERIFY ALL
DIMENSIONS PRIOR TO CONSTRUCTION, AND
REPORT ANY DISCREPANCIES TO JASPER

NOTE:
CONTRACTOR IS RESPONSIBLE TO INSTALL
ANY AND ALL REQUIRED TEMPORARY
BRACING DURING CONSTRUCTION, AND ALL
BRACING THAT MAY BE REQUIRED FOR
ROOF TRUSSES AS PER TRUSS
MANUFACTURER

DRAWINGS ARE NOT TO BE SCALED

NOTE: THE MINIMUM REQUIRED SOIL BEARING CAPACITY IS TO BE 1500 P.S.F UNLESS OTHERWISE SPECIFIED

DATE:

2020-02-27

PROJECT:

BLACKMOOR COMMUNITY CENTRE

PROJECT LOCATION:

COLLINGWOOD, ON

SCALE:

AS NOTED

SHEET NO.


A - 7

WALL SECTIONS


W-1 WALL SECTION

A4-6 SCALE: 1/2" = 1'-0"

SCHEDULES



FLOOR CONSTRUCTION: (F1) - FLOOR FINISH AS PER CLIENT - 4" 25 MPA CONC. SLAB (4650 p.s.i) - 6" COMPACTED STONE (ALL FILL TO BE SOAKED, COMPACTED AND FREE OF ORGANIC MATERIAL)



FLOOR

ROOF

ROOF CONSTRUCTION: (R 1)

- 25YR. ASPHALT SHINGLES (AS PER CLIENT)

- 1/2" PLYWOOD SHEATHING W/ H-CLIPS

- ICE AND WATER SHIELD ALL EAVES AND VALLEYS

ASSEMBLIES

GENERAL NOTES	3
SCOPE OF WORK: THE CONSTRUCTION OF A RECREATIONAL BUILDING AS PER THE DRAWINGS PROVIDED	STEP FOOTING AND TOP OF FOUNDATION WALL MAINTAIN 4' FROST COVERAGE. 24" MAX. VERTICAL AND 48" HORIZONTAL RUN FOR ALL STEP FOOTINGS 3 PLY 2"x6" STUD SUPPORT
BUILDER RESPONSIBLE FOR SAFE DISPOSAL OF ALL ORGANIC AND NON-ORGANIC WASTE AND MATERIAL.	FOR ALL GIRDER END- BEARINGS (MIN) ALL COLUMNS SHALL HAVE SOLID BLOCKING TO
ALL WINDOW DIMENSIONS IN FEET EX. 4660= 4'6"x6'0"	STEEL LINTELS FOR STONE/BRICK VENEER, 5"x3-1/2"x1/4" STEEL ANGLE IRON (AS PER. O.B.C.
NOTES: -ALL FRAMING TO OBC 9.23 -ALL PLUMBING TO OBC PART 7 -PROVIDE ANTI-SCALD/MIX VALVES TO OBC 7.6.5.1 -PROVIDE SWITCHED LIGHT @ EACH ENTRY	9.20.5.2.8) ALL FLOOR BEAMS MUST CONFORM TO D.B.C. 9.23.4. WHERE ENGINEERED FLOOR SYSTEM IS BEING CONSTRUCTED, BEAMS MUST CONFORM TO D.B.C. 9.23.4. AND ENGINEERED FLOOR SYSTEM SPECIFICATIONS
-HRV REQUIRED ELECTRICAL NOTES 9.34.2.1 - PROVIDE SWITCHED ELECTRICAL	ALL ENGINEERED BEAMS 2.0(E) UNLESS SUPPLIER DESIGNS COMPATIBLE OPTION NOTE: ALL ENGINEERED LINTELS TO HAVE
LIGHT @ EACH ENTRY DOOR INTO DWELLING 9.34.2.2 - PROVIDE SWITCHED ELECTRICAL LIGHT IN ALL ROOMS DESCRIBED IN SENT (1) OF THIS SUBSECTION	2 PLY JACK STUDS VALLEY FRAMING @ 16" 0/C, W/ RIDGE BOARD (NOT LESS 2" (50MM) GREATER IN DEPTH THEN THE COMMON RAFTERS) AND 1/2" SHEATHING (WITH H-CLIPS)
9.34.2.3 - PROVIDE 3-WAY WALL SWITCH LIGHT AT HEAD AND FOOT OF ALL STAIRS UNLESS OTHER STATED	2" x 4" TO MAX 6' - 2" 2" x 6" TO MAX 10' - 1" 2" x 8" TO MAX 13' - 0" 2" x 10" TO MAX 15'-10"
9.34.2.5 - A LIGHTING OUTLET WITH FIXTURE SHALL BE PROVIDED IN STORAGE ROOMS.	

ALL LOAD BEARING WALLS 9'-0" OR TALLER TO BE PROVIDED W/ INTERMEDIATE BLOCKING MATCHING STUD DEPTH @ 4'-0" D.C.

COMPLIANCE OPTIONS:							
SB-12 PRESCRIPTIVE [SB-12 - 3.1.1.2.(A TO C)]	TABLE: XXXXXXXXX PACKAGE	E: A1 A2 A3 A4 A5 A6 (CIRCLE ONE)					
SB-12 PERFORMANCE [SB-12 - 2.1.2.]	- ATTACH ENERGY PERFORMANCE	CALCULATIONS USING AN APPROVED SOFTWARE					
ENERGY STAR [SB-12 - 2.1.3.]	- ATTACH BUILDER OPTION PACKA	AGE FORM					
R-2000 *[se-12 - 3.1.3]	- ATTACH R-2000 HOT2000 REPO	IRT					
PROJECT DESIGN CO	NDITIONS:						
LIMATIC ZONE (SB-1):	ATING EQUIPMENT EFFICIENCY:	SPACE HEATING FUEL SOURCE:					
ZONE 1 (< 5000 DEGREE DAYS)	> DR = 92% AFUE	GAS PROPANE SOLID FUEL					
ZONE 2 (> OR = 5000 DEGREE DAYS)	> DR = 84% < 92% AFUE	OIL ELECTRIC EARTH ENERGY					
INDOWS+SKYLIGHTS & GLASS DOORS:		OTHER BUILDING CONDITIONS:					
ROSS WALL AREA = XXXXX SQFT ()	(XXX M²)	☐ LOG/POST & BEAM ☐ WALKOUT BASEMENT ☐ COMBO UNIT ☐ ICF BASEMENT ☐ SLAB-ON-GRADE ☐ AIR SOURCED HEAT PUMP (ASHP)					
	7.5						

ENERGY EFFICIENCY DESIGN SUMMARY

ZONE Z (> DK SOUD BEAKEE BATS)									
WINDOWS+SKYLIGHTS & GLASS DOORS:		OTHER B	BUILDING CONDITIONS:						
GROSS WALL AREA = XXXXX SQFT (XXXX M²)	% WINDOW+ =			BO UNIT SOURCED HEAT PUMP (ASHP)					
GROSS WINDOW+ AREA = XXXXX SQFT (XXXX M²)	1 1 1			UND SOURCED HEAT PUMP (GSHP)					
BUILDING SPECIFICATIONS: [PROVIDE VALUES AND RATINGS OF THE ENERGY EFFICIENCY COMPONENTS PROPOSED, OR ATTACH BOP FORM]									
BUILDING COMPONENT:	RSI / R VALUES:		BUILDING COMPONENT:	EFFICIENCY RATINGS:					
THERMAL INSULATION:	NOMINAL	EFFECTIVE							
CEILING WITH ATTIC SPACE	xxxx	xxxx	WINDOWS & DOORS: 1						
CEILING WITHOUT ATTIC SPACE	xxxx	xxxx	WINDOWS/SLIDING GLASS DOORS	XXXX ADJUSTED TO XXX					
EXPOSED FLOOR	xxxx	xxxx	SKYLIGHTS XXXX						
WALLS ABOVE GRADE	xxxx	xxxx	MECHANICALS:						
BASEMENT WALLS	xxxx	xxxx	SPACE HEATING EQUIPMENT 2	xxxx					
SLAB (ALL > 600MM BELOW GRADE)	xxxx	xxxx	HRV EFFICIENCY (SRE% AT □°C)	xxxx					
SLAB (EDGE ONLY < OR = 600MM BELOW GRADE) XXXX XXXX		xxxx	DOMESTIC HOT WATER HEATER (EF)	xxxx					
SLAB (ALL < DR = 600MM BELOW GRADE OR HEATED)	xxxx	xxxx	DRAIN WATER HEAT RECOVERY (CSA B55.1(MIN. 42% EFFICIENCY))	XXXX # SHOWERS XXXX					
SLAD (ALL V UR - DUUMM BELUW GRADE OR HEATED)	****	****	COMBINED HEATING SYSTEM						
			1. PROVIDE U-VALUE IN EITHER W/(M2 . K) OR E	BTU/(H . FT ² . F) BUT NOT BOTH					



WWW.JASPERDESIGN.CA

279 STE. MARIE STREET COLLINGWOOD, ON. L9Y 3K6 (705) 888-6300

BCIN SIGNATURE:

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS
DESIGN, AND HAS THE QUALIFICATIONS
AND MEETS THE REQUIREMENTS SET OUT IN THE ONTARIO BUILDING CODE AS A QUALIFIED DESIGNER UNDER DIVISION C SECTION 3.2.4.

JAMES SCHNEIDER IND. BCIN# 22823

SIGNATURE:

CODE DESIGNATION:

O.B.C.

PART 9	
REVISIONS:	
DATE:	SUMMARY:

NOTES:

NOTE:
CONTRACTOR IS TO VERIFY ALL
DIMENSIONS PRIOR TO CONSTRUCTION, AND
REPORT ANY DISCREPANCIES TO JASPER

NOTE: CONTRACTOR IS RESPONSIBLE TO INSTALL ANY AND ALL REQUIRED TEMPORARY
BRACING DURING CONSTRUCTION, AND ALL
BRACING THAT MAY BE REQUIRED FOR
ROOF TRUSSES AS PER TRUSS
MANUFACTURER

DRAWINGS ARE NOT TO BE SCALED

NOTE: THE MINIMUM REQUIRED SOIL BEARING CAPACITY IS TO BE 1500 P.S.F UNLESS OTHERWISE SPECIFIED

DATE:

2020-02-27

PROJECT:

BLACKMOOR COMMUNITY CENTRE

PROJECT LOCATION:

COLLINGWOOD, ON

SCALE:

NOT TO SCALE

SHEET NO.

GENERAL NOTES STAIRS, RAMPS, HANDRAILS, AND GUARDS CONSTRUCTION SHALL BE EXECUTED AS PER DRAWINGS. NO ADDITIONS OR REVISIONS WITHOUT WRITTEN PERMISSION FROM JASPER DESIGN. · CONTRACTOR MUST CHECK AND VERIFY ALL DIMENSIONS ON THE SITE AND WITH ALL SUPPLIERS, AND REPORT ANY DISCREPANCIES OR ERRORS TO JASPER DESIGN PRIOR TO COMMENCING OF ANY WORK. - SECURE AND PAY FOR ALL PERMITS AND LICENSES AS NECESSARY FOR PROPER EXECUTION AND COMPLETION OF WORK. THE CONTRACTOR STAIR DIMENSIONS 9.8.2.1. STAIR WIDTH SHALL NOT PROCEED WITH THE WORK BEFORE OBTAINING ALL THE PERMITS IN RESPECT TO THEIR WORK. (1) EXCEPT AS PROVIDED IN SENTENCE (5), GUARDS SHALL BE DESIGNED TO RESIST THE LOADS SPECIFIED IN TABLE 9.8.8.2 - ALL WORK SHALL COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES AND REQUIREMENTS OF ALL AUTHORITIES HAVING JURISDICTION. - THE WORK SHALL COMPLY WITH ALL CONSTRUCTION SAFETY REQUIREMENTS OF THE OCCUPATIONAL HEALTH & SAFETY ACT AND THE FIRE CODE - WIDTH, MEASURED BETWEEN WALL FACES OR GUARDS, OF NOT LESS THAN 900MM (3'-0") (5) GUARDS CONSTRUCTED IN ACCORDANCE WITH THE REQUIREMENTS IN MMAH SUPPLEMENTARY STANDARD SB-7, "GUARDS FOR HOUSING AND SMALL BUILDINGS" SHALL BE DEEMED TO SATISFY THE REQUIREMENTS OF SENTENCE (1). OF ONTARIO, AS WELL AS OTHER APPLICABLE REGULATIONS OF JURISDICTION AUTHORITIES. ALL WORK SHALL BE GUARANTEED AGAINST DEFECTS OF MATERIALS AND WORKMANSHIP FOR A PERIOD AS AGREED TO BY OWNER AND (2) AT LEAST ONE STAIR BETWEEN EACH FLOOR LEVEL WITHIN A DWELLING UNIT, AND EXTERIOR STAIRS AND REQUIRED EXIT STAIRS SERVING A SINGLE SHALL HAVE A WIDTH NOT LESS THAN 860MM (2'-10"). 9.8.8.3. HEIGHT OF GUARDS (SEE APPENDIX A) WHEREVER SHOP DRAWINGS ARE CALLED FOR IN ANY SECTION, ALL WORK OF THAT SECTION SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THOSE SHOP DRAWINGS REVIEWED BY JASPER DESIGN AND/OR OWNER AND/OR ENGINEER. THESE SHALL BE COMPLETE DETAILS OF ALL CONDITIONS, CONSTRUCTION, AND INTERFACING. (3) REQUIRED EXIT STAIRS AND PUBLIC STAIRS SERVING BUILDINGS OF OTHER THAN RESIDENTIAL OCCUPANCY SHALL HAVE A WIDTH OF NOT LESS (1) Except as provided in Sentence (2) to (4), all guards shall be not less then 1070mm (3 $^{\circ}$ 6 $^{\circ}$) high GENERAL CONDITIONS OF "CANADIAN STANDARD CONSTRUCTION DOCUMENT, CCDC 2, 1994" GOVERN THE WORK OF THIS PROJECT. (2) ALL GUARDS WITHIN A DWELLING SHALL BE NOT LESS THEN 900MM (3'-0") (B) 8MM (1/2") PER PERSON BASED ON THE OCCUPANT LOAD LIMITS SPECIFIED IN TABLE 3.1.17.1L WORK NOT FULLY SPECIFIED HEREIN SHALL BE APPROVED BY THE OWNER (3) EXTERIOR GUARDS SERVING NOT MORE THEN ONE UNIT SHALL BE 900MM (3'0") WHERE WALKING SURFACE SERVED BY THE GUARD IS NO MORE THAN 1800MM CONSTRUCTION NOTES (BY O.B.C. CODE REFERENCE) 9.8.2.2. HEIGHT OVER STAIRS (1) THE CLEAR HEIGHT OVER STAIRS SHALL BE, (4) GUARDS FOR FLIGHTS OF STEPS, EXCEPT IN REQUIRED EXIT STAIRS, SHALL BE NOT LESS THAN 900MM (3'-0") HIGH. MEASURED VERTICALLY, OVER THE CLEAR WIDTH OF THE STAIR, FROM A STRAIGHT LINE TANGENT TO THE TREAD AND LANDING NOSINGS TO T LOWEST POINT ABOVE, AND (5) EXCEPT AS PROVIDED IN SENTENCE (6), THE HEIGHT OF GUARDS SHALL NOT BE LESS THAN (1) EXCEPT AS PROVIDED IN SENTENCE (2), UNREINFORCED AND NOMINALLY REINFORCED CONCRETE SHALL BE DESIGNED, MIXED, PLACED, (B) BE NOT LESS THAN, (A) 920MM (3'-1") FOR REQUIRED EXIT STAIRS, AND CURED, AND TESTED IN ACCORDANCE WITH THE REQUIREMENTS FOR "R" CLASS CONCRETE STATED IN CLAUSE 8.13 OF CSA A23.1, "CONCRETE (i) 1950mm (6'-5') For stairs serving a single family dwelling unit, and (ii) 2050mm (6'-8") For stairs not serving a single dwelling unit. (B) 1070MM (3'-6") AROUND LANDINGS. MATERIALS AND METHODS OF CONCRETE CONSTRUCTION" (6) THE HEIGHT OF GUARDS FOR EXTERIOR STAIRS AND LANDINGS MORE THAN 10M ABOVE ADJACENT GROUND LEVEL SHALL BE NOT LESS THAN 1500MM (5'-0") (2) UNREINFORCED AND NOMINALLY REINFORCED SITE-BATCHED CONCRETE SHALL BE DESIGNED, MIXED, PLACED, AND CURED IN ACCORDANCE 9.8.3. STAIR CONFIGURATIONS 9.8.3.1. STRAIGHT AND CURVED RUNS IN STAIRS (7) THE HEIGHT OF GUARDS FOR STAIRS AND LANDINGS SHALL BE MEASURED VERTICALLY FROM THE TOP OF THE GUARD TO, (A) A STRAIGHT LINE DRAWN TANGENT TO THE TREAD NOSINGS OF THE STAIR, OR (1) EXCEPT AS PROVIDED IN SENTENCE (2), STAIRS SHALL CONSIST OF 9.3.1.2. CEMENT (B) THE SURFACE OF THE LANDING. (1) CEMENT SHALL MEET THE REQUIREMENTS OF CAN/CSA-A3001 "CEMENTITIOUS MATERIALS FOR USE IN CONCRETE" (B) CURVED-RUNS. 9.10.19.1 REQUIRED SMOKE ALARMS 9.3.1.6. COMPRESSIVE STRENGTH (A) STRAIGHT-RUNS, (1) SMOKE ALARMS CONFORMING TO CAN/ULC-SS31, "SMOKE ALARMS", SHALL BE INSTALLED IN EACH DWELLING UNIT AND IN EACH SLEEPING ROOM NOT WITHIN A (1) EXCEPT AS PROVIDED ELSEWHERE IN THIS PART, THE COMPRESSIVE STRENGTH OF UNREINFORCED CONCRETE AFTER 28 DAYS SHALL BE NOT (B) CURVED-RUNS, (C) STRAIGHT-RUNS WITH WINDERS, OR (A) 32 MPA FOR GARAGE FLOOR, CARPORT FLOORS, AND ALL EXTERIOR FLATWORK (D) STRAIGHT-RUNS WITH CURVED RUNS (B) 20 MPA FOR INTERIOR FLOORS OTHER THEN THOSE FOR GARAGES AND CARPORTS, AND (1) WITHIN DWELLING UNITS, SUFFICIENT SMOKE ALARMS SHALL BE INSTALLED SO THAT, 9.8.3.3. MAXIMUM HEIGHT OF STAIRS (A) THERE IS AT LEAST ONE SMOKE ALARM INSTALLED ON EACH STOREY, INCLUDING BASEMENTS, (B) ON ANY STOREY OF A DWELLING UNIT CONTAINING SLEEPING ROOMS, A SMOKE ALARM IS INSTALLED (2) CONCRETE USED FOR GARAGE AND CARPORT FLOORS AND EXTERIOR STEPS SHALL HAVE AIR ENTRAINMENT OF 5% TO 8%. (1) THE VERTICAL HEIGHT BETWEEN ANY LANDINGS SHALL NOT EXCEED 3.7M (12-1"). (I) IN EACH SLEEPING ROOM, AND (II) IN A LOCATION BETWEEN SLEEPING ROOMS AND THE REMAINDER OF THE STOREY, AND IF THE SLEEPING ROOMS ARE SERVED BY A HALLWAY, THE SMOKE ALARM SHALL BE LOCATED IN THE HALLWAY. (SEE APPENDIX A) LUMBER AND WOOD PRODUCTS STEP DIMENSIONS 9.3.2.1. GRADE MARKING 9.8.4.1. DIMENSIONS FOR RISERS 9.10.19.5. INTERCONNECTION OF SMOKE ALARMS (1) LUMBER FOR JOISTS, RAFTERS, TRUSSES AND BEAMS, AND FOR THE USES LISTED IN TABLE 9.3.2.1. SHALL BE IDENTIFED BY A GRADE (1) THE RISE, WHICH IS MEASURED AS THE VERTICAL NOSING-TO-NOSING DISTANCE, SHALL CONFORM TO TABLE 9.8.4.1. SIGNATURE: STAMP TO INDICATE ITS GRADE AS DETERMINED BY THE NLGA, "STANDARD GRADING RULES FOR CANADIAN LUMBER" (SEE APPENDIX A (1) WHERE MORE THAN ONE SMOKE ALARM IS REQUIRED IN A DWELLING UNIT, THE SMOKE ALARMS SHALL BE WIRED SO THAT THE ACTIVATION OF ONE ALARM WILL 9.8.4.2. DIMENSIONS FOR RECTANGULAR RUNS AND TREADS (1) THE RUN, WHICH IS MEASURED AS THE HORIZONTAL NOSING-TO-NOSING DISTANCE, AND THE TREAD DEPTH OF RECTANGULAR TREADS SHALL 9.12. EXCAVATION (1) EXCEPT FOR JOISTS, RAFTERS, TRUSSES, AND BEAMS, VISUALLY GRADED LUMBER SHALL CONFORM TO THE GRADES IN TABLE 9.3.2.1. 9.4.3. DEFLECTIONS (2) THE DEPTH OF A RECTANGULAR TREAD SHALL BE NOT LESS THAN ITS RUN AND NOT MORE THAN ITS RUN PLUS 25MM (1"). 9.12.1.1. REMOVAL OF TOPSOIL AND ORGANIC MATTER 9.8.4.5. WINDERS (1) THE TOPSOIL AND VEGETABLE MATTER IN ALL UNEXCAVATED AREAS UNDER A BUILDING SHALL BE REMOVED (1) THE MAXIMUM DEFLECTION OF STRUCTURAL MEMBERS SHALL CONFORM TO TABLE 9.4.3.1. (1) STAIRS WITHIN DWELLING UNITS ARE PERMITTED TO CONTAIN WINDERS THAT CONVERGE TO A CENTRE POINT PROVIDED (2) IN LOCALITIES WHERE TERMITE INFESTATION IS KNOWN TO BE A PROBLEM, ALL STUMPS, ROOTS, AND OTHER WOOD DEBRIS SHALL BE REMOVED FROM THE SOIL TO 9.4.4. FOUNDATION CONDITIONS A) THE WINDERS TURN THROUGH AN ANGLE OF NOT MORE THAN 90° (B) INDIVIDUAL TREADS TURN THROUGH AN ANGLE OF NOT LESS THAN 30° OR NOT MORE THAN 45° , AND 9.4.4.1 ALLOWABLE BEARING PRESSURE (3) THE BOTTOM OF EVERY EXCAVATION SHALL BE FREE OF ALL ORGANIC MATERIAL (2) WHERE MORE THAN ONE SET OF WINDERS DESCRIBED IN SENTENCE (1) IS PROVIDED IN A SINGLE STAIRWAY BETWEEN ADJACENT FLOOR LEVELS, 9.12.1.2. STANDING WATER (1) FOOTING SIZES FOR SHALLOW FOUNDATIONS SHALL BE (A) DETERMINED IN ACCORDANCE WITH SECTION 9.15.. OR (B) DESIGNED IN ACCORDANCE WITH SECTION 4.2. USING, (1) EXCAVATIONS SHALL BE KEPT FREE OF STANDING WATER (I) THE MAXIMUM ALLOWABLE BEARING PRESSURES IN TABLE 9.4.4.1., OR (II) ALLOWABLE BEARING PRESSURES DETERMINED FROM SUBSURFACE INVESTIGATION 9.8.5.2. RAMP WIDTH 9.12.1.3. PROTECTION FROM FREEZING (1) EXCEPT AS PROVIDED IN SENTENCE (2), EXIT RAMPS AND PUBLIC RAMPS SERVING BUILDINGS OF RESIDENTIAL OCCUPANCY SHALL HAVE A CLEAR (1) THE BOTTOM OF EXCAVATIONS SHALL BE KEPT FROM FREEZING THROUGHOUT THE ENTIRE CONSTRUCTION PERIOD (1) WHERE A FOUNDATION BEARS ON GRAVEL, SAND OR SILT, AND THE WATER TABLE IS WITHIN A DISTANCE BELOW THE BEARING SURFAC EQUAL TO THE WIDTH OF THE FOUNDATION, THE ALLOWABLE BEARING PRESSURE SHALL BE 50% OF THAT DETERMINED IN TABLE 9.4.4.1 (2) A RAMP SERVING A SINGLE FAMILY DWELLING UNIT SHALL HAVE A WIDTH OF NOT LESS THAN 860MM (2'-10"). 9.12.2.1. EXCAVATION TO UNDISTURBED SOIL (3) EXIT RAMPS AND PUBLIC RAMPS SERVING BUILDINGS OF OTHER THAN RESIDENTIAL OCCUPANCY SHALL HAVE A CLEAR WIDTH OF NOT LESS THAN (1) EXCAVATIONS FOR FOUNDATIONS SHALL EXTEND TO UNDISTURBED SOIL 9.5.3.1. CEILING HEIGHTS OF ROOMS OR SPACES THE GREATER OF, (a) 900mm (3'-0"), OR (B) 8mm (1/2") PER PERSON BASED ON THE OCCUPANT LOAD LIMITS SPECIFIED IN TABLE 3.1.17.1.9.12.2.2. MINIMUM DEPTH OF FOUNDATIONS (1) THE CEILING HEIGHTS OF ROOMS OR SPACES IN RESIDENTIAL OCCUPANCIES AND LIVE/WORK UNITS SHALL CONFORM TO TABLE 9.5.3.1. (1) EXCEPT AS PROVIDED IN SENTENCE (4) AND (5), THE MINIMUM DEPTH OF FOUNDATIONS BELOW FINISHED GROUND LEVEL SHALL CONFORM TO TABLE 9.12.2.2. 9.5.3.2. MEZZANINES 9.8.5.3. HEIGHT OVER RAMPS (1) THE CEILING HEIGHT ABOVE AND BELOW A MEZZANINE FLOOR ASSEMBLY IN ALL OCCUPANCIES SHALL NOT BE LESS THAN 2100MM (6^L-10") (1) THE CLEAR HEIGHT OVER RAMPS SHALL BE NOT MORE THAN, (a) 1950mm (6^i - 5^i) for ramps serving a single dwelling unit, and (b) 2050mm (6^i -8) for ramps not serving a single dwelling unit 9.5.3.3. STORAGE GARAGES (1) EXECPT AS PROVIDED IN ARTICLE 9.13.3.1., WHERE THE EXTERIOR FINISHED GROUND LEVEL IS AT A HIGHER ELEVATION THAN THE GROUND LEVEL INSIDE THE FOUNDATION WALLS, EXTERIOR SURFACES OF FOUNDATION WALLS BELOW GROUND LEVEL SHALL BE DAMP PROOFED. (1) The clear height in a storage garage shall not be less than 2000mm (6^i-6^i) (2) EXCEPT AS PROVIDED IN SENTENCE (3) AND ARTICLE 9.13.3.1., FLOORS-ON-GROUND SHALL BE DAMP PRODFED 9.5.5. DINING ROOMS OR SPACES WITHIN DWELLING UNITS (1) THE SLOPE OF RAMPS SHALL BE NOT MORE THAN, (A) 1 IN 10 FOR EXTERIOR RAMPS, (B) 1 IN 10 FOR INTERIOR RAMPS SERVING RESIDENTIAL OCCU (3) FLOORS IN GARAGES, FLOORS IN UNENCLOSED PORTIONS OF BUILDINGS, AND FLOORS INSTALLED OVER GRANULAR FILL IN CONFORMANCE WITH ARTICLE 9.5.5.1. AREA OF DINING ROOMS OR SPACES 9.16.2.1. NEED NOT BE DAMP PROOFED. (C) 1 IN 6 FOR MERCANTILE OR INDUSTRIAL OCCUPANCIES, AND (1) A DINING SPACE IN COMBINATION WITH OTHER SPACE SHALL HAVE AN AREA OF NOT LESS THAN 3.25m². (D) 1 IN 8 FOR ALL OTHER OCCUPANCIES (4) DAMPPROOFING IN SENTENCE (1) IS NOT REQUIRED WHERE THE EXTERIOR SURFACES OF FOUNDATION WALLS BELOW GROUND LEVEL ARE WATERPROOFED 9.5.6. KITCHENS WITHIN DWELLING UNITS 9.13.3.1. REQUIRED WATERPROOFING (1) KITCHEN AREAS WITHIN DWELLING UNITS EITHER SEPARATE FROM, OR IN COMBINATION WITH OTHER SPACES, SHALL HAVE AN AREA OF NOT LANDINGS (A) FLOORS-ON-GROUND, AND LESS THAN 4.2M 2 INCLUDING THE AREA OCCUPIED BY THE BASE CABINETS, EXCEPT IN DWELLING UNITS CONTAINING SLEEPING ACCIFOR NOT MORE THAN TWO PERSONS, THE MINIMUM AREA SHALL BE 3.7M 2 9.8.6.2. REQUIRED LANDINGS (8) BELOW GROUND WALLS, WHERE THE EXTERIOR FINISHED GROUND LEVEL IS AT A HIGHER ELEVATION THAN THE GROUND LEVEL INSIDE THE FOUNDATION WALLS (1) EXCEPT AS PROVIDED IN SENTENCES (2) TO (4) AND SENTENCES 9.9.6.6.(2), A LANDING SHALL BE PROVIDED. 9.5.7. BEDROOMS OR SPACES IN DWELLING UNITS AND DORMITORIES (A) AT THE TOP AND BOTTOM OF EACH FLIGHT OF INTERIOR AND EXTERIOR STAIRS, INCLUDING (B) AT THE TOP AND BOTTOM OF EVERY RAMP WITH A SLOPE GREATER THAN 1 IN 50, AND (2) ROOFS OF UNDERGROUND STRUCTURES SHALL BE WATERPROOFED TO PREVENT THE ENTRY OF WATER INTO THE STRUCTURE (C) WHERE A DOORWAY OPENS ONTO A STAIR OR RAMP 9.20.9.5. TIES FOR MASONRY VENEER (1) EXCEPT AS PROVIDED IN ARTICLES 9.5.7.2. AND 9.5.7.3., BEDROOMS IN DWELLING UNITS SHALL HAVE AN AREA NOT LESS THAN 7M^2 WHERE BUILT-IN CABINETS ARE NOT PROVIDED, AND NOT LESS THAN $\mathsf{6M^2}$ WHERE BUILT-IN CABINETS ARE PROVIDED. (2) WHERE A DOOR AT THE TOP OF A STAIR IN A DWELLING UNIT SWINGS AWAY FROM THE STAIR, NO LANDING IS REQUIRED BETWEEN THE DOORWAY (1) MASONRY VENEER 70MM (2 3/4") OR MORE IN THICKNESS AND RESTING ON A BEARING SUPPORT SHALL BE TIED TO MASONRY BACK-UP OR TO WOOD FR MEMBERS WITH STRAPS THAT ARE, 9.5.7.2. AREAS OF MASTER BEDROOMS (A) CORROSION-RESISTANT. (3) A LANDING MAY BE OMITTED AT THE TOP OF AN EXTERIOR STAIR SERVING A GARAGE OR A SECONDARY ENTRANCE TO A SINGLE DWELLING UNIT, (B) NOT LESS THAN 0.76MM (1/32") THICK (1) EXCEPT AS PROVIDED IN ARTICLE 9.5.7.3., AT LEAST ONE BEDROOM IN EVERY DWELLING UNIT SHALL HAVE AN AREA OF NOT LESS THAN INCLUDING AN ENTRANCE FROM AN ATTACHED GARAGE, PROVIDED. (C) NOT LESS THAN 22MM (1") WIDE 9.8m2 WHERE BUILT-IN CABINETS ARE NOT PROVIDED, AND NOT LESS THAN 8.8m2 WHERE BUILT-IN CABINETS ARE PROVIDE (A) THE STAIR DOES NOT CONTAIN MORE THAN THREE RISERS, (D) SHAPED TO PROVIDE A KEY WITH THE MORTAR, AND (B) EXCEPT AS PROVIDED IN CLAUSE (C), THE DOOR IS A SLIDING DOOR OR SWINGS AWAY FROM THE STAIR, AND (E) SPACED IN ACCORDANCE WITH TABLE 9.20.9.5 9.5.7.3. AREAS OF COMBINATION BEDROOMS (C) WHERE A STORM OR SCREEN DOOR IS PROVIDED, IT MAY SWING OVER THE STAIR IF IT IS EQUIPPED WITH HARDWARE 9.23.3.4. NAILING OF FRAMING (1) BEDROOM SPACES IN COMBINATION WITH OTHER SPACES IN DWELLING UNITS SHALL HAVE AN AREA NOT LESS THAN $4.2 \mathrm{m}^2$ (4) A LANDING MAY BE OMITTED AT THE BOTTOM OF AN EXTERIOR STAIR OR RAMP PROVIDED THERE IS NO OBSTRUCTION, SUCH AS A GATE OR DOOR, (1) EXCEPT AS PROVIDED IN SENTENCE (2), NAILING OF FRAMING SHALL CONFORM TO TABLE 9.23.3.4. VITHIN THE LESSER OF THE WIOTH OF THE STAIR OR RAMP, OR A) 900MM (3'-0") FOR STAIRS OR RAMPS SERVING A SINGLE DWELLING UNIT, AND 9.5.9. BATHROOMS AND WATER CLOSET ROOMS (2) WHERE THE BOTTOM WALL PLATE OR SOLE PLATE OF AN EXTERIOR WALL IS NOT NAILED TO JOISTS OR BLOCKING IN CONFORMANCE WITH TABLE 9.23.3.4., THE (B) 1100mm (3'-7") FOR STAIRS OR RAMPS NOT SERVING A SINGLE DWELLING UNIT EXTERIOR WALL MAY BE FASTENED TO THE FLOOR FRAMING BY, (1) IN EVERY DWELLING LINIT, AN ENCLOSED SPACE OF SUFFICIENT SIZE SHALL BE PROVIDED TO ACCOMMODATE A WATER CLOSET, LAVATOR (A) HAVING PLYWOOD, OSB OR WAFERBOARD SHEATHING EXTEND DOWN OVER FLOOR FRAMING AND FASTENED TO THE FLOOR FRAMING BY NAILS OR STAPLES 9.8.6.3. DIMENSIONS OF LANDINGS CONFORMING TO ARTICLE 9.23.5., OR (B) TYING THE WALL FRAMING TO THE FLOOR FRAMING BY 50MM (2*) WIDE GALVANIZED-METAL STRIPS, 9.5.9.2. DOORS TO ROOMS CONTAINING WATER CLOSETS (1) EXCEPT AS PROVIDED IN SENTENCES (3) TO (6), THE WIDTH AND LENGTH OF LANDINGS SHALL COMPLY WITH TABLE 9.8.6.3. (SEE APPENDIX A) (I) NOT LESS THAN 0.41MM (1/64") IN THICKNESS (1) A DOOR SHALL BE PROVIDED TO EACH ROOM CONTAINING A WATER CLOSER WITHIN A DWELLING UNIT. (2) RESERVED (III) FASTENED AT EACH END WITH AT LEAST TWO 63MM (3") NAILS 3) WHERE THE STAIRS OR RAMPS OF DIFFERENT WIDTHS ADJOIN A SINGLE LANDING, THE MINIMUM WIDTH OF THE LANDING SHALL BE 9.23.9.1. END BEARING FOR JOISTS 9.5.11.1. DOORWAY OPENING SIZES (A) NOT LESS THAN THE GREATER REQUIRED STAIR OR RAMP WIDTH, WHERE ONE OR MORE OF THE STAIR OR RAMP WIDTHS DO NOT EXCEED THEIR (1) EXCEPT WHEN SUPPORTED ON RIBBON BOARDS, FLOOR JOISTS SHALL HAVE NOT LESS THAN 38MM (1 1/2") LENGTH OF END BEARING. (1) EXCEPT AS PROVIDED IN ARTICLES 9.5.11.3., 9.9.6.2. AND 9.9.6.3., DOORWAY OPENINGS WITHIN DWELLING UNITS SHALL BE DESIGNATION. IODATE AT LEAST THE DOOR SIZES IN TABLE 9.5.11.1. FOR SWING-TYPE DOORS OR FOLDING DOORS. (2) RIBBON BOARDS REFERRED TO IN SENTENCE (1) SHALL BE NOT LESS THAN 19MM (3/4") BY 89MM (3 1/2") LUMBER LET INTO THE STUDS 9.7. WINDOWS, DOORS, AND SKYLIGHTS (4) WHERE A DOOR SWINGS TOWARD A STAIR, THE FULL ARC OF THE SWING SHALL BE OVER THE LANDING 9.25.3. AIR BARRIER SYSTEMS 9.7.2. REQUIRED WINDOWS, DOORS, AND SKYLIGHTS (5) THE SLOPE OF LANDINGS SHALL NOT EXCEED 1 IN 5. 9.7.2.1. ENTRANCE DOORS (1) WALL, CEILING, AND FLOOR ASSEMBLIES THAT SEPARATE CONDITIONED SPACES FROM UNC (6) WHERE A DOORWAY OR STAIRWAY OPENS ONTO THE SIDE OF A RAMP, THE LANDING SHALL EXTEND FOR A DISTANCE OR NOT LESS THAN 300MM SO AS TO INCLUDE AN AIR BARRIER SYSTEM THAT WILL PROVIDE A CONTINUOUS BARRIER TO AIR LEAKAGE, (1) A DOOR SHALL BE PROVIDED AT EACH ENTRANCE TO A DWELLING UNIT (1'-0") ON EITHER SIDE OF THE DOORWAY OR STAIRWAY, EXCEPT ON A SIDE ABUTTING AN END WALL (A) FROM THE INTERIOR OF THE BUILDING INTO WALL, FLOOR, ATTIC, OR ROOF SPACES SUFFICIENT TO PREVENT EXCESSIVE MOISTURE CONDENSATION IN SUCH SPACES (A) A DOOR VIEWER OR TRANSPARENT GLAZING IN THE DOOR TO, OR 9.8.7.1. REQUIRED HANDRAILS (2) THE CONTINUITY OF THE AIR BARRIER SYSTEM SHALL EXTEND THROUGHOUT THE BASEMENT (1) EXCEPT AS PROVIDED IN SENTENCE (2) TO (4), A HANDRAIL SHALL BE INSTALLED ON STAIRS AND RAMPS IN CONFORMANCE WITH TABLE 9.8.7.1. 9.7.2.2. OTHER REQUIREMENTS FOR WINDOWS, DOORS, AND SKYLIGHTS VAPOUR BARRIERS (2) Where a stair or ramp is required to be at least 2200mm (7^{l} - 3^{l}) wide due to the occupant load, a handrail shall be installed such that no position on the stair or ramp is more than 825mm (2^{l} - 9^{l}) from a handrail. 9.25.4.1. REQUIRED BARRIER TO VAPOUR DIFFUSION (1) WINDOWS AND SKYLIGHTS INSTALLED TO PROVIDE REQUIRED NON-HEATING SEASON VENTILATION SHALL CONFORM TO ARTICLE 9.32.1 (1) THERMALLY INSULATED WALL, CEILING, AND FLOOR ASSEMBLIES SHALL BE CONSTRUCTED WITH A VAPOUR BARRIER SUFFICIENT TO PREVENT CON (3) A HANDRAIL IS NOT REQUIRED FOR STAIRS AND RAMPS SERVING A SINGLE DWELLING UNIT, WHERE, THE WALL SPACES, FLOOR SPACES, OR ATTIC OR ROOF SPACES. A) INTERIOR STAIRS HAVE NOT MORE THAN TWO RISERS, (B) EXTERIOR STAIRS HAVE NOT MORE THAN THREE RISERS, OR 9.26.4.1. REQUIRED FLASHING AT INTERSECTIONS (SEE APPENDIX A) (4) ONLY ONE HANDRAIL IS REQUIRED ON EXTERIOR STAIRS HAVING MORE THAN THREE RISERS, PROVIDED SUCH STAIRS SERVE A SINGLE DWELLING (1) EXCEPT WHERE THE OMISSION WILL NOT ADVERSELY AFFECT ADJACENT SUPPORTED OR SUPPORTING ELEMENTS, FLASHING SHALL BE INSTALLED AT JUNC BETWEEN ROOFS AND, A) WALLS THAT RISE ABOVE THE ROOF, AND 9.8.7.4. HEIGHT OF HANDRAILS (SEE APPENDIX A) (B) GUARDS THAT ARE CONNECTED TO THE ROOF BY OTHER THAN PICKETS OR POSTS (5) MINIMUM SIZES OF DOORWAYS AND DOORS WITHIN BARRIER-FREE PATH OF TRAVEL SHALL CONFORM TO SECTION 9.5. (2) FOR THE PURPOSE OF SENTENCE (1), ROOFS SHALL INCLUDE PLATFORMS THAT EFFECTIVELY SERVE AS ROOFS WITH RESPECT TO ACCUMULATION OR DRA (6) THE LOCATION AND PROTECTION OF WINDOWS, DOORS, AND SKYLIGHTS IN ORDER TO CONTROL THE SPREAD OF FIRE SHALL CONFORM TO (A) A STRAIGHT LINE DRAWN TANGENT TO THE TREAD NOSINGS OF THE STAIR SERVED BY THE HANDRAIL, OR E SURFACE OF THE RAMP, FLOOR OR LANDING SERVED BY THE HANDRA 9.26.4.3. VALLEY FLASHING (7) DOORS BETWEEN DWELLING UNITS AND ATTACHED GARAGES SHALL CONFORM TO ARTICLE 9.10.13.15. (2) EXCEPT AS PROVIDED IN SENTENCES (3) AND (4), THE HEIGHT OF HANDRAILS ON STAIRS AND RAMPS SHALL BE) NOT LESS THAN 865MM (2¹-10"), AND (1) WHERE SLOPING SURFACES OF SHINGLED ROOFS INTERSECT TO FORM A VALLEY, THE VALLEY SHALL BE FLASHED (8) THE SURFACE FLAME-SPREAD RATING FOR DOORS AND SKYLIGHTS SHALL CONFORM TO ARTICLE 9.10.17.1. (2) VALLEY FLASHING SHALL BE INSTALLED OVER CONTINUOUS SHEATHING (9) PROPERTIES OF WINDOWS AND DOORS WITHIN EXITS SHALL CONFORM TO SECTION 9.9. (3) Where guards are required, handrails required on landings shall be not more than 1070mm (3'-6") in height. (3) CLOSED VALLEYS SHALL NOT BE USED WITH RIGID SHINGLES ON SLOPES LESS THE 1 IN 1.2 (4) HANDRAILS INSTALLED IN ADDITION TO REQUIRED HANDRAILS NEED NOT COMPLY WITH SENTENCE (2). O.B.C. NOTES (1) EXCEPT AS REQUIRED IN ARTICLE 9.9.10.1. AND SENTENCE (3), THE MINIMUM WINDOW GLASS AREA FOR ROOMS IN BUILDINGS OF

RESIDENTIAL OCCUPANCY, OR ROOMS THAT ARE USED FOR SLEEPING, SHALL CONFORM TO TABLE 9.7.2.3.

WWW.JASPERDESIGN.CA

279 STE. MARIE COLLINGWOOD, ON. L9Y 3K6

BCIN SIGNATURE:

(705) 888-6300

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS DESIGN, AND HAS THE QUALIFICATIONS AND MEETS THE REQUIREMENTS SET OUT IN THE ONTARIO BUILDING CODE DIVISION C SECTION 3.2.4. IND. BCIN# 22823 JAMES SCHNEIDER

JASPER DESIGN FIRM BCIN# 101098

DATE:

CODE DESIGNATION:

PART 9 0.B.C.

REVISIONS: DATE: SUMMARY:

NOTES:

CONTRACTOR IS TO VERIFY ALL DIMENSIONS PRIOR TO CONSTRUCTION, AND REPORT ANY DISCREPANCIES TO JASPER

CONTRACTOR IS RESPONSIBLE TO INSTALL ANY AND ALL REQUIRED TEMPORARY BRACING DURING CONSTRUCTION, AND ALL BRACING THAT MAY BE REQUIRED FOR **ROOF TRUSSES AS PER TRUSS** MANUFACTURER

DRAWINGS ARE NOT TO BE SCALED

HE MINIMUM REQUIRED SOIL BEARING CAPACITY IS TO BE 1500 P.S.F UNLESS OTHERWISE SPECIFIED

DATE:

2020-02-27

PROJECT:

BLACKMOOR COMMUNITY CENTRE

PROJECT LOCATION:

COLLINGWOOD, ON

SCALE:

NOT TO SCALE

SHEET NO.