


11476 HIGHWAY 26

TOWN OF COLLINGWOOD



KEY PLAN

DRAWING LIST

Sheet Number	Drawing	Description
1	120232-TP-1	TITLE PAGE
2	120232-EC-1	EROSION CONTROL AND CONSTRUCTION COORDINATION PLAN
3	120232-SG-1	SITE GRADING PLAN
4	120232-DE-1	DETAILS AND NOTES

LEGEND

PROPERTY LINE	----
EXISTING CENTERLINE	----
PROPOSED CENTRELINE	----
EXISTING EDGE OF ASPHALT	----
PROPOSED EDGE OF ASPHALT	----
EXISTING EDGE OF SHOULDER	----
PROPOSED EDGE OF SHOULDER	----
EXISTING DITCH/DIRECTION OF FLOW	----
PROPOSED DITCH/DIRECTION OF FLOW	----
EXISTING SANITARY SEWER/SIZE/DIRECTION OF FLOW	2008 SAN
PROPOSED SANITARY SEWER/SIZE/DIRECTION OF FLOW	2008 SAN
EXISTING SANITARY SERVICE	----
PROPOSED SANITARY SERVICE	----
EXISTING SANITARY FORCEMAIN/SIZE/DIRECTION OF FLOW	2008 SAN F/M
EXISTING WATERMAIN/SIZE	1508 W/M
PROPOSED WATERMAIN/SIZE	1508 W/M
EXISTING WATER SERVICE	----
PROPOSED WATER SERVICE	----
EXISTING STORM SEWER/SIZE/DIRECTION OF FLOW	3758 STM
PROPOSED STORM SEWER/SIZE/DIRECTION OF FLOW	3758 STM
EXISTING CULVERT	----
PROPOSED CULVERT	----
PROPOSED SWALE LOCATION	----
PROPOSED JOINT HYDRO, BELL AND ROGERS	----
EXISTING GAS MAIN	----
PROPOSED GAS MAIN	----
EXISTING FENCELINE	----
PROPOSED FENCELINE	----
EXISTING BUSHLINE	----
EXISTING CONTOUR	179.00
EXISTING SPOT ELEVATION	x 179.00
PROPOSED SPOT ELEVATION	x 179.00
EXISTING GRADING DIRECTION	----
PROPOSED GRADING DIRECTION	----
PROPOSED REAR YARD OVERFLOW ROUTE	----
PROPOSED SWALE LOCATION	----
EXISTING TEMPORARY BENCHMARK	• TEM
EXISTING STANDARD IRON BAR	• SIB
EXISTING BOREHOLE/NUMBER	• BH#
EXISTING HYDRO TRANSFORMER	• HT
EXISTING CABLE PEDESTAL	• CP
EXISTING BELL PEDESTAL	• BP
EXISTING BELL MAINTENANCE HOLE	○ BELL MH
EXISTING BELL POLE	○ BP
EXISTING HYDRO POLE	○ HP
EXISTING HYDRO GUY WIRE	---
PROPOSED WALL MOUNTED LIGHT	• L
PROPOSED HYDRO PEDESTAL	• HP
PROPOSED ROGERS BOX	• RB
PROPOSED BELL PEDESTAL	• BP
PROPOSED BELL HAND WELL	• BH
EXISTING DECIDUOUS TREE	• DT
EXISTING CONIFEROUS TREE	• CT
EXISTING SANITARY MAINTENANCE HOLE/NUMBER	○ SAN MH17
PROPOSED SANITARY MAINTENANCE HOLE/NUMBER	● SAN MH17
EXISTING HYDRANT AND VALVE	• HYD & WV
PROPOSED HYDRANT AND VALVE	• HYD & WV
EXISTING WATER VALVE	• WV
PROPOSED WATER VALVE	• WV
PROPOSED CURB STOP VALVE	• CSV
EXISTING STORM MAINTENANCE HOLE	○ STM MH20
PROPOSED STORM MAINTENANCE HOLE/NUMBER	● STM MH9
EXISTING CATCH BASIN	□ CBMH 18
PROPOSED CATCH BASIN	■ CB
PROPOSED CATCH BASIN MAINTENANCE HOLE/NUMBER	○ CBMH12
PROPOSED PARKING SPACE	①



NVCA SUBMISSION

Contract No. : 120232



LEGEND

- REMOVAL AREA
- DOUBLE-WALLED WIRE BACKED HEAVY DUTY SILT FENCE AS PER NVCA BSD-23
- ENTRANCE MUD MAT
- EXISTING OVERLAND FLOW DIRECTION
- EXISTING DRAINAGE DITCH
- EXISTING TREE TO BE REMOVED
- EXISTING TREE TO REMAIN
- LIMITS OF EXISTING WETLAND
- LIMITS OF 30M WETLAND BUFFER

ADJACENT PROPERTY IMPACT NOTES:



- PRIOR TO ANY WORK BEING UNDERTAKEN, THE CONTRACTOR SHALL OBTAIN AND PAY FOR A ROAD OCCUPANCY PERMIT FROM THE TOWN. THE PERMIT SHALL BE TAKEN OUT IN THE NAME OF CONTRACTOR.
- ALL ADJACENT PROPERTIES DISTURBED BY THE CONSTRUCTION SHALL BE NOTIFIED BY LETTER DELIVERED DIRECTLY TO ADJACENT PROPERTY OWNERS.
- THE CONTRACTOR WILL PROVIDE WEEKLY CONSTRUCTION UPDATES AS THEY RELATE TO STREET CLOSURES, LARGE DELIVERIES, GARBAGE COLLECTION AND/OR ANY POTENTIAL DISTURBANCES TO THE COMMUNITY.

SILTATION AND EROSION CONTROL NOTES

- ALL SILTATION AND EROSION CONTROL WORKS TO BE IN PLACE PRIOR TO CONSTRUCTION.
- CONTRACTOR TO INSTALL AND MAINTAIN SILTATION AND EROSION CONTROL WORKS AT LOCATIONS SHOWN OR AS DIRECTED BY THE ENGINEER IF ADDITIONAL CONTROLS ARE DEEMED NECESSARY.
- CONTRACTOR TO ARRANGE PRE-CONSTRUCTION MEETING WITH ENGINEER AFTER PLACING ALL SILTATION AND EROSION CONTROL WORKS.
- THE CONTRACTOR WILL INSPECT THE SILTATION AND EROSION CONTROL MEASURES WEEKLY AND AFTER EACH SIGNIFICANT (>15mm) STORM EVENT. THE CONTRACTOR WILL NOTIFY THE ENGINEER OF CORRECTIVE ACTIONS REQUIRED AS SOON AS DEFICIENCIES ARE NOTED. HOWEVER, THE CONTRACTOR MAINTAINS ULTIMATE RESPONSIBILITY TO ENSURE PROPER SILTATION AND EROSION CONTROL MEASURES ARE IMPLEMENTED AND MAINTAINED. ALL DEFICIENCIES AND CORRECTIVE MEASURES WILL BE DOCUMENTED IN A WEEKLY INSPECTION REPORT. A COPY OF THE WEEKLY INSPECTION REPORT WILL BE PROVIDED TO THE ENGINEER.
- CONTRACTOR TO REMOVE SILTATION AND EROSION CONTROL WORKS ONLY AFTER ALL PAVING IS COMPLETED AND VEGETATION HAS TAKEN ROOT TO THE ENGINEER'S SATISFACTION.
- ALL CONSTRUCTION VEHICLES TO ACCESS THE SITE USING THE DESIGNATED CONSTRUCTION ACCESS.
- TEMPORARY ROCK FLOW CHECK DAM AND STRAW BALE FLOW CHECK DAM TO OPSD 219.180 AND 219.210 (SEE DRAWING DE-1 FOR DETAIL).
- IF CONSTRUCTION IS INTERRUPTED AND/OR INACTIVITY EXCEEDS 30 DAYS, THEN STOCKPILED, STRIPPED OR EXPOSED AREAS MUST BE STABILIZED BY HYDRO SEEDING AND ANY OTHER APPROPRIATE GEOTEXTILE MATERIAL, IF REQUIRED.

GEOTECHNICAL NOTES:



- PRIOR TO SITE WORK INVOLVING ENGINEERED FILL, A SITE MEETING TO DISCUSS ALL ASPECTS MUST BE CONVENED. THE SURVEYOR, CONTRACTOR, DESIGN ENGINEER AND GEOTECHNICAL ENGINEER MUST ATTEND THE MEETING. AT THIS MEETING, THE LIMITS OF THE ENGINEERED FILL WILL BE DEFINED. THE CONTRACTOR MUST MAKE KNOWN WHERE ALL FILL MATERIAL WILL BE OBTAINED, AND SAMPLES MUST BE PROVIDED TO THE GEOTECHNICAL ENGINEER FOR REVIEW, AND APPROVAL BEFORE FILLING BEGINS.
- THE BUILDING FOOTPRINTS AND BASE OF THE PAD, INCLUDING THE BASEMENTS, GARAGES, ETC. MUST BE DEFINED BY OFFSET STAKES THAT REMAIN IN PLACE UNTIL THE FOOTINGS AND SERVICE CONNECTIONS ARE ALL CONSTRUCTED. CONFIRMATION THAT THE FOOTINGS ARE WITHIN THE PAD, SERVICE LINES ARE IN PLACE, AND THAT THE GRADE CONFORMS TO DRAWINGS, MUST BE OBTAINED BY THE OWNER IN WRITING FROM THE SURVEYOR AND DS. WITHOUT THIS CONFIRMATION NO RESPONSIBILITY FOR THE PERFORMANCE OF THE STRUCTURE CAN BE ACCEPTED BY DS. SURVEY DRAWING OF THE PRE AND POST FILL LOCATION AND ELEVATIONS WILL ALSO BE REQUIRED.
- THE AREA MUST BE STRIPPED OF ALL TOPSOIL, FILL MATERIALS, WEATHERED/DISTURBED AND LESS COMPETENT NATIVE SOILS, TO BE CONFIRMED ON SITE DURING GRADING/EXCAVATION PROCESS. SUBGRADE MUST BE PROOF-ROLLED. SOFT SPOTS MUST BE DUG OUT. THE STRIPPED NATIVE SUBGRADE MUST BE EXAMINED AND APPROVED BY A DS ENGINEER PRIOR TO PLACEMENT OF FILL. THE APPROVED ENGINEERED FILL MUST BE COMPACTED TO 100% STANDARD PROCTOR MAXIMUM DRY DENSITY THROUGHOUT. GRANULAR FILL PREFERRED. ENGINEERED FILL SHOULD NOT BE PLACED (WHERE IT WILL SUPPORT FOOTINGS) DURING THE WINTER MONTHS. ENGINEERED FILL COMPACTED TO 100% SPMD WILL SETTLE UNDER ITS OWN WEIGHT APPROXIMATELY 0.5% OF THE FILL HEIGHT AND THE STRUCTURAL ENGINEER MUST BE AWARE OF THIS SETTLEMENT. IN ADDITION TO THE SETTLEMENT OF THE FILL, ADDITIONAL SETTLEMENT DUE TO CONSOLIDATION OF THE UNDERLYING SOILS FROM THE STRUCTURAL AND FILL LOADS WILL OCCUR.
- FULL-TIME GEOTECHNICAL INSPECTION BY DS DURING PLACEMENT OF ENGINEERED FILL IS REQUIRED. WORK CANNOT COMMENCE OR CONTINUE WITHOUT THE PRESENCE OF THE DS REPRESENTATIVE. THE FILL MUST BE PLACED SUCH THAT THE SPECIFIED GEOMETRY IS ACHIEVED. TAKE CAREFUL NOTE THAT THE PROJECTION OF THE COMPACTED PAD BEYOND THE FOOTING AT FOOTING LEVEL IS A MINIMUM OF 2 M. THE BASE OF THE COMPACTED PAD EXTENDS 2 M PLUS THE DEPTH OF EXCAVATION BEYOND THE EDGE OF THE FOOTING.
- ALL EXCAVATIONS MUST BE DONE IN ACCORDANCE WITH THE OCCUPATIONAL HEALTH AND SAFETY REGULATIONS OF ONTARIO. AFTER COMPLETION OF THE PAD, A SECOND CONTRACTOR MAY BE SELECTED TO INSTALL FOOTINGS. ALL EXCAVATIONS MUST BE BACKFILLED UNDER FULL TIME SUPERVISION BY DS TO THE SAME DEGREE AS THE ENGINEERED FILL PAD. SURFACE WATER CANNOT BE ALLOWED TO POND IN EXCAVATIONS OR TO BE TRAPPED IN CLEAR STONE BACKFILL. CLEAR STONE BACKFILL CAN ONLY BE USED WITH THE APPROVAL OF DS.
- AFTER COMPLETION OF COMPACTION, THE SURFACE OF THE PAD MUST BE PROTECTED FROM DISTURBANCE FROM TRAFFIC, RAIN AND FROST.
- IF THERE IS A DELAY IN CONSTRUCTION, THE ENGINEERED FILL PAD MUST BE INSPECTED AND ACCEPTED BY THE GEOTECHNICAL ENGINEER. THE LOCATION OF THE STRUCTURE MUST BE RECONFIRMED THAT IT REMAINS WITHIN THE PAD.



Nottawasaga Valley Conservation Authority		APR'D:	DATE: 03.06.24
TYPICAL DETAIL OF SILT/SEDIMENT FENCE		DRAWN: A.S.C	SCALE: NTS
NO.	REVISION	APR'D	DATE
BSD-23			

PERIOD	MONITORING LOCATION	PARAMETERS	MONITORING FREQUENCY	TRIGGER FOR MITIGATION	MITIGATION MEASURES/COMMENTS
Trial Dewatering	Dewatering Discharge	PWQGO Metals	Once during trial dewatering	Exceeds the PWQGO	Modify treatment method and/or shut down.
During Construction	Dewatering Discharge	PWQGO Metals	Weekly, then every four weeks after three consecutive weekly compliant samples	Exceeds the PWQGO	Modify/change treatment method and/or shut down.
		Turbidity	Daily until stable, then weekly. Minimum of five samples	Exceeds 15 NTU	
	Discharge Point	Impact Assessment	At each sampling event	Sedimentation, erosion	Reduce pumping and/or improve sediment/erosion control measures
	On-site monitoring wells	Water level meter	Every two weeks	Water level to be no more than 1 m lower than proposed depth of excavation	Reduce pumping
Post Construction	Wetland Piezometers P21 and P22	Water level	Weekly, then every four weeks after three consecutive weekly compliant samples	Water level in P21 at or below 0.1 m bgs (elevation 177.8 m asl).	LGL will be notified within 6 hours of noting water levels below the trigger limit. Mitigation measures will be discussed and approved by LGL and Tatham within 24 hours of noting water levels below the trigger limit. Potential mitigation measures could include a reduced dewatering pumping rate, the re-direction of treated dewatering discharge to feature, and/or ultimately the cessation of dewatering efforts. Tatham will provide recommendation to the dewatering contractor with 24 hours of noting water levels below the trigger limit.
	On-site monitoring wells	Water level meter	Every two weeks for four weeks, then every four weeks until 90% recovery	Water level recovery less than 90% of baseline level	Continue monitoring
Post Construction	Wetland Piezometers	Water level meter	Every two weeks for four weeks, then every four weeks until 90% recovery	Water level recovery less than 90% of baseline level	Continue monitoring

DISCLAIMER AND COPYRIGHT CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED. TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.	BENCHMARKS TBM1 — ELEVATION 179.70 T/NUT OF HYDRANT LOCATED AT SOUTHEAST SIDE OF EXISTING MOTEL ENTRANCE TBM2 — ELEVATION 179.68 T/NUT OF HYDRANT LOCATED AT THE NORTH OF JOHNSTON PARK AVENUE NORTH OF THE NORTHEAST CORNER OF THE SITE	NOTES	No.	REVISION DESCRIPTION	DATE	ENGINEER STAMP 	11476 HIGHWAY 26 TOWN OF COLLINGWOOD	EROSION CONTROL AND CONSTRUCTION COORDINATION PLAN	DESIGN: AVN/KRL	FILE: 120232	DWG:
			1.	FIRST SUBMISSION	FEB/2023				DRAWN: AVN/KRL	DATE: OCT 2022	EC-1
			2.	NVCA SUBMISSION	JUNE/2025				CHECK: KRS	SCALE: 1:500	



SG-1 A
1:500

DISCLAIMER AND COPYRIGHT CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED. TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.	BENCHMARKS TBM1 — ELEVATION 179.70 T/NUT OF HYDRANT LOCATED AT SOUTHEAST SIDE OF EXISTING MOTEL ENTRANCE TBM2 — ELEVATION 179.68 T/NUT OF HYDRANT LOCATED AT THE NORTH OF JOHNSTON PARK AVENUE NORTH OF THE NORTHEAST CORNER OF THE SITE	NOTES	No.	REVISION DESCRIPTION	DATE	ENGINEER STAMP	11476 HIGHWAY 26 TOWN OF COLLINGWOOD SITE SERVICING AND GRADING PLAN	TATHAM ENGINEERING DESIGN: AVN/KRL FILE: 120232 DRAWN: AVN/KRL DATE: OCT 2022 CHECK: KRS SCALE: 1:500 SG-1		
			1.	FIRST SUBMISSION	FEB/2023					
			2.	NVCA SUBMISSION	JUN/2025					

