

Environmental Impact Study

Part of Lot 40, Concession 8 (The Gateway Centre)

Town of Collingwood

Prepared for: Charis Developments Ltd.

Prepared by: Azimuth Environmental Consulting, Inc.

September 2024

AEC 24-153



Environmental Assessments & Approvals

September 9, 2024 AEC 24-153

Charis Developments Ltd. 186 Hurontario Street, Suite 204 Collingwood, Ontario L9Y 4T4

Attention: David Finbow

Re: Environmental Impact Study for a Proposed Development on Part of Lot 40, Concession 8 (The Gateway Centre), Town of Collingwood

Dear Mr. Finbow:

Azimuth Environmental Consulting, Inc. was retained to provide an Environmental Impact Study report for a proposed development at the location described above. The purpose of this report is to provide the Town of Collingwood, Nottawasaga Valley Conservation Authority, and other review agencies with an understanding of natural environmental conditions and potential for impacts related to the proposed development on significant natural heritage features and functions of the property and adjacent lands. This report also documents the natural environmental features present within the property and adjacent lands with regard to Species at Risk and their habitats.

Should you have any questions or require additional information please do not hesitate to contact the undersigned.

Yours truly,

AZIMUTH ENVIRONMENTAL CONSULTING, INC.

Dan Stuart, M.Env.Sc.

Ecology Lead/Partner

Roger Holmes, M.Sc.

Senior Aquatic Ecologist



Table of Contents

	i
1.0 INTRODUCTION	3
2.0 PLANNING CONTEXT	3
2.1 Provincial Planning Policy (2024)	3
2.2 Endangered Species Act, 2007	4
2.3 County of Simcoe	
2.4 Town of Collingwood	
2.5 Nottawasaga Valley Conservation Authority	
2.6 Federal Fisheries Act	6
3.0 STUDY APPROACH	6
3.1 Terms of Reference	6
3.2 Background Information	8
3.3 Vegetation Community Mapping and Surveys	
3.4 Wildlife Surveys	
3.4.1 Species at Risk	
3.4.2 Amphibian Breeding	
3.4.3 Breeding Birds	
3.5 Fish and Fish Habitat	
4.0 EXISTING CONDITIONS	10
4.1 Land Use	
4.2 Terrestrial Resources	
4.2.1 Vegetation	
4.2.2 Wildlife	
4.3 Species at Risk	
4.3.1 Butternut	
4.5 Candidate Significant Woodland	
4.6 Candidate Significant Valleyland	
4.7 Candidate Significant Wildlife Habitat	
4.8 Areas of Natural and Scientific Interest	
4.9 Fish and Fish Habitat	
5.0 NATURAL HERITAGE FEATURES AND FUNCTIONS	18
5.0 NATURAL HERITAGE FEATURES AND FUNCTIONS	
	19



7.3 Ca 7.3.1 7.4 Fis 8.0 REC 8.1 Spo 8.1.1 8.2 Mi 8.3 Sec	Little Brown Myotis, Northern Myotis, and Tri-colored Bat	21 21 21 22 22 22 22
_	erationsh and Fish Habitat	
	NCLUSIONS	
	TERENCES	
10.0 KEF	List of Figures	•••••
Figure 2:	Site Location Environmental Features Proposed Development	
	List of Tables	
Table 1: Table 2: Table 3: Table 4: Table 5:	Species at Risk Habitat Summary and Assessment Vascular Plant Species List Vegetation Community Summary Table Dawn Breeding Bird Summary Significant Wildlife Habitat Assessment	
	List of Appendices	
Appendix Appendix Appendix Appendix Appendix	B: Provincial Background and Correspondence C: NVCA Background and Correspondence D: Photographic Record E: Butternut Documentation F: 2004 Commercial Facility Drawings	
Appendix	G: Proposed Development Concept	



1.0 INTRODUCTION

Azimuth Environmental Consulting, Inc. (Azimuth) was retained by Charis Developments Ltd. (the "proponent"), to undertake an Environmental Impact Study (EIS) for a proposed development at Part of Lot 40, Concession 8 (also referred to as The Gateway Centre lands) within the Town of Collingwood (the "Town"), County of Simcoe (the "County"). A map illustrating the limits of the property in its regional context is shown on Figure 1. It is our understanding that the Town and the Nottawasaga Valley Conservation Authority (NVCA) have requested that an EIS be undertaken due to presence of mapped wetlands and the Hamilton Drain (off-property) within the study area. The study area including the proposed development footprint are mapped within the jurisdiction of the NVCA, and therefore a permit issued Ontario Regulation (O. Reg.) 41/24 under the *Conservation Authorities Act* may be required to proceed with the proposed development.

This purpose of this EIS is to identify the candidate Key Natural Heritage Features (KNHFs) present within the study area and address potential impacts to candidate KNHFs. A review of background information in combination with a detailed field program was undertaken in spring-summer 2024 to identify significant natural heritage features and functions. This report also examines potential for Species at Risk (SAR) protected under the *Endangered Species Act*, 2007 (ESA) within the study area. The potential for negative impacts to natural heritage features resulting from the proposed development is considered and recommendations for avoidance and mitigation are provided.

For the purposes of this EIS the study area comprises the approximate consolidated property boundaries ("the property") as shown on Figures 1-3 and adjacent lands (within approximately 120 metres (m)) of the property limits). Natural features in the overall planning area beyond the defined study area limits are discussed where applicable throughout this report.

2.0 PLANNING CONTEXT

2.1 Provincial Planning Policy (2024)

The Provincial Policy Statement (PPS) (MMAH, 2024) outlines policies related to natural heritage features (Section 4.1) and water resources (Section 4.2). Ontario's *Planning Act*, (1990) requires that planning decisions shall be consistent with the PPS. The study area for this assessment is located entirely within **Ecoregion 6E**. According to the PPS development and site alteration shall not be permitted in:

- Significant wetlands in Ecoregions 5E, 6E and 7E; and,
- Significant coastal wetlands.



Similarly, Section 4.1.5 of the PPS states that, unless it has been demonstrated that there will be no negative impacts on the natural features or their ecological functions, development and site alteration shall not be permitted within:

- a) significant wetlands in the Canadian Shield north of Ecoregions 5E, 6E; and 7E;
- b) significant woodlands in Ecoregions 6E; and 7E;
- c) significant valleylands in Ecoregions 6E; and 7E;
- d) significant wildlife habitat;
- e) significant areas of natural and scientific interest; and,
- f) coastal wetlands in Ecoregions 5E, 6E; and 7E that are not subject to policy 4.1.4(b).

It is ultimately the responsibility of the Province and/or the Municipality to designate areas identified within Section 4.1.4 and 4.1.5 of the PPS as "significant".

Section 4.1.6 of the PPS states that development and site alteration is not permitted in fish habitat except in accordance with federal and provincial requirements.

Section 4.1.7 of the PPS states that development and site alteration shall not be permitted in the habitat of Threatened and Endangered species, except in accordance with provincial and federal requirements.

Furthermore, under Section 4.1.8 of the PPS, no development or site alteration will be permitted on lands adjacent to natural heritage features and areas identified in policies 4.1.4, 4.1.5 and 4.1.6 unless the ecological function of the adjacent lands has been evaluated and it has been demonstrated there will be no negative impacts on the natural features and their ecological functions.

2.2 Endangered Species Act, 2007

Ontario's *Endangered Species Act*, 2007 (ESA) provides regulatory protection to Endangered and Threatened species prohibiting harassment, harm and/or killing of individuals and destruction of their habitats. Habitat is broadly characterized within the ESA as the area prescribed by a regulation as the habitat of the species or an area on which the species depends, directly or indirectly, to carry on its life processes including reproduction, rearing of young, hibernation, migration or feeding.

The various schedules of the ESA included under O. Reg. 230/08 identify SAR in Ontario. These include species listed as Extirpated, Endangered, Threatened and Special



Concern. As noted above, only species listed as Endangered and Threatened receive protection from harm and destruction to habitat on which they depend.

2.3 County of Simcoe

The County of Simcoe Official Plan ("Simcoe OP"; 2023) illustrates the property within the Settlements designation under Section 5.1 (Land Use Designations; Appendix A).

Natural features including Provincially Significant Wetland, Locally Significant Wetland, Watercourse, or Areas of Natural and Scientific Interest (ANSIs) are not shown in the vicinity of the property in Schedule 5.2.2 (Streams and Evaluated Wetlands) and Schedule 5.2.3 (Areas of Natural and Scientific Interest) of the Simcoe OP (Appendix A).

County of Simcoe Interactive Mapping (County of Simcoe, 2024) illustrates a segment of the Hamilton Drain beyond the northern property limit, approximately parallel with the northern property boundary (Appendix A), consistent with watercourse limits mapped through provincial resources (Appendix B). No Evaluated Wetlands or Unevaluated Wetlands are mapped within the study area, however a Waterbody is illustrated in the northeast portion of the property. A Woodlands unit is illustrated within 120m of the property on the west side of Hurontario Street, however a review of recent aerial imagery indicates that this unit is not present and its mapped location is currently occupied by a commercial facility (Appendix A).

2.4 Town of Collingwood

The Town of Collingwood Official Plan ("Collingwood OP"; 2018) illustrates the western and northern portions of the property as Highway Commercial, and eastern segments of the property as Residential within Schedule "A" – Land Use Plan (Appendix A).

Schedule "B" - Environmental Protection-Natural Heritage Resource Areas of the Collingwood OP (Appendix A) does not illustrate Category 1 Valleylands, Category 1 Wetlands, Category 1 Woodland, Category 2 Woodland, or Fish Spawning & Nursery Habitat associated with the property or adjacent lands (Appendix A).

The above policy review acknowledges pending updates to the Collingwood OP with the new Town of Collingwood Official Plan (2023) adopted by council but awaiting approval by the County at the time of writing. The new Collingwood OP illustrates a watercourse beyond the northern property limit, consistent with the Hamilton Drain shown on other municipal and provincial resources (Appendix A, Appendix B). No other relevant designations with regards for natural heritage features or functions are associated with the study area within the new Collingwood OP.



2.5 Nottawasaga Valley Conservation Authority

The northern portion of the study area is located within the jurisdiction of the NVCA, as illustrated in Appendix C, associated with the Hamilton Drain and its regulated area. Preliminary NVCA correspondence (Appendix C) also indicates presence of potential wetlands in the northern portions of the property. Regulated lands are subject to O. Reg. 41/24 – "Prohibited Activities, Exemptions and Permits" under the *Conservation Authorities Act*. Under O. Reg. 41/24, the NVCA may require that approvals be obtained for a proposed development or site alteration within areas regulated under the Conservation Authority's jurisdiction.

2.6 Federal Fisheries Act

The *Fisheries Act* includes protections for fish and fish habitat in the form of standards, codes of practice, and guidelines for projects near water. The *Fisheries Act* provides protection against the "death of fish, other than by fishing", (Section 34.4(1)) and the "harmful alteration, disruption or destruction of fish habitat", (Section 35(1)), otherwise known as HADD. In cases where impacts to fish and fish habitat cannot be avoided, and the project does not fall within waterbodies where Fisheries and Oceans Canada (DFO) review is not required, proponents are asked to submit a request for review to their Fish and Fish Habitat Protection Program regional office to determine approval requirements. All projects are encouraged to avoid causing the death of fish and a HADD of fish habitat, using measures to protect fish and fish habitat that include standards and codes of practice for common works, undertakings and activities.

3.0 STUDY APPROACH

3.1 Terms of Reference

A combination of a background information and field data were used to fulfill the objectives of this EIS. Azimuth undertook the following activities for this study:

- Searched the Town, County, Ministry of Natural Resources (MNR), Ministry of the Environment, Conservation and Parks (MECP), and DFO records, in addition to other available background resources (*e.g.* Ontario Breeding Bird Atlas, Ontario Reptile and Amphibian Atlas; see Section 3.2 below) to obtain available background information, including obtaining current information related to natural heritage conditions including SAR in the nearby area;
- Conducted field surveys to document existing natural heritage features, functions, and species. Surveys included:
 - Evaluated/mapped vegetation communities onsite using Ecological Land Classification methods;



- Three (3) vascular plant inventories (June 6, July 31, and August 22, 2024);
- One (1) Butternut Health Assessment (BHA) for two (2) Butternut trees on the property (August 22, 2024) and submission of one (1) BHA Report to MECP according to provincial protocols;
- Three (3) amphibian breeding surveys (April 26, May 20, and June 19, 2024);
- o Two (2) dawn breeding bird surveys (June 6 and June 27, 2024);
- One (1) aquatic habitat assessment to document fish and fish habitat features on the property (August 22, 2024);
- o Recorded all incidental wildlife observations during site visits;
- Attended one (1) wetland staking exercise with NVCA to delineate wetland boundaries (August 22, 2024);
- Completed an assessment of potential SAR and Significant Wildlife Habitat (SWH) that could be present within the study area, including (but not limited to) a screening for Butternut and Black Ash trees, and potential habitat function for Eastern Meadowlark within the study area limits;
- Assessed the potential direct and indirect impacts of the proposed development on the natural heritage features and functions identified on or adjacent to the development parcel; and,
- Reviewed the conformity of the proposed development with the applicable municipal, provincial, and federal natural heritage policy framework.

A Terms of Reference for the field program and associated review was provided to the Town (via their peer reviewer Natural Resource Solutions Inc. (NRSI)) on June 21, 2024. A response from NRSI was received with requests for additional considerations in preparing the EIS (*e.g.* two-season plant inventory, specific attention to review for Eastern Meadowlark habitat function). Azimuth was agreeable to the suggested revisions to the Terms and provided a response indicating such on July 3, 2024, to which NRSI accepted the revised Terms in a reply on July 4, 2024. A record of relevant correspondence detailed above is included in Appendix A. Notably, in addition to the agreed Terms, Azimuth elected to complete a third vascular plant survey on August 22, 2024, in addition to a review of fish habitat features and functions by a fisheries ecology specialist on the same day.

Pre-consultation with NVCA was undertaken in early spring 2024 prior to Azimuth's engagement by the proponent. In a pre-consultation letter dated April 11, 2024 (Appendix C), NVCA indicated presence of potential wetlands in the northern portion of the property and included a proposed Terms of Reference for the corresponding EIS by a qualified ecologist. Field studies included in the Terms were incorporated within the list



presented above and provided to the Town. Notably, a feature-based water balance was not undertaken as a part of this EIS under Azimuth's scope; alternatively, a Stormwater Management (SWM) report (high level), Functional Servicing Report, Geotechnical Report, and Hydrology Report for the proposed development will be prepared by others as part of the project submission package.

3.2 Background Information

A review of background documents provided information on site characteristics, habitat, wildlife, rare species and communities, and general cultural/historic aspects of the study area:

- MNR Natural Heritage Information Centre (NHIC; MNR, 2024a);
- Atlas of the Breeding Birds of Ontario (OBBA; Cadman *et al.*, 2007);
- Ontario Reptile and Amphibian Atlas (Ontario Nature, 2020);
- MECP's Species at Risk Ontario list (MECP, 2024);
- iNaturalist (NHIC) Rare Species of Ontario (iNaturalist, 2024);
- Air photos available for the Project Area (Google, VuMap);
- Government of Canada's Species at Risk Public Registry;
- Atlas of the Mammals of Ontario (Dobbyn, 1994)
- MNRF Aquatic Resource Areas Mapping (ARA; MNR, 2024b); and,
- DFO Aquatic Species at Risk Map (DFO, 2024).

3.3 Vegetation Community Mapping and Surveys

Prior to undertaking the field studies, an initial classification of vegetation communities was undertaken using recent air photo imagery for an area encompassing the study area. Vegetation community boundaries were then checked in the field on July 6, July 31, and August 22, 2024 during the growing season when the emergent ground cover vegetation layer was present. Vegetation community types were classified using ELC protocols.

A wetland site staking occurred with NVCA on August 22, 2024 to ensure wetland boundaries were delineated in accordance with ELC protocols, supported by Ontario Wetland Evaluation System (OWES; MNRF, 2022) methodology and carried out by a qualified ecologist certified by the province in OWES. Wetland boundaries were staked by a qualified surveyor (J.D. Barnes Limited) such that boundaries are illustrated on Figure 2 to a high level of accuracy.

The site visits were undertaken by qualified ecologists with existing knowledge related to rare, Threatened, and Endangered plant species with potential to occur in the area. The site assessment was focused during ELC work to ensure that appropriate effort was made



to detect any federally or provincially designated species, notably SAR as identified under the ESA. A detailed survey including a screening for Butternut (Endangered) and Black Ash (Endangered) was also conducted within the study area.

3.4 Wildlife Surveys

Wildlife species utilizing the study area were identified from direct observation, auditory signs, and through interpretation of other signs (tracks, scats, vocalizations, *etc.*) as a matter of course while conducting field surveys.

3.4.1 Species at Risk

The SAR screening undertaken for the scope of this assignment includes an assessment of SAR with potential to occur in the overall planning area, compared with potential habitat features identified within the study area. Habitat requirements and appropriate designations (Endangered, Threatened, or Special Concern) are outlined in Table 1.

3.4.2 Amphibian Breeding

Azimuth conducted three (3) evening calling amphibian surveys on April 26, May 20, and July 19, 2024 to assess amphibian breeding within and adjacent to the development parcel in accordance with the Great Lakes Marsh Monitoring Program (Bird Studies Canada, 2008) protocol. In accordance with the protocol, the amphibian surveys were completed during the period between 30 minutes after sunset and midnight, on evenings with winds Beaufort <4. The survey occurred during the early, mid-, and late- spring periods (April 15-30, May 15-31, June 15-30) on evenings with a minimum temperature of 5°C, 10°C, and 17°C respectively. The location of the survey station is illustrated on Figure 2.

Wetland and associated permanent standing water in northwest portion of the property (SAS_1 (inclusion); Figure 2) was limited to the dug pond representing the historical manmade sedimentation pond, an area occupying approximately 236m² (0.02ha). In accordance with the Significant Wildlife Habitat Technical Guide (OMNR, 2000) and accompanying the Ecoregion 6E Criteria Schedules (MNRF, 2015), candidate Amphibian Breeding Habitat (Wetland) features must exceed 500m² to be considered as potentially significant. Given the minimal extent of potentially suitable habitat for amphibian breeding, a dedicated amphibian evening breeding station was not established in proximity to this feature, however potential amphibians could be detected from the amphibian survey station illustrated on Figure 2.



3.4.3 Breeding Birds

Two (2) dawn breeding bird surveys were conducted within the study area on June 6 and June 27, 2023 guided by point count methodology presented in Appendix D of the OBBA Guide for Participants (2001). All surveys were conducted no earlier than one half hour before sunrise and were completed prior to 10:00a.m. Surveys were completed under suitable weather conditions (*i.e.* no precipitation and light winds (Beaufort wind scale \leq 3)), with an observation period of 10 minutes carried out at the point count station shown on Figure 2.

3.5 Fish and Fish Habitat

Fish and fish habitat features within the study area were evaluated on August 22, 2024. The site evaluation was intended to understand the location of watercourses and drainage features on the property, noting channel features such as wetted width, water depths, flow, bank slopes, vegetation communities, substrate material, general morphometrics, and observations of fish to determine characteristics of fish habitat and fish habitat sensitivity.

4.0 EXISTING CONDITIONS

4.1 Land Use

The property consists of pioneer and early successional vegetation communities, primarily as a result of initiating conversion of the property from agricultural lands into a commercial facility between 2007-2008 as indicated by historical aerial imagery (County of Simcoe, 2024) and available background documentation. The majority of the property comprises a large gravel pad with minor vegetation establishment, surrounded by a fringe of early successional meadow and thicket communities on the east and west sides. A historical sedimentation pond and associated linear ditch was established in the northwest portion of the property between 2007-2008 as a part of early works associated with the development. A minor wetland unit is also located in the northeast portion of the property approximately consistent with the Waterbody illustrated on the site by County of Simcoe (2024) mapping.

The northern fringe of the property is occupied by an existing residential dwelling, hedgerows, and small old-field meadow community (approx. 0.2 hectares (ha)). Lands beyond the northern property limit include the Hamilton Drain and associated naturalized corridor, which abut the northern property boundary on an east-west axis. A residential subdivision is located beyond the east property limit and a commercial facility is located west of the property, on the opposite side of Hurontario Street. Lands beyond the southern property boundary (south of Poplar Sideroad) comprise agricultural lands which appeared primarily fallow in character during the 2024 site investigations.



4.2 Terrestrial Resources

4.2.1 Vegetation

The limits of all ELC communities identified within the property are illustrated in Figure 2. A complete list of vascular plant species identified within the development parcel limits is presented in Table 2, and summary descriptions of vegetation communities within the development parcel are presented in Table 3.

Vegetation communities within the property were determined in accordance with the ELC system, are illustrated on Figure 2 and summarized as follows:

- MAMM1-2/MASM1-1a (Cattail Mineral Meadow Marsh/Cattail Mineral Shallow Marsh)
 - o with SAS_1 (Submerged Shallow Aquatic) inclusion
- MAMM1-2/MASM1-1b (Cattail Mineral Meadow Marsh/Cattail Mineral Shallow Marsh)
- SWDM2-2 (Green Ash Mineral Deciduous Swamp)
- MEGM4 (Fresh-Moist Graminoid Meadow)
 - o with FODM11 (Naturalized Deciduous Hedgerow) inclusion
- MEMM4 (Fresh-Moist Mixed Meadow)
- THDM5/MEMM4 (Fresh-Moist Deciduous Thicket/Fresh-Moist Mixed Meadow)
 - o with WODM5 (Fresh-Moist Deciduous Woodland) inclusion
- CVC_1 (Business Sector), representing pioneer vegetation on gravel pad
- CVR_4 (Rural Property), representing maintained residential dwelling and yard

None of the vegetation communities or species documented are of federal or provincial conservation concern (MNR, 2024a). A photographic record of vegetation communities and associated environmental features throughout the property limits is presented in Appendix D.

4.2.1.1 Rare and Uncommon Plants

There is are (2) of Element of Occurrence (EO_ID) within 1 kilometre (km) of the study area for provincially Endangered or Threatened, or provincially rare vegetation species according to the NHIC database (MNR, 2024a):

- Butternut (Endangered); and,
- Stiff Yellow Flax (*Linum medium var. medium*; S-Rank 2).



Two (2) Butternut trees were identified within the study area, at the locations illustrated in Figure 2. As described in Section 4.3.1 below, Butternut #001 was determined to be a hybrid upon completion of genetic testing.

No other plant species considered Endangered or Threatened (including Black Ash) were identified during the site investigation. Further, no provincially rare (S1-S3) species (including Stiff Yellow Flax) were observed during the field program.

4.2.2 Wildlife

4.2.2.1 Mammals

Direct and indirect observations of wildlife (*e.g.* tracks, scat, fur) were collected as a matter of course during the course of the field program.

Evidence of two (2) mammalian species including Gray Squirrel (direct observation) and Eastern Cottontail (direct observation) were observed throughout the course of the field program. Given the proximity of the study area to the Hamilton Drain and fallow agricultural lands south of the property, it is expected the following other mammals could conceivably be encountered within the study area: small mammal species (various mice, voles, and shrews), Eastern Chipmunk, weasel species, Virginia Opossum, Striped Skunk, Raccoon, Groundhog, Red Fox, and Coyote.

4.2.2.2 Reptiles and Amphibians (Herpetofauna)

The wetland unit in the northeast portion of the property (Wetland #2; Figure 2) represents the only feature within the study area with standing water, vernal pools/breeding pools, and/or wetland sloughs and of sufficient size to potentially render significant amphibian breeding function. As a result of the three (3) spring 2024 evening amphibian breeding surveys, the following species were detected within Wetland #2:

- Gray Treefrog (3 calling; May 20, 2024)
- Green Frog (3 calling; June 19, 2024)

No salamanders were observed within the property limits, nor would be anticipated given the minimal extent of standing water on the property and generally disturbed character of the lands. No reptiles (turtles or snakes) were observed throughout the course of the field program.

4.2.2.3 Birds

A total of 17 bird species were recorded during dawn breeding bird surveys, all of which are typical of urban/semi-urban landscapes and woodland edge habitats (Table 4). An



additional 4 bird species were identified incidentally during the remainder of the field program, also documented on Table 4.

No Eastern Meadowlark were detected throughout the study area during the dawn breeding bird survey program, or incidentally throughout the remainder of the field program.

4.2.2.4 Insects

Invertebrate species were documented as a matter of course throughout the field program, and included observations of the following:

- Monarch (*Danaus plexippus*)
- Viceroy (*Limenitis archippus*)
- Black Swallowtail (*Papilio polyxenes*)
- Cabbage White (*Pieris rapae*)
- Green Darner (*Anax junius*)

Monarch is listed as Special Concern under Ontario's ESA, and is considered in the context of Candidate SWH (Habitat for Rare and Special Concern Species) below. None of the other observed invertebrates are of provincial conservation concern (MNR, 2024a).

4.3 Species at Risk

The SAR assessment (Table 1) fully considers SAR with potential to occur in the planning area. Based on this assessment in combination with vegetation communities and other environmental features observed during the site investigation, the following species are considered below in this report:

- Threatened or Endangered: Butternut, Little Brown Myotis, Northern Myotis, Tri-colored Bat
- Special Concern: Monarch

Only species designated Threatened or Endangered receive individual and habitat protection under Section 9 and Section 10 of the ESA. Special Concern species are further discussed in the context of Candidate SWH (Habitat for Special Concern and Rare Wildlife Species) below.

4.3.1 Butternut

Two (2) Butternut trees were documented during the site investigation and was subject to a Butternut Health Assessment (BHA) in accordance with provincial guidelines (MECP,



2021) undertaken on August 22, 2024. The BHA was completed by a qualified Butternut Health Expert Dan Stuart (Ecology Lead, Azimuth). A BHA report was prepared by Dan Stuart and submitted to MECP on September 5, 2024 (Appendix E). In accordance with provincial guidelines (MECP, 2021), MECP reserves a 30-day audit period following submission of BHA reports. MECP reserves the right to initiate the audit process within 30 days of received of a BHA. Should MECP not contact Azimuth to initiate such process before October 5, 2024, tree statuses will be considered accepted by the province.

With regards for Butternut #001, a leaf sample was collected from the individual which was submitted for genetic hybrid testing on August 23, 2024. The results of genetic testing completed by the Canadian Centre for DNA Barcoding determined that the individual is a hybrid between Butternut and Japanese Walnut (*Juglans cinerea* x *Juglans ailantifolia*), as outlined in a detailed report presented in Appendix E. In accordance with provincial guidelines (MECP, 2021), Butternut hybrids are **not** subject to protections under Ontario's ESA.

The BHA confirmed the assessed Butternut #002 as a Category 1 tree, considered "non-retainable" under BHA Guidelines and **not** subject to ESA protections.

4.4 Wetlands

Provincially or locally Significant Wetlands are not located within the study area limit according to municipal (Appendix A) and provincial (Appendix B) mapping resources.

Two (2) wetlands were identified within the study area limits, verified through the wetland staking exercise that took place with NVCA on August 22, 2024, at the locations illustrated on Figure 2.

Wetland #1 (northwest feature)

The northwest Wetland #1 (Figure 2) comprises a meadow marsh/shallow marsh complex (MAMM1-2/MASM1-1a) and minor interior offline pond inclusion (SAS_1). The total feature measures 0.27ha in size, including the interior offline pond measuring $236m^2$ in area.

Wetland #1 was initially established as a sedimentation pond and connected drainage ditch as a component of early works toward the establishment of a commercial facility between 2007-2008, which was ultimately not constructed. An Erosion & Sedimentation Control Plan, Grading Plan associated with the previous development concept are available for reference in Appendix F, and the previous NVCA Permit (#2007-8832) is available in Appendix C. As illustrated on the above-referenced design drawings, the intent of the current Wetland #1 was to function as a sedimentation pond with



Hurontario Street. It is notable that the Hickenbottom Drain and evidence of the emergency spillway remain present and were identified during the site investigation. In accordance with discussions with NVCA during the wetland staking exercise on August 22, 2024, it is Azimuth's understanding that constructed sedimentation and/or stormwater management features are <u>not</u> subject to regulation under O. Reg. 41/24. The drawing package presented in Appendix F provides clear evidence of the sedimentation pond as an engineered feature for the purposes of water management, demonstrating that Wetland #1 should not be subject to NVCA Regulation.

Based on the above review, Wetland #1 should not be treated as a natural feature subject to contemplation under NVCA's regulatory framework, and is therefore not considered further in this assessment.

Wetland #2 (northeast feature)

The northwest Wetland #2 (Figure 2) comprises a meadow marsh/shallow marsh complex (MAMM1-2/MASM1-1b) with attached deciduous swamp dominated by Green Ash (*Fraxinus pennsylvanica*). The total feature measures 0.39ha in size, the marsh feature composing 0.26ha of the wetland unit and the treed swamp comprising 0.13ha of the feature. In accordance with updated provincial protocols described in the OWES Southern Manual (4th Edition, December 2022; MNRF, 2022) wetlands <0.5ha in size do not meet the minimum unit size for mapping and by extension, consideration for potential status as significant, therefore Wetland #2 is referred to as "Other Wetlands" for the purposes of this assessment.

Wetland #2 is isolated on the landscape and not directly connected to a watercourse or other drainage feature via surface flow. According to O. Reg. 41/24, a "wetland" means land that:

- (a) is seasonally or permanently covered by shallow water or has a water table close to or at its surface,
- (b) directly contributes to the hydrological function of a watershed through connection with a surface watercourse,
- (c) has hydric soils, the formation of which have been caused by the presence of abundant water, and
- (d) has vegetation dominated by hydrophytic plants or water tolerant plants, the dominance of which have been favoured by the presence of abundant water.



Based on discussions with NVCA during the wetland staking exercise on August 22, 2024, it is understood that provincial direction has clarified that isolated wetland features influenced by surface water input only should be not be interpreted as "wetland" in accordance with O. Reg. 41/24, and therefore not subject to NVCA regulation. Conversely, isolated wetland features influenced by groundwater input are to be considered "wetland" in accordance with O. Reg. 41/24 and therefore subject to NVCA regulation.

At the time of writing a groundwater study verifying presence/absence of groundwater input into Wetland #2 remains pending, therefore the status of NVCA Regulation of the feature remains unknown. It is recommended a future EIS addendum be prepared to verify the status of groundwater contribution to the feature and resulting status of NVCA regulation.

4.5 Candidate Significant Woodland

Significant Woodlands are not located within the study area limit according to municipal (Appendix A) and provincial (Appendix B) mapping resources.

Wooded areas within the study area are limited to a minor node of deciduous swamp and adjacent deciduous woodland inclusion (SWD/WODM5; Figure 2) associated with the wetland in the northeast portion of the property. The wooded unit demonstrates an average width of 20-25m (maximum width 37m) and measures approximately 0.19ha in size, below the minimum size threshold (>0.5ha) for consideration as a standalone vegetation community under the ELC system.

A series of hedgerows are also located within the northern portion of the property, connecting to off-property hedgerows associated with the Hamilton Drain and residential areas on adjacent lands. The Collingwood OP does not provide criteria for differentiation between a hedgerow and a woodland, therefore in lieu of such framework provincial guidance documents including the Natural Heritage Reference Manual (NHRM; OMNR, 2010) are utilized. The NHRM (Section 7.3.2; Delineation of Woodland Patches) suggests that for small woodlots <4ha, a minimum patch width of approximately 40m is an appropriate minimum width to differentiate a woodland from a linear hedgerow feature. In the case of wooded features within the study area, no wooded areas exceed 40m in width and therefore should not be considered of sufficient width to be considered as "woodland" in accordance with NHRM criteria.

The SWD/WODM5 feature illustrated on Figure 2 is mapped and discussed within this report to facilitate further review related to ecological features and functions (*e.g.* wetland, Candidate SWH), but should not be interpreted as meeting the definition of a



woodland in accordance with provincial criteria. No other ecological features meeting the definition of a woodland are located within the study area limits.

4.6 Candidate Significant Valleyland

No portion of the study area is identified as Significant Valleyland, nor assigned a similar designation (*e.g.* Category 1 Valleyland) on municipal (Appendix A) or provincial (Appendix B) mapping resources.

There are no valleyland features located within the property limits according standards presented in the NHRM or Collingwood OP, principally due to the lack of permanent or intermittent watercourses that constitute a defining component of a valleyland feature. The Hamilton Drain represents a municipal drainage feature on adjacent lands that does not demonstrate the well-defined valley morphology and/or landform prominence required to be considered Candidate Significant Valleyland.

4.7 Candidate Significant Wildlife Habitat

An assessment of the potential for SWH within study area was conducted, using the criteria outlined within the Significant Wildlife Habitat Technical Guide (OMNR, 2000) and the accompanying the Ecoregion 6E Criteria Schedules (MNRF, 2015). An assessment of Candidate Significant Wildlife Habitat categories relative to documented vegetation communities and habitats within the development parcel is presented in Table 5. The following Candidate SWH types were determined to be present, or have potential to be present within the study area based on the results of the field program:

- Habitat for Special Concern and Rare Wildlife Species
 - Monarch

4.8 Areas of Natural and Scientific Interest

There are no Areas of Natural and Scientific Interest located within the study area according to municipal (Appendix A), or provincial (Appendix B) mapping resources.

4.9 Fish and Fish Habitat

The property is located within the Blue Mountains subwatershed. The nearest mapped watercourse feature is the Hamilton Drain, which is located approximately 11m north of the property and flows in an easterly direction. The Hamilton Drain outlets into the Pretty River approximately 1km to the east. Pretty River is a known coldwater system that hosts species such as Brook Trout and migratory salmonids (MNR, 2024b). Hamilton Drain in proximity to the property consists of a straightened channel system with dense riparian and in-water vegetation consisting of cattails and watercress. A



concrete box culvert is located at the Hurontario Street crossing and minnows were observed upstream of this crossing within the Hamilton Drain. Given the direct connection to the Pretty River and observation of watercress, which indicates potential groundwater contributions, the Hamilton Drain is characterized as a permanent coldwater system and would be protected under the Federal *Fisheries Act*. The water depth (0.15m) and wetted channel width (1.0-1.5m) may limit direct fish use by coldwater species (*i.e.*, Brook Trout and migratory salmonids), but it is our understanding that the feature should still be managed as a coldwater system given the connection to the Pretty River downstream. No aquatic SAR are also known to occur within the Hamilton Drain as per DFO aquatic SAR mapping (DFO, 2024).

A pond feature and roadside ditch were also located on the property as shown on Figure 2. The roadside ditch was dry during the site visit, and was overgrown with cattails and terrestrial grasses. The roadside ditch outlets into the Hamilton Drain via a CSP culvert, which is perched 15cm at the outlet. No substrate sorting or defined banks were observed within the roadside ditch, and vegetation growth was dense throughout the flow path. These are indicators of an ephemeral feature and is typical for roadside drainage ditches. Therefore, the roadside ditch is not characterized as direct or indirect fish habitat and would not be protected under the Federal *Fisheries Act*.

The pond feature on the property is located at the northwest corner as shown on Figure 2. Based on aerial photographs, the pond was constructed in approximately 2007-2008 and was previously a cultivated farm field. During the site visit, a Hickenbottom outlet was located at the northwest corner of the pond and an overflow rip rap channel was present that would drain into the roadside ditch. The ditch and overflow channel were both dry during the site visit, and no pond drainage was observed. The discharge point of the Hickenbottom outlet could not be located, but it is assumed that it would also outlet to the roadside ditch if still functioning. The pond collects drainage from the property, which has been historically altered to direct drainage to lowland areas to the north and west of a large gravel/stone pad. An inlet to the pond is located at the southeast corner of the pond that would facilitate drainage during rain events, but no defined watercourse feature was located upstream of the pond. Therefore, the pond is not located along a watercourse feature and is not directly connected to a watercourse feature downstream (*i.e.*, fish cannot access the pond from the Hamilton Drain). Therefore, the pond is characterized as an offline feature and would not be protected under the Federal *Fisheries Act*.

5.0 NATURAL HERITAGE FEATURES AND FUNCTIONS

The results of Azimuth's field studies combined with review of background information indicate the potential for the following candidate KNHFs within the study area:



- Habitat for Threatened and Endangered Species
 - o Little Brown Myotis, Northern Myotis, Tri-colored Bat
- Other Wetland (Wetland #2)
- Candidate Significant Wildlife Habitat
 - o Habitat for Special Concern and Rare Wildlife Species
 - Monarch
- Fish Habitat (Hamilton Drain; Coldwater)

6.0 PROPOSED DEVELOPMENT

The proposed development involves construction of a commercial and mixed-use facility at the northeast corner of Hurontario Street and Poplar Sideroad that will occupy the entire property described throughout this report. The proposed commercial facility includes retail space such as a supermarket and restaurants, with the majority of the central portion of the property comprising a parking lot. An interior access route will link Hurontario Street with Poplar Sideroad, north of which additional retail buildings and offices are proposed (*i.e.* along the southern edge of the Hamilton Drain Trail). A mixed-use building is proposed at the northwest corner of the property.

It is anticipated that grading and/or other disturbance will take place throughout the entire property limit to facilitate the proposed commercial facility. A proposed development concept is presented in Appendix G, and overlain on environmental features mapping in Figure 3.

7.0 IMPACT ASSESSMENT

This impact assessment is prepared with regards to the limits of the proposed concept plan, as described above and illustrated in Figure 3 and presented in Appendix G.

7.1 Habitat for Threatened or Endangered Species

Impacts with regards to the ESA and Habitat of Threatened or Endangered species are covered under Section 9 and 10 of the ESA. Section 9 deals directly with killing, harming, or harassing living members of a species while Section 10 covers destruction or damage to habitat of Threatened or Endangered species. The following Threatened or Endangered species have the potential or are confirmed to occur within the limits of the study area:

- Little Brown Myotis, Northern Myotis, Tri-colored Bat
- 7.1.1 Little Brown Myotis, Northern Myotis, and Tri-colored Bat

Little Brown Myotis, Northern Myotis, and Tri-colored Bat may utilize woodlands as maternity roost sites, preferring trees >25cm DBH with evidence of cracks, holes, splits,



lifted bark, *etc*. (called "snags") to provide refuge for the rearing of young during the late spring and early summer months (approximately June). Trees of any size with suitable opportunities for bat access may also be utilized for day roosting purposes during the remainder of the active period.

The site investigation was conducted outside of the "leaf-off" period when potential access points for bats can be reviewed in detail, however Green Ash in advanced stages of decline due to Emerald Ash Borer (EAB) infestation resulted in an abundance of dead/denuded tree cover within treed areas on the property. The majority of these trees (and others on the property) were generally young in age and are unlikely to provide high quality roosting function for bats during the active season. Tree cover on the property was limited to hedgerows and the minor deciduous swamp/woodland edge (SWDM2-2/WODM5; Figure 2) unit in the northeast portion of the property, in addition to occasional scattered tree cover throughout the remainder of the site. Based on the above, it is anticipated that bat habitat cover within the property boundaries provides minimal potential bat roosting function and would be limited to opportunistic day roosting activities during the active period. The proposed development would retain similar wooded areas directly north of the property boundaries associated with the Hamilton Drain and adjacent lands, which would continue to provide potential day roosting function for bats in the post-development setting.

For projects of a similar scope, Azimuth has engaged the MECP regarding potential impacts to woodland bat habitat. Guidance was provided via the Bat Survey Standards Note (MECP, 2022), which clarifies the following:

"If a proposed activity will avoid impairing or eliminating the function of habitat for supporting bat life processes (e.g. remove, stub, etc. a small number of potential maternity or day roost trees in treed habitats) but the timing of tree removal will avoid the bat active season (April 1-September 30 in Southern Ontario)"... "then there is no need to conduct species at risk bat surveys of treed habitats."

The above is consistent with Azimuth's understanding when suitable habitat availability is not limiting, a mitigation approach that restricts vegetation removals during the active period for bats is a suitable approach to avoid a contravention to SAR bat individuals or habitats under Section 9 and Section 10 of the ESA.

Given that potential bat roosting habitat is expected to be of marginal quality and extent within the property limits, and such habitat opportunities would be retained north of the property boundary in the post-development setting, there is no expectation that the



proposed works involving removal of a small number of immature snag trees would result in a negative impact to Little Brown Myotis, Northern Myotis, Tri-colored Bat, or the habitat upon which they depend.

7.2 Other Wetland (Wetland #2)

At the time of writing a groundwater study verifying presence/absence of groundwater inputs into Wetland #2 remains pending, therefore the status of NVCA regulation of the feature remains unknown. It is recommended a future EIS addendum be prepared to verify the status of groundwater contribution to the feature and resulting status of NVCA regulation. If applicable, the EIS addendum should outline a mitigation hierarchy and associated recommendations for proposed wetland removal of 0.39ha of wetland in the context of NVCA's regulatory framework.

7.3 Candidate Significant Wildlife Habitat

According to the PPS development and site alteration are not permitted within SWH located in Ecoregion 6E, unless it can be demonstrated there will be no negative impacts upon the feature and its ecological functions. For the purposes of this assessment, Candidate SWH described below is treated as significant:

- Habitat for Special Concern and Rare Wildlife Species
 - o Monarch

7.3.1 Monarch

Monarch can generally be identified in any old-field or cultural meadow habitat, often including disturbed ditches along road right of ways. Key habitat is typically associated with tracts of old-field meadow habitat containing an abundance of Common Milkweed (*Asclepias syriaca*). Common Milkweed was identified within open areas on the property, and the species (adults; larvae or eggs not observed) was observed directly on July 31 and August 22, 2024.

Habitat for Monarch is highly represented in the general area within and beyond the study area and in the local landscape. Breeding and nectaring habitat is anticipated to remain abundant in the post-development setting, and as such no negative impact to the species or its habitat function is anticipated as a result of the proposed development.

7.4 Fish Habitat

No direct or indirect fish habitat features are located on the property that are protected under the Federal *Fisheries Act*. Therefore, no direct impacts to fish habitat are expected to occur from the proposed developed. Indirect impacts to nearby fish habitat features



(Hamilton Drain) can still occur as a result of nearby works, but can be addressed through standard erosion and sediment control measures as mentioned in Section 8.

The existing riparian vegetation directly adjacent to the Hamilton Drain is outside of the property limits and will not be altered as a result of the proposed development. This existing riparian vegetation to the north of the Hamilton Drain Trail provides valuable shading of the coldwater system. Given the width and paved surface of the Hamilton Drain Trail, which disrupts the natural riparian vegetation further south, further riparian vegetation to the south for the purposes of additional shading/buffering of the watercourse is not warranted. The retained riparian vegetation to the north should be sufficient to provide shading and cooling of the Hamilton Drain.

At this time, a detailed SWM plan has not been developed for the property, however a high level SWM has been submitted by others as a component of the application package. A detailed SWM plan will need to be developed that will outline water quality and quantity controls, particularly how discharge to the Hamilton Drian will be managed. Given the coldwater nature of the Hamilton Drain and Pretty River downstream, measures should be incorporated into the SWM design to reduce sedimentation and thermal impacts. General thermal and sediment mitigation measures have been included in Section 8 for consideration in future design phases.

8.0 RECOMMENDATIONS

8.1 Species at Risk

It should be noted that the absence of a protected species within the study area does not indicate that they will never occur within the area. Given the dynamic character of the natural environment, there is a constant variation in habitat use. Care should be taken in the interpretation of presence of species of concern including those listed under the ESA. Changes to policy, or the natural environment, could result in shifts, removal, or addition of new areas to the list of areas currently considered candidate KNHFs. This report is intended as a point in time assessment of the potential to impact SAR; not to provide long term "clearance" for SAR. While there is no expectation that the assessment should change significantly, it is the responsibility of the proponent to ensure that they are not in contravention of the ESA at the time that site works are undertaken. A review of the assessment provided in this report by a qualified person should be sufficient to provide appropriate advice at the time of the onset of future site works.

8.1.1 Worker Training

Worker training would assist the on-site workers in the identification of the SAR with potential to occur in the area. Workers should be instructed to stop work and contact the



MECP immediately if any SAR are encountered within the work area. Individuals working on site should ensure that SAR are not harmed during construction or killed by heavy machinery, vehicles or other equipment.

The contractor should educate all site personnel to ensure that, if identified, the SAR are not wantonly injured or killed, and to ensure that damage to features which could constitute habitat is avoided. Information should be conveyed through a SAR expert and include:

- Species habitat and identification;
- Requirements under the ESA including avoidance of harm to the species and damage to relevant habitat;
- Appropriate action to take if the species is encountered;
- How to record sightings and encounters; and,
- That care should be taken when undertaking construction activities in order to avoid harming the species or damaging/destroying habitat.

The expert should be a qualified biologist who specializes in ecology/biology, or SAR.

8.2 Migratory Breeding Birds and Bats

Activities involving the removal of vegetation should be restricted from occurring during the breeding season. Migratory birds, nests, and eggs are protected by the *Migratory Birds Convention Act*, 1994 (MBCA) and the *Fish and Wildlife Conservation Act*, 1997 (FWCA). Environment Canada outlines dates when activities in any region have potential to impact nests at the Environment Canada Website (https://www.canada.ca/en/environment-climate-change/services/avoiding-harm-migratory-birds/general-nesting-periods/nesting-periods.html). In Zones C1 and C2 vegetation clearing should be avoided between **April 1 through August 31** of any given year. If work requires that vegetation clearing is required between these dates screening by an ecologist with knowledge of bird species present in the area could be undertaken to ensure that the vegetation has been confirmed to be free of nests prior to clearing.

Activities involving tree removal, particularly within wooded area on the property, should be avoided between **April 1 through September 30** of any given year, during the active period for bat species that may utilities trees for maternity and day roosting purposes. It is anticipated that adherence to this timing restriction will avoid impacts to individual SAR bats, therefore remaining in compliance with Section 9 of the ESA affording individual protection to Endangered species.



8.3 Sediment and Erosion Controls

Diligent application of ESCs is recommended for all future construction activities to minimize the extent of accidental or unavoidable impacts to adjacent vegetation communities, wildlife habitat and fish habitat. Prior to the commencement of site works, silt fencing should be applied along the length of directly adjacent natural or naturalized features, and routine inspection/maintenance of the silt fencing should occur throughout construction. It is recommended that ESCs be maintained until vegetation is reestablished post-construction.

Materials storage on the property (*i.e.* soil stockpiles) should be located over 30m from natural features where feasible. Material storage areas should be contained with ESCs to avoid potential indirect impacts to natural features onsite.

8.4 Operations

All maintenance activities (including refueling) required during future construction should be conducted at least 30m away from natural features to prevent accidental spillage of deleterious substances that may harm natural environments.

The contractor is recommended to have a Contaminant and Spill Management Plan in place prior to initiation of works. This should include keeping an emergency spill kit on site at all times. In the event of a spill, the contractor must report it immediately to the provincial Spills Action Centre (SAC).

8.5 Fish and Fish Habitat

As specified above, construction activities occurring on the property should have regard for nearby fish habitat features and utilize Best Management Practices (BMPs) during construction as follows:

- All ESC measures are to be installed prior to any ground disturbance, and shall be maintained until all disturbed soils have been restored and stabilized following construction;
- All dewatering is to discharge into a filter bag (i.e. envirobag or equivalent).
 Filter bags should be placed a minimum of 30m from fish habitat on stable, vegetated ground to allow fines to settle out of the water. Monitoring of dewatering operations should occur throughout the construction process to ensure water is free of fines before entering the watercourses and that dewatering operations do not erode sloped areas;
- All site disturbance should be minimized to the extent possible;



- All machinery maintenance/refueling is recommended to maintain a minimum distance of 30m from fish habitat to prevent accidental spillage of deleterious substances into natural areas; and,
- Disposal of material should occur in a timely fashion to minimize risk of entry into the watercourse.

Details on SWM design are unknown at this time and will need to be assessed once the design has been advanced, which can be incorporated into a future EIS addendum. Measures should be incorporated into the SWM design to reduce sedimentation and thermal impacts on the receiving watercourse. Stormwater runoff can be warmed significantly as it drains off warm pavement. Design considerations can include, but not be limited to:

- Incorporate Low Impact Development (LID) features within the site to address pollutants directly at the source and treats small, frequent rainfall events to reduce the volume of water in the holding tanks;
- Riparian plantings along drainage and outlet channels to shade water and reduce surface water temperatures;
- Install cooling trenches and/or lengthen the outlet channel if possible to increase the shading potential, reduce flows during storm events, and allow sediment to settle; and,
- Install an energy dissipation device at the outlet to reduce flows rates and potential scouring at the receiving channel outlet location.

9.0 CONCLUSIONS

Based upon our analysis, it is concluded that subject to the incorporation of the environmental protection measures and criteria described throughout this report, the proposed development is not anticipated to result in a negative impact upon KNHFs or their ecological functions. At this time, our findings are summarized as follows:

- The proposed development is consistent with the applicable natural heritage policies of the Provincial Policy Statement, ESA, Town of Collingwood Official Plan, and County of Simcoe Official Plan.
- Our impact assessment has given full consideration to the habitat requirements of all SAR assumed and documented to occur in the area and results indicate the proposed site development will not result in negative direct or indirect impacts to habitat of SAR providing conformance is demonstrated to mitigation measures described in Section 8.



- The proposed works are not expected to negatively impact the ecological functions of the Candidate Significant Wildlife Habitat outlined in Section 5 if the appropriate mitigation measures outlined in Section 8 are followed.
- It is recommended a future EIS addendum be prepared to verify the status of groundwater contribution to Wetland #2 and resulting status of NVCA regulation. If applicable, the EIS addendum should outline a mitigation hierarchy and associated recommendations for proposed removal of 0.39ha of wetland in the context of NVCA's regulatory framework. It is anticipated that resolving the above will ensure the proposed development occurs in a manner compliant with O. Reg. 41/24 under the *Conservation Authorities Act*.
- No ephemeral, intermittent or permanent drainage/watercourse features or their associated fish habitat are expected to be negatively impacted as a result of the proposed works if the appropriate mitigation measures described in Section 8 are followed during construction.



10.0REFERENCES

Bird Studies Canada. 2008. Marsh Monitoring Program Participant's Handbook for Surveying Amphibians. Bird Studies Canada, Environment Canada - Canadian Wildlife Service, U.S. Environmental Protection Agency. 16 pp.

Cadman, M.D., D.A. Sutherland, G.G. Beck, D. Lepage, and A.R. Couturier (eds.). 2007. Atlas of the Breeding Birds of Ontario (OBBA). 2001-2005. Bird Studies Canada, Environment Canada, Ontario Field Ornithologies, Ontario Ministry of Natural Resources and Ontario Nature, Toronto, xxii + 706pp.

County of Simcoe Official Plan.

County of Simcoe. 2024. Interactive Map - County of Simcoe (GIS). (https://opengis.simcoe.ca/). Accessed August 2024.

Dobbyn, J. 1994. Atlas of the Mammals of Ontario. Federation of Ontario Naturalists.

Endangered Species Act, Ontario. 2007. An Act to protect species at risk and to make related changes to other Acts. Bill 184 Chapter 6, Statutes of Ontario 2007.

Fish and Wildlife Conservation Act, Ontario. 1997. S.O. 1997, c.41.

Fisheries and Oceans Canada (DFO). 2024. Aquatic Species at Risk Map. (https://www.dfo-mpo.gc.ca/species-especes/sara-lep/map-carte/index-eng.html). Accessed August 2024.

Government of Canada. 1985. Federal Fisheries Act. Available at: (http://lawslois.justice.gc.ca/eng/acts/f-14/). Accessed August 2024.

Government of Canada. 2014. Migratory Birds Convention Act. Available at (http://lawslois.justice.gc.ca/eng/acts/M-7.01/). Accessed August 2024.

Government of Canada. 2024. List of Wildlife Species at Risk. Available at: (https://www.canada.ca/en/environment-climate-change/services/species-risk-act-accord-funding/listing-process.html). Accessed August 2024.

iNaturalist. 2024. (NHIC) Rare Species of Ontario. (https://www.inaturalist.org/projects/nhic-rare-species-of-ontario). Accessed August 2024.



Lee, H.T., W.D. Bakowsky, J. Riley, J. Bowles, M. Puddister, P. Uhlig and S. McMurray. 1998. Ecological Land Classification for Southern Ontario. First Approximation and its Application. Ontario Ministry of Natural Resources, Southcentral Sciences Section, Science Development and Transfer Branch. SCSS Field Guide FG-02.

Lee, H.T. 2008. SOnt_ELC_Ecosystem_Table_Dec_2008. [Unpublished].

Ministry of the Environment, Conservation and Parks (MECP). 2021. Butternut Health Assessment Guidelines: Assessment of Butternut Tree Health for the Purposes of the *Endangered Species Act*, 2007. December 2021. Queen's Printer for Ontario. 19 pp.

Ministry of the Environment, Conservation and Parks (MECP). 2022. Bat Survey Standards Note 2022. 2 pp.

Ministry of the Environment, Conservation and Parks (MECP). 2024. Species at Risk in Ontario List. (https://www.ontario.ca/page/species-risk) Accessed August 2024.

Ministry of Municipal Affairs and Housing (MMAH). 2024. Provincial Policy Statement.

Ministry of Natural Resources (MNR). 2024a. Natural Heritage Information Centre. (https://www.ontario.ca/page/natural-heritage-information-centre). Accessed August 2024.

Ministry of Natural Resources (MNR). 2024b. Ontario Geohub: Aquatic Resource Area Survey Point online database. (https://geohub.lio.gov.on.ca/datasets/aquatic-resource-area-line-segment/about). Accessed September 2024.

Ministry of Natural Resources and Forestry (MNRF). 2015. Significant Wildlife Habitat Criteria Schedules for Ecoregion 6E. 39pp.

Ministry of Natural Resources and Forestry (MNRF). 2022. Ontario Wetland Evaluation System: Southern Manual. 4th Edition, King's Printer for Ontario. vi. + 239 pp.

Ontario Conservation Authorities Act. (1990). (https://www.ontario.ca/laws/statute/90c27). Accessed September 2024.

Ontario Ministry of Natural Resources (OMNR). 2000. Significant Wildlife Habitat Technical Guide. Fish and Wildlife Branch, Wildlife Section, Science Development and Transfer Branch, Southcentral Science Section. Queen's Printer for Ontario. 151 pp.




Ontario Ministry of Natural Resources and Forestry (OMNR). 2010. Natural Heritage Reference Manual for Natural Heritage Policies of the Provincial Policy Statement, 2005. Second Edition. Toronto: Queen's Printer for Ontario. 248 pp.


Ontario Nature. 2020. Ontario Reptile and Amphibian Atlas.


Ontario Planning Act. (1990). (https://www.ontario.ca/laws/statute/90p13). Accessed September 2024.

Town of Collingwood. 2019. Town of Collingwood Official Plan.

Town of Collingwood. 2023. Official Plan Update (http://engage.collingwood.ca/official-plan). Accessed September 2024.







Common Name	Species Name	ESA	SARA	Key Habitats Used By Species ¹	Initial Assessment
Bald Eagle	Haliaeetus leucocephalus	SC	Not at Risk	Occupies a variety of habitats and forest types, but prefers sites in the vicinity of a major lake or river for hunting. Nests occur in large trees (e.g. pine, poplar) typically adjacent to large bodies of water (MECP, 2024). ESA Protection: N/A	Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.
Bank Swallow	Riparia riparia	THR	THR	Nests in burrows excavated in natural and human-made settings with vertical sand and silt faces. Commonly found in sand or gravel pits, road cuts, lakeshore bluffs, and along riverbanks (COSEWIC, 2013a). ESA Protection: Species and general habitat protection	No excavated vertical features, sand or gravel pits providing potential nesting habitat. Species not observed during the dawn breeding bird survey program, or incidentally throungout the course of the field program.
Barn Swallow	Hirundo rustica	SC	THR	Ledges and walls of man-made structures such as buildings, barns, boathouses, garages, culverts and bridges. Also nest in caves, holes, crevices and cliff ledges (COSEWIC, 2011a). ESA Protection: N/A	Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.
Black Ash	Fraxinus nigra	END	END	Facultative wetland tree species frequently found in floodplain forests, swamps, seepage areas, shoreline margins and fens. Occupied sites are generally seasonally-flooded (COSEWIC, 2018a). ESA Protection: Species and general habitat protection	Species was not observed during the vascular plant inventory.
Black Tern	Chlidonias niger	SC	No status	Colonial nesters typically found within marshes. Its preferred nesting habitat is a hemi-marsh (<i>i.e.</i> a wetland with 50:50 open water and emergent vegetation). Nests are usually built on an upturned cattail root, floating vegetation mat or patch of mud (Cadman <i>et al.</i> , 2007). ESA Protection: N/A	Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.
Bobolink	Dolichonyx oryzivorus	THR	No Status	Nests primarily in forage crops (e.g. hayfields and pastures) dominated by a variety of species such as clover, Timothy, Kentucky Bluegrass, tall grass, and broadleaved plants. Also occurs in wet prairie, graminoid peatlands, and abandoned fields dominated by tall grasses. Does not generally occupy fields of row crops (e.g. corn, soybeans, wheat) or short-grass prairie. Sensitive to habitat size and has lower reproductive success in small habitat fragments (COSEWIC, 2010a). ESA Protection: Species and general habitat protection	Grassland/meadow habitats hightly limited in size, and not considered sufficient to provide breeding/nesting potential for the species. Gravel pad area in central portion of property does not comrpise "old-field" conditions with developed thatch later that would be considered suitable fo the species. Species not observed during the dawn breeding bird survey program, or incidentally throuhgout the course of the field program.
Butternut	Juglans cinerea	END	END	Commonly found in riparian habitats, but is also found in rich, moist, well-drained loams, and well-drained gravels. Butternut is intolerant of shade (COSEWIC, 2003). ESA Protection: Species and general habitat protection	Local NHIC records occur within 1km of the study area for Butternut. Two (2) Butternut trees observed during the vascular plant inventory, noting Butternut #001 (Figure 2) was determined to be a hybrid upon genetic testing (refer to Section 4.3.1 for additional discussion).
Canada Warbler	Cardellina canadensis	SC	THR	Wet, mixed deciduous-coniferous forests with a well developed shrub layer. Shrub marshes, Red-Maple stands, cedar stands, Black Spruce swamps, larch and riparian woodlands along rivers and lakes (COSEWIC, 2008a). ESA Protection: N/A	Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.
Cerulean Warbler	Dendroica cerulea	THR	END	Associated with large tracts of mature deciduous forest with tall trees and an open understory. Found in both wet bottomland forests and upland areas (COSEWIC, 2010b). ESA Protection: Species and general habitat protection	Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.
Chimney Swift	Chaetura pelagica	THR	THR	Nests primarily in chimneys though some populations (<i>i.e.</i> in rural northern areas) may nest in cavity trees (COSEWIC, 2007a). Recent changes in chimney design may be a significant factor in recent declines in numbers (Cadman <i>et al.</i> , 2007). ESA Protection: Species and general habitat protection	No suitable chimney structures located within the study area. Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.
Common Nighthawk	Chordeiles minor	SC	SC	Open habitats including sand dunes, beaches recently logged/burned over areas, forest clearings, short grass prairies, pastures, open forests, bogs, marshes, lakeshores, gravel roads, mine tailings, quarries, and other open relatively clear areas (COSEWIC, 2018b). Microhabitat requirements for nesting include open, dry areas that will not overheat and provide shelter from the sun and predators. In urban areas, the species nests almost exclusively on roofs covered with pea gravel that have adjacent sources of shade (e.g. parapet)(COSEWIC, 2018b). ESA Protection: N/A	Species not observed incidentally during evening amphibian breeding surveys. Although the central portion of the property is occupied by a gravel pad, the site does not provide the necessary microhabitat conditions (i.e. pea gravel with nearby shaded areas for concealment from sun and predators) necessary for species' life functions. Study area is not consistent with typically suitable urban habitat conditions, comprising gravel roofs with built shaded features.
Eastern Meadowlark	Sturnella magna	THR	THR	Most common in grassland, pastures, savannahs, as well as anthropogenic grassland habitats, including hayfields, weedy meadows, young orchards, golf courses, restored surface mines, etc. Occasionally nest in row crop fields such as corn and soybean, but there are considered low-quality habitat. Large tracts of grassland are preferred over smaller fragments and the minimum area required is estimated at 5ha (COSEWIC, 2011b). ESA Protection: Species and general habitat protection	Local NHIC records occur within 1km of the study area for Eastern Meadowlark. Grassland/meadow habitats hightly limited in size, and not considered sufficient to provide breeding/nesting potential for the species. Gravel pad area in central portion of property does not comrpise "old-field" conditions with developed thatch later that would be considered suitable fo the species. Species not observed during the dawn breeding bird survey program, or incidentally throuhgout the course of the field program.
Eastern Small-footed Myotis	Myotis Lleibii	END	END	Generally occurs in mountainous or rocky regions, on the face of rock bluffs and beneath slabs of rock and stones. Hibernation is typically confined to caves and old mines (Best and Jennings, 1997). ESA Protection: Species and general habitat protection	No rock bluffs, rock slabs, large stones, rock fencelines, or similar habitats located within the property limits. No caves, abandoned mines, or similar features located within the study area limits. No suitable habitat for the spcies.

Table 1 (AEC24-153)

Common Name	Species Name	ESA	SARA	Key Habitats Used By Species ¹	Initial Assessment
Eastern Whip-poor-will	Antrostomus vociferus	THR	THR	Semi-open forests or patchy forests with clearings, such as barrens or forests that are regenerating following major disturbances, are preferred nesting habitats (COSEWIC, 2009a). ESA Protection: Species and general habitat protection	Semi-open patchy forests typical of those occupied by the species not located within the study area limits. Species is also not expected to occur in an urbanized setting. No suitable habitat for the species.
Eastern Wood-pewee	Contopus virens	SC	SC	Mostly in mature and intermediate-age deciduous and mixed forests having an open understory. It is often associated with forests dominated by Sugar Maple and oak. Usually associated with forest clearings and edges within the vicinity of its nest (COSEWIC, 2012a).	Local NHIC records occur within 1km of the study area for Eastern Wood-pewee.
	Compas vicis			ESA Protection: N/A	Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.
Golden-winged Warbler	Vermivora chrysoptera	SC	THR	Areas of early successional scrub surrounded by mature forests including dry uplands, swamp forests, and marshes (COSEWIC, 2006). ESA Protection: N/A	Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.
Grasshopper Sparrow pratensis subspecies	Ammodramus savannarum pratensis	SC	SC	Typically breeds in large human-created grasslands (≥5 ha), such as pastures and hayfields, and natural prairies, such as alvars, characterized by well-drained, often poor soil dominated by low, sparse perennial herbaceous vegetation (COSEWIC, 2013b). ESA Protection: N/A	Grassland/meadow habitats hightly limited in size, and not considered sufficient to provide breeding/nesting potential for the species. Gravel pad area in central portion of property does not comrpise "old-field" conditions with developed thatch later that would be considered suitable fo the species. Species not observed during the dawn breeding bird survey program, or incidentally throuhgout the course of the field program.
Least Bittern	Ixobrychus exilis	THR	THR	Breed strictly in marshes of emergents (usually cattails) that have relatively stable water levels and interspersed areas of open water (COSEWIC, 2009b). ESA Protection: Species and general habitat protection	Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.
Little Brown Myotis	Myotis lucifugus	END	END	Forests and regularly aging human structures as maternity roost sites. Regularly associated with attics of older buildings and barns for summer maternity roost colonies. Overwintering sites are characteristically mines or caves (MNRF, 2014) (COSEWIC, 2013c). ESA Protection: Species and general habitat protection	Wooded areas consist of several linear hedgerows, not typical of woodland features utilized by the species for maternity roosting purposes. Residences and commercial buildings within the study area are relatively newly-built and well maintained, and are not anticipated to provide maternity roosting opportunities. Trees associated with hedgerows throughout the study area may provide marginal day roosting function for bats throughout the active period. No caves or abandoned mines that could provide suitable
Monarch	Danaus plexippus	SC	SC	Breeding habitat is confined to sites where milkweeds, the sole food of caterpillars, grow. Milkweeds grow in a variety of environments, including meadows in farmlands, along roadsides and in ditches, open wetlands, dry sandy areas, short and tall grass prairie, river banks, irrigation ditches, arid valleys, and south-facing hills (COSEWIC, 2010c). ESA Protection: N/A	overwintering habitat located within the study area limits. Species was observed on the property during the field program. Milkweed (<i>Asclepias spp.</i>), a critical component of the speceis' life history, was documented within open portions of the property.
Northern Myotis	Myotis septentrionalis	END	END	Maternity roost sites are generally located within deciduous and mixed forests and focused in snags including loose bark and cavities of trees. Overwintering sites are characteristically mines or caves (COSEWIC, 2013b). ESA Protection: Species and general habitat protection	Wooded areas consist of several linear hedgerows, not typical of woodland features utilized by the species for maternity roosting purposes. Trees associated with hedgerows throughout the study area may provide marginal day roosting function for bats throughout the active period. No caves or abandoned mines that could provide suitable overwintering habitat located within the study area limits.
Red-headed Woodpecker	Melanerpes erythrocephalus	END	END	Occurs in open deciduous forests, particularly those dominated by oak and beech, groves of dead trees, floodplain forests, orchards, cemeteries, savannas and savanna-like grasslands. Although the species occupies a range of habitat types, key habitat is characteristically composed of woodlands where tall trees are of large crcumference (<i>i.e.</i> mature cover) and are at a low density. A high density of snag trees is also an indicator of key habitat types (COSEWIC, 2007b). ESA Protection: Species and general habitat protection	Open deciduous forests dominated by oak and beech, not located within the study area limits; wooded areas consist of hedgerows comrpising immature to mid-aged tree cover that would not be expected to provide suitable breeding and nesting opportunities for the species. Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.
Snapping Turtle	Chelydra serpentina	SC	SC	Habitat is characterized by slow-moving water with a soft mud bottom and dense aquatic vegetation. Often located in ponds, sloughs, shallow bays or river edges and slow streams, or areas combining several of these wetland habitats (COSEWIC, 2008b). ESA Protection: N/A	Local NHIC records occur within 1km of the study area for Snapping Turtle; species was not observed throughout the course of the field program. Wetlands and drainage features within the study area contain minimal standing water, limited to a partially-naturalized created sedimentation pond approximatley 236m2 in size that would not be expected to provide suitable foraging opportunities for the species. Further, wetlands on the property are isolated and would not be anticipated to provide wildlife conveyance opportunities for the species. The sedimentation pond was dug to shallow depth (approx. 20cm) and is not anticipated to meet the necessary size and/or depth requirements to provide suitable overwintering habitat function for the species. No areas with potential to function as turtle nesting areas were identified within the study area throughout the course of the field program.
Tri-colored Bat	Perimyotis subflavus	END	END	Maternity roost sites include forests and modified landscapes (barns or human-made structures). Overwintering sites include mines and caves (COSEWIC, 2013b). ESA Protection: Species and general habitat protection	Wooded areas consist of several linear hedgerows, not typical of woodland features utilized by the species for maternity roosting purposes. Residences and commercial buildings within the study area are relatively newly-built and well maintained, and are not anticipated to provide maternity roosting opportunities. Trees associated with hedgerows throughout the study area may provide marginal day roosting function for bats throughout the active period. No caves or abandoned mines that could provide suitable overwintering habitat located within the study area limits.

Table 1 (AEC24-153)

Common Name	Species Name	ne ESA SARA Key Habitats Used By Species ¹		Initial Assessment	
Wood Thrush	Hylocichla mustelina	SC	THE	Found in moist, deciduous hardwood or mixed stands, often previously disturbed, with a dense deciduous undergrowth and with tall trees for singing perches (COSEWIC, 2012b). ESA Protection: N/A	Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.
Yellow Rail	Coturnicops noveboracensis	SC	SC	Nest in wet marshy areas of short grass-like vegetation. The habitat must remain wet throughout the breeding season (COSEWIC, 2009c). ESA Protection: N/A	Species not observed during the dawn breeding bird survey program, or incidentally throughout the course of the field program.

Habitat as outlined within the MECP's Species at Risk in Ontario website files (https://www.ontario.ca/page/species-risk-ontario), or Species Specific COSEWIC Reports referenced in this document. Best, T., and J. Jennings. 1997. Mammalian Species, Myotis leibii. The American Society of Mammalogists. No. 547, pp. 1-6, 5 figs.

Cadman, M., D. Sutherland, G. Beck, D. Lepage and A. Couturier. 2007. Atlas of the Breeding Birds of Ontario 2001-2005. Bird Studies Canada, Environment Canada, Ontario Field

COSEWIC 2003. COSEWIC assessment and status report on the Butternut Juglans cinerea in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vii + 32 pp.

COSEWIC 2006. COSEWIC assessment and status report on the Golden-winged Warbler Vermivora chrysoptera in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vii + 30 pp.

COSEWIC. 2007a. COSEWIC assessment and update status report on the Chimney Swift Chaetura pelagic a in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vii + 49 pp.

COSEWIC . 2007b. COSEWIC assessment and status report on the Red-headed Woodpecker Melanerpes erythrocephalus in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vi + 27 pp.

COSEWIC. 2007c. COSEWIC assessment and update status report on the Redside Dace Clinostomus elongates in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vii + 59 pp.

COSEWIC. 2008a. COSEWIC assessment and status report on the Canada Warbler Wilsonia Canadensis in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vi + 35 pp. COSEWIC . 2008b. COSEWIC assessment and status report on the Snapping Turtle Chelydra serpentina in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vii + 47 pp.

COSEWIC. 2009a. COSEWIC assessment and update status report on the Whip-poor-will Caprimulgus vociferus in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vi + 28 pp.

COSEWIC. 2009b. COSEWIC assessment and update status report on the Least Bittern Ixobrychus exilis in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vi + 36 pp.

COSEWIC 2009c, COSEWIC assessment and status report on the Yellow Rail Coturnicops noveboracensis in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vii + 32 pp.

COSEWIC. 2010a. COSEWIC assessment and update status report on the Bobolink Dolichonyx oryzivorus in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vi + 42 pp.

COSEWIC . 2010b. COSEWIC assessment and update status report on the Cerulean Warbler Dendroica cerulea in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. x + 40 pp. COSEWIC . 2010c. COSEWIC assessment and status report on the Monarch Danaus plexippus in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. vii + 43 pp.

COSEWIC. 2011a. COSEWIC assessment and update status report on the Barn Swallow Hirundo rustica in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. ix + 37 pp.

COSEWIC. 2011b. COSEWIC assessment and update status report on the Eastern Meadowlark *Sturnella magna* in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. x + 40 pp. COSEWIC. 2012a. COSEWIC assessment and status report on the Eastern Wood-pewee *Contopus virens* in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. x + 39 pp.

COSEWIC . 2012b. COSEWIC assessment and status report on the Wood Thrush Hylocichla mustelina in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. ix + 46 pp.

COSEWIC. 2013a. COSEWIC assessment and update status report on the Bank Swallow Riparia riparia in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. ix + 48 pp.

COSEWIC . 2013b. COSEWIC assessment and status report on the Grasshopper Sparrow pratensis subspecies Ammodramus savannarum pratensis in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. ix + 36 pp. COSEWIC . 2013c. COSEWIC assessment and update status report on the Little Brown Myotis Myotis Myotis septentrionalis and Tri-colored Bat Perimyotis subfalvus in Canada. Committee on the Status of Endangered Wildlife in

Canada. Ottawa. xxiv + 93 pp.

COSEWIC. 2018a. COSEWIC assessment and status report on the Black Ash Fraxinus nigra in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. xii + 95 pp.

COSEWIC. 2018b. COSEWIC assessment and status report on the Common Nighthawk Chordeiles minor in Canada. Committee on the Status of Endangered Wildlife in Canada.

Ministry of Natural Resources and Forestry (MNRF). 2014. Eastern Small-footed Bat. Queen's Printer for Ontario. https://www.ontario.ca/environment-and-energy/eastern-small-footed-bat Ministry of the Environment, Conservation and Parks (MECP). 2024. Species at Risk in Ontario. https://www.ontario.ca/page/species-risk-ontario

Table 1 (AEC24-153) Page 3 of 3

			Vegetation Communities ²			Conservation Rankings ³			Regional ⁴				
\mathbf{FAMILY}^1	SCIENTIFIC NAME ¹	COMMON NAME ¹	MAMM1-2/MASM1-1a	MAMM1-2/MASM1-1b	SWDM2-2	MEGM4	MEMM4	THDM5/MEMM4		GRANK	SRANK	TRACK	Simcoe
Aceraceae	Acer negundo	Manitoba Maple				X		X		G5	S5	N	
Aceraceae	Acer platanoides	Norway Maple						X		GNR	SE5	N	
Aceraceae	Acer saccharum	Sugar Maple				X				G5	S5	N	
Alismataceae	Alisma triviale	Northern Water-plantain	X	Ĭ						G5	S5	N	
Anacardiaceae	Rhus typhina	Staghorn Sumac					X	X	X	G5	S5	N	
Anacardiaceae	Toxicodendron radicans var. radicans	Eastern Poison Ivy			X		X		X	G5T5	S5	N	
Apiaceae	Daucus carota	Wild Carrot					X	X	X	GNR	SE5	N	
Apocynaceae	Apocynum cannabinum	Hemp Dogbane						X		GNR	S5	N	
Apocynaceae	Asclepias incarnata	Swamp Milkweed						X		G5	S5	N	
Apocynaceae	Asclepias syriaca	Common Milkweed				X	X		X	G5	S5	N	
Apocynaceae	Vinca minor	Lesser Periwinkle				X				GNR	SE5	N	
Apocynaceae	Vincetoxicum rossicum	European Swallowwort		Ĭ		Ĭ		X		GNR	SE5	N	
Asteraceae	Achillea millefolium	Common Yarrow	X			X	X	X		G5	SE5?	N	
Asteraceae	Arctium minus	Common Burdock		Ĭ		Ĭ	X			GNR	SE5	N	
Asteraceae	Bidens frondosa	Devil's Beggarticks	X							G5	S5	N	
Asteraceae	Centaurea stoebe	Spotted Knapweed					X	X	X	GNR	SE5	N	
Asteraceae	Cichorium intybus	Wild Chicory				X	X		X	GNR	SE5	N	
Asteraceae	Cirsium arvense	Canada Thistle		X			X	X		G5	SE5	N	
Asteraceae	Cirsium vulgare	Bull Thistle				X	X	X	X	GNR	SE5	N	
Asteraceae	Doellingeria umbellata	Flat-top White Aster			X					G5	S5	N	
Asteraceae	Erigeron annuus	Annual Fleabane				X		X	X	G5	S5	N	
Asteraceae	Euthamia graminifolia	Grass-leaved Goldenrod	X	X	X	X	X	X	X	G5	S5	N	
Asteraceae	Eutrochium maculatum	Spotted Joe Pye Weed	X					X		G5	S5	N	
Asteraceae	Inula helenium	Elecampane						X		GNR	SE5	N	
Asteraceae	Leucanthemum vulgare	Oxeye Daisy					X	X		GNR	SE5	N	
Asteraceae	Pilosella officinarum	Mouse-ear Hawkweed						X		GNR	SE5	N	
Asteraceae	Solidago altissima	Tall Goldenrod		X	X	X	X	X	X	G5	S5	P	

Table 2 (24-153)

Page 1 of 6

				ı			Conservation							
			V	egeta	atio	n Co	mn	nuni	ties ²		Rankings ³			Regional ⁴
FAMILY ¹	SCIENTIFIC NAME ¹	COMMON NAME ¹	MAMMI-2/MASMI-13	MAMMI-2/MASMI-1F			MEGM4	MEMM4	THDM5/MEMM4		GRANK	SRANK	TRACK	Simcoe
Asteraceae	Solidago canadensis	Canada Goldenrod							X		G5	S5	N	
Asteraceae	Solidago nemoralis	Grey-stemmed Goldenrod								X	G5	S5	P	
Asteraceae	Sonchus arvensis	Field Sow-thistle		7	X		X	X	X	X	GNR	SE5	N	
Asteraceae	Symphyotrichum lanceolatum	Panicled Aster	Σ	ζ .		X	X	X	X		G5	S5	P	
Asteraceae	Symphyotrichum lateriflorum	Calico Aster				X	X				G5	S5	P	
Asteraceae	Symphyotrichum novae-angliae	New England Aster					X	X	X		G5	S5	N	
Asteraceae	Symphyotrichum puniceum	Purple-stemmed Aster	Σ	ζ 2	X	X					G5	S5	N	
Asteraceae	Taraxacum officinale	Common Dandelion				X	X			X	G5	SE5	N	
Asteraceae	Tussilago farfara	Coltsfoot	Σ	ζ.							GNR	SE5	N	
Betulaceae	Betula papyrifera	Paper Birch								X	G5	S5	N	
Bignoniaceae	Catalpa speciosa	Northern Catalpa							X		G4?	SE1	N	
Boraginaceae	Echium vulgare	Common Viper's Bugloss						X		X	GNR	SE5	N	
Brassicaceae	Alliaria petiolata	Garlic Mustard							X		GNR	SE5	N	
Cannabaceae	Cannabis sativa	Hemp							X		GNR	SE1	N	
Caprifoliaceae	Viburnum opulus var. opulus	Cranberry Viburnum		2	X	X			X		G5TN	R SE4?	N	
Caryophyllaceae	Dianthus armeria	Deptford Pink	Σ	ζ.				X			GNR	SE5	N	
Clusiaceae	Hypericum perforatum	Common St. John's-wort	Σ	Υ .		X	X	X		X	GNR	SE5	N	
Convolvulaceae	Convolvulus arvensis	Field Bindweed							X		GNR	SE5	N	
Cornaceae	Cornus sericea	Red-osier Dogwood	Σ	ζ		X		X	X	X	G5	S5	N	
Cupressaceae	Juniperus virginiana	Eastern Red Cedar					X		X		G5	S5	N	
Cupressaceae	Thuja occidentalis	Eastern White Cedar				X	X		X	X	G5	S5	N	
Cyperaceae	Carex bebbii	Bebb's Sedge	Σ	X 2	X						G5	S5	N	
Cyperaceae	Carex granularis	Limestone Meadow Sedge					X		X		G5	S5	N	
Cyperaceae	Carex spicata	Spiked Sedge			X				X		GNR	SE5	N	R-5
Cyperaceae	Carex vulpinoidea	Fox Sedge	Σ		X		X		X		G5	S5	N	
Cyperaceae	Scirpus atrovirens	Dark-green Bulrush	Σ			X		X	X		G5	S5	N	
Cyperaceae	Scirpus cyperinus	Common Woolly Bulrush		2	X	X			X		G5	S5	N	

Table 2 (24-153) Page 2 of 6

			Vegetation Communities ²			Conservation Rankings ³			Regional ⁴				
\mathbf{FAMILY}^1	SCIENTIFIC NAME ¹	COMMON NAME ¹	MAMM1-2/MASM1-1a	MAMM1-2/MASM1-1b	SWDM2-2	MEGM4	MEMM4	THDM5/MEMM4		GRANK	SRANK	TRACK	Simcoe
Cyperaceae	Scirpus microcarpus	Red-tinged Bulrush		X						G5	S5	N	
Elaeagnaceae	Elaeagnus angustifolia	Russian Olive				X				GNR	SE3	N	
Equisetaceae	Equisetum arvense	Field Horsetail	X	X	X			X	X	G5	S5	N	
Equisetaceae	Equisetum hyemale	Common Scouring-rush	X					X		G5	S5	N	
Equisetaceae	Equisetum variegatum	Variegated Scouring-rush	X							G5	S5	N	
Fabaceae	Lathyrus latifolius	Everlasting Pea						X		GNR	SE4	N	
Fabaceae	Lotus corniculatus	Garden Bird's-foot Trefoil	X			X	X	X	X	GNR	SE5	N	
Fabaceae	Medicago lupulina	Black Medick						X		GNR	SE5	N	
Fabaceae	Medicago sativa	Alfalfa							X	GNR	SE5	N	
Fabaceae	Melilotus albus	White Sweet-clover				X			X	G5	SE5	N	
Fabaceae	Robinia pseudoacacia	Black Locust				X		X		G5	SE5	N	
Fabaceae	Trifolium pratense	Red Clover				X			X	GNR	SE5	N	
Fabaceae	Vicia cracca	Tufted Vetch	X	X		X	X	X	X	GNR	SE5	N	
Fagaceae	Quercus robur	English Oak				X				GNR	SE1	N	
Haloragaceae	Proserpinaca palustris	Marsh Mermaidweed	X							G5	S4	N	
Juglandaceae	Juglans cinerea	Butternut				X				G3	S2?	Y	
Judlandaceae	Juglans cinerea x Juglans ailantifolia	Butternut Hybrid						X		GNA		N	
Juglandaceae	Juglans nigra	Black Walnut				X		X	X	G5	S4?	N	R-1
Juncaceae	Juncus articulatus ssp. articulatus	Jointed Rush	X					X		G5TN	RS5	N	
Juncaceae	Juncus brevicaudatus	Short-tailed Rush					X			G5	S5	N	
Juncaceae	Juncus dudleyi	Dudley's Rush	X	X			X	X		G5	S5	N	
Juncaceae	Juncus effusus	Soft Rush	X							G5	S5	N	
Juncaceae	Juncus tenuis	Path Rush	X	X		X		X		GNR	S5	N	
Lamiaceae	Clinopodium vulgare ssp. vulgare	Wild Basil							X	G5T5	S5	N	
Lamiaceae	Leonurus cardiaca	Common Motherwort						X		GNR	SE5	N	
Lamiaceae	Lycopus uniflorus	Northern Water-horehound			X		Ĭ			G5	S5	N	
Lamiaceae	Prunella vulgaris	Common Self-heal			X	X				G5	S5	N	

Table 2 (24-153) Page 3 of 6

							Conservation						
			Ve	getai	tion (Comi	muni	ties ²		I	Ranking	s^3	Regional ⁴
FAMILY ¹	SCIENTIFIC NAME ¹	COMMON NAME ¹	MAMM1-2/MASM1-1a	MAMM1-2/MASM1-1b	SWDM2-2	MEGM4	m MEMM4	THDM5/MEMM4		GRANK	SRANK	TRACK	Simcoe
Lemnaceae	Lemna minor	Small Duckweed		X						G5	S5	N	
Liliaceae	Asparagus officinalis	Garden Asparagus			X		X	X		G5?	SE5	N	
Lythraceae	Lythrum salicaria	Purple Loosestrife	X				X	X		G5	SE5	N	
Oleaceae	Fraxinus pennsylvanica	Red Ash	X	X	X	X	X	X		G4	S4	N	
Onagraceae	Epilobium coloratum	Purple-veined Willowherb		X						G5	S5	N	R-4
Onagraceae	Oenothera biennis	Common Evening-primrose					X		X	G5	S5	N	
Pinaceae	Pinus strobus	Eastern White Pine				X				G5	S5	N	
Pinaceae	Pinus sylvestris var. sylvestris	Scots Pine				X		X	X	GNRT	NSE5	N	
Plantaginaceae	Plantago lanceolata	English Plantain				X			X		SE5	N	
Poaceae	Agrostis gigantea	Redtop	X				X	X	X	G4G5	SE5	N	
Poaceae	Agrostis stolonifera	Creeping Bentgrass	X	X	X		X			G5	SE5	N	
Poaceae	Bromus inermis	Smooth Brome				X	X	X		G5T5	SE5	N	
Poaceae	Dactylis glomerata	Orchard Grass			X	X		X		GNR	SE5	N	
Poaceae	Festuca rubra	Red Fescue	X	X		X	X	X		G5	S5	P	
Poaceae	Phalaris arundinacea	Reed Canarygrass	X	X	X	X	X	X		G5	S5	N	
Poaceae	Phleum pratense	Common Timothy				X	X	X		GNR	SE5	N	
Poaceae	Phragmites australis ssp. australis	European Reed	X				X			G5T5	SE5	N	
Poaceae	Poa compressa	Canada Bluegrass				X				GNR	SE5	N	
Poaceae	Poa palustris	Fowl Bluegrass			X					G5	S5	N	
Poaceae	Poa pratensis	Kentucky Bluegrass	X							G5	S5	P	
Polygonaceae	Persicaria amphibia	Water Smartweed		X						G5	S5	N	
Polygonaceae	Reynoutria japonica	Japanese Knotweed						X		GNR	SE5	N	
Polygonaceae	Rumex crispus	Curled Dock				X	X			GNR	SE5	N	
Primulaceae	Lysimachia nummularia	Creeping Yellow Loosestrife			X					GNR	SE5	N	
Ranunculaceae	Ranunculus acris	Common Buttercup			X	X				G5	SE5	N	
Rhamnaceae	Rhamnus cathartica	European Buckthorn		X	X	X	X	X	Ī	GNR	SE5	N	
Rosaceae	Crataegus sp.	a Hawthorn						X		N/A	N/A	N/A	

Table 2 (24-153) Page 4 of 6

			V	Vegetation Communities ²				Conserva Ranking	_	Regional ⁴			
FAMILY ¹	SCIENTIFIC NAME ¹	COMMON NAME ¹	MAMMI-2/MASMI-19	VICALVILVIL-2/ IVICALSIVIL-14 	MAMMI-2/MASMI-1b	SW DM2-2		MEMM4		CVC_I	SRANK	TRACK	Simcoe
Rosaceae	Fragaria virginiana	Wild Strawberry					X			X G5	S5	N	
Rosaceae	Geum aleppicum	Yellow Avens		_			X			G5	S5	N	
Rosaceae	Geum canadense	Canada Avens				X				G5	S5	N	
Rosaceae	Malus pumila	Common Apple					X			G5	SE4	N	
Rosaceae	Rosa multiflora	Multiflora Rose							X	GN	-	N	
Rubiaceae	Galium palustre	Common Marsh Bedstraw		X						G5	S5	N	
Salicaceae	Populus balsamifera	Balsam Poplar	2	X						X G5	S5	N	
Salicaceae	Populus grandidentata	Large-toothed Aspen								X G5	S5	N	
Salicaceae	Populus tremuloides	Trembling Aspen				Ĭ				X G5	S 5	N	
Salicaceae	Salix alba	White Willow	2	X	X				X	G5	SE4	N	
Salicaceae	Salix bebbiana	Bebb's Willow		X		Ĭ			Ĭ	G5	S 5	N	
Salicaceae	Salix discolor	Pussy Willow	2	X						G5	S5	N	
Salicaceae	Salix eriocephala	Cottony Willow		Ĭ		Ĭ		X	X I	X G5	S5	N	
Salicaceae	Salix euxina	Crack Willow			X	X				GN	R SE	N	
Salicaceae	Salix petiolaris	Meadow Willow		X	X	X		X	X	G5	S5	N	
Solanaceae	Solanum dulcamara	Bittersweet Nightshade			X	X				GN	R SE5	N	
Tiliaceae	Tilia americana	Basswood							X	G5	S5	N	
Typhaceae	Typha angustifolia	Narrow-leaved Cattail	2	X	X			X	X	G5	SE5	N	
Typhaceae	Typha latifolia	Broad-leaved Cattail	2	X	X	X	Ī	X	Υ .	G5	S5	N	
Ulmaceae	Ulmus americana	White Elm		Ī			X		1	X G4	S5	N	
Ulmaceae	Ulmus pumila	Siberian Elm		Ī		Ī	Ī		Χ :	K GN	R SE3	N	
Vitaceae	Parthenocissus vitacea	Thicket Creeper	2	X		X				G5	S5	N	
Vitaceae	Vitis riparia	Riverbank Grape	2	X	X	X	X	X	X Z	X G5	S5	N	

¹ Nomenclature based on Ministry of Natural Resources (MNR) Natural Heritage Information Centre (NHIC, 2024)

Table 2: Vascular Plant List, The Gateway Centre (Collingwood)

Table 2 (24-153) Page 5 of 6

² ELC Codes based on Ecological Land Classification for Southern Ontario manual (Lee et al., 1998, 2008)

³ Conservation Rankings: From Ontario Ministry of Natural Resources, Natural Heritage Information Centre (https://www.ontario.ca/page/natural-heritage-information-centre)

Table 2 (24-153) Page 6 of 6

⁴ Riley, J.L. 1989. Distribution and Status of the Vascular Plants of Central Region, Ontario. Ministry of Natural Resources. Parks and Recreational Areas Section, OMNR, Open File Ecological Report SR8902, Central Region, Richmond Hill, Ontario. XiX + 110 pp.

Table 3: Summary of Vegetation Communities, The Gateway Centre (Collingwood)

Unit	Description
MA (MARSH)	Tree and shrub cover ≤25%, dominated by emergent hydrophytic macrophytes; variable flooding regime with water depth <2m.
Meadow Marsh (MAM)/Shallow Marsh (MAS)	Meadow Marsh: Species less tolerant of prolonged flooding; includes facultative, facultative wetland, and obligate wetland plants; flooding seasonal (soils flooded in spring, moist to dry by summer); represents the wetland-terrestrial interface.
	Shallow Marsh: Species less tolerant of prolonged flooding; species restricted to facultative and obligate wetland plants.
MAMM1-2/MASM1-1a (Cattail Mineral Meadow Marsh/Cattail Mineral Shallow Marsh) complex	This community represents a cattail-dominated wetland complex occupying a historical sedimentation pond in the northwest portion of the property, including a connecting ditch established along the north side of a gravel pad.
	This wetland complex features a small number of standing White Willow (<i>Salix alba</i>) among a moderately sparse (10-25% cover) understory of Meadow Willow (<i>Salix petiolaris</i>), Red-osier Dogwood (<i>Cornus sericea</i>), White Willow, and Pussy-willow (<i>Salix discolor</i>). The ground layer is dense and comprises Narrow-leaved Cattail (<i>Typha angustifolia</i>), Creeping Bentgrass (<i>Agrostis stolonifera</i>), Dudley's Rush (<i>Juncus dudleyi</i>), Grass-leaved Goldenrod (<i>Euthamia graminifolia</i>), Reed Canary Grass (<i>Phalaris arundinacea</i>), Panicled Aster (<i>Symphyotrichum lanceolatum</i>), Purple Loosestrife (<i>Lythrum salicaria</i>), and Variegated Scouring Rush (<i>Equisetum variegatum</i>) in descending order of density.
	A minor (approx. 236m²) open water inclusion is located in the northwest corner of the unit, representing a historical sedimentation pond with retained Hickenbotton Drain and emergency spillway. Permanent water within the pond is approx. 20cm deep and includes abundant Marsh Mermaid-weed (<i>Proserpinacea palustris</i>).
MAMM1-2/MASM1-1b (Cattail Mineral Meadow Marsh/Cattail Mineral Shallow Marsh) complex	This community represents a cattail-dominated wetland complex in the northeast portion of the property and is directly connected to the SWDM2-2 community. This wetland unit appears to be of natural origin and maintained (in part) by fluvial inputs from the adjacent residential subdivision to the east.
	This wetland complex features a large standing Crack Willow (<i>Salix euxina</i>) at the canopy level (>10m in height), with sparse (<10%) moderately-aged Crack Willow and Green Ash (<i>Fraxnus pennsylvanica</i>) <10m in height. A sparse (<10% cover) understory includes Green Ash, Meadow Willow, Common Buckthorn (<i>Rhamnus cathartica</i>), and White Willow. The ground layer is dense and is dominated by Narrow-leaved Cattail (<i>Typha angustifolia</i>) with Reed Canary Grass and Broad-leaved Cattail (<i>Typha latifolia</i>) associates, in addition to a more limited representation of Grass-leaved Goldenrod, Fox Sedge (<i>Carex vulpinoidea</i>), Swamp Aster (<i>Symphyotrichum puniceum</i>), Purple Loosestrife, Creeping Bentgrass, and Dudley's Rush.
SW (SWAMP)	Tree or shrub cover >25%; dominated by hydrophytic shrub and tree species. Variable flooding regimes, water depth <2m, standing water or vernal pooling >20% of ground coverage.
Deciduous Swamp (SWD)	Tree cover >25%; trees >5m in height; deciduous tree species >75% of canopy cover.
SWDM2-2 (Green Ash Mineral Deciduous	This community is located in the northeast corner of the property and is directly connected to the MAMM1-2/MASM1-1b complex community. This wetland unit

AEC24-153 1 of 3

Table 3: Summary of Vegetation Communities, The Gateway Centre (Collingwood)

Unit	Description
Swamp)	appears to be of natural origin and maintained (in part) by fluvial inputs from the adjacent residential subdivision to the east.
	This community features a large standing Crack Willow (<i>Salix euxina</i>) at the canopy level (>10m in height), with moderately dense (25-60%) moderately-aged Green Ash and occasional Eastern White Cedar (<i>Thuja occidentalis</i>) <10m in height. The understory later is dense (>60% cover) and comprises Red-osier Dogwood, Common Buckthorn, Green Ash, and Meadow Willow in descending order of density. The ground
	layer is moderately dense (25-60% cover) and includes Calico Aster (<i>Symphyotrichum lateriflorum</i>), Panicled Aster, Grass-leaved Goldenrod, Bittersweet Nightshade (<i>Solanum dulcamara</i>), Tall Goldenrod (<i>Solidago altissima</i>), and Creeping Bentgrass in descending order of density.
CU (CULTURAL)	Community resulting from, or maintained by, cultural or anthropogenic-based disturbances.
ME (Meadow)	Tree and shrub cover <25%; open herbaceous communities; cover varies from scattered and patchy to continuous meadow; areas with a cultural legacy typically dominated by invasive plant species.
	Mineral soil >30cm deep; shrub and tree establishment inhibited by environmental or have been removed by land use practices; areas subjected to natural disturbance (<i>e.g.</i> fire) or recovering from cultural disturbance (<i>e.g.</i> clearing, pasture).
MEGM (Graminoid Meadow)	Meadow dominated by grass-like species (e.g. grass, sedge).
MEGM4 (Fresh-Moist Graminoid Meadow)	This community represents a minor old-field meadow unit in the northern portion of the property, adjacent to the Hamilton Drain Trail.
	This community is open in character with no canopy or subcanopy later. A very sparse shrub layer (<<10% cover) consists of Green Ash, Common Apple (<i>Malus pumila</i>), Redosier Dogwood, and Eastern Redcedar (<i>Juniperus virginiana</i>). The ground layer is dense and dominated by meadow grasses and associated forbs, including Redtop (<i>Agrostis gigantea</i>), Red Fescue (<i>Festuca rubra</i>), Garden Bird's-foot Trefoil (<i>Lotus corniculatus</i>), English Plantain (<i>Plantago lanceolata</i>), Panicled Aster, and Grass-leaved Goldenrod in descending order of density.
	The southern and western edges of the meadow are bordered by a Naturalized Deciduous Hedgerow (FODM11) inclusion, with a canopy/subcanopy layer comprising Green Ash, Easter White Pine (<i>Pinus strobus</i>), Sugar Maple (<i>Acer saccharum</i>), Scot's Pine (<i>Pinus sylvestris</i>), and Common Apple. The ground layer within the hedgerow inclusion comprises Green Ash seedlings, occasional Red-osier Dogwood, Common Buckthorn, and White Elm (<i>Ulmus americana</i>) seedlings.
MEMM4 (Fresh-Moist Mixed Meadow)	This community represents a minor old-field meadow unit between the western edge of the gravel pad and Hurontario Street, comprising the majority of the wester border of the property.
	This community is open in character with no canopy or subcanopy later. A very sparse shrub layer (<<10% cover) consists of Green Ash, Staghorn Sumac (<i>Rhus typhina</i>), Meadow Willow, and Red-osier Dogwood. The ground layer is dense and dominated by

AEC24-153 2 of 3

Table 3: Summary of Vegetation Communities, The Gateway Centre (Collingwood)

Unit	Description
	meadow grasses and associated forbs, including Red Fescue, Reed Canary Grass, Tall Goldenrod, Redtop, Common Milkweed (<i>Asclepias syriaca</i>), Grass-leaved Goldenrod, Creeping Bentgrass, and Smooth Brome (<i>Bromus inermis</i>) in descending order of density.
THDM5/MEMM4 (Fresh- Moist Deciduous Thicket/Fresh-Moist Mixed Meadow) complex	This community represents a fresh-moist regenerating deciduous thicket/meadow marsh complex, primarily open meadow with patchy areas of shrubs and young trees exceeding 25% cover. This community is located in the southeast portion of the property, occupying lands between the eastern edge of the gravel pad and the adjacent residential subdivision.
	This community features a sparse (<10%) canopy and subcanopy layer including occasional Large-tooth Aspen (<i>Populus grandidentata</i>), White Willow, Siberian Elm (<i>Ulmus pumila</i>), and Black Locust (<i>Robinia pseudoacacia</i>) in descending order of density. The understory layer is sparse (<10% cover) in some locations and moderately dense (25-60% cover) in others, comprising Green Ash with Meadow Willow, Red-osier Dogwood, and Eastern White Cedar associates. The ground layer is dense and includes Tall Goldenrod, Reed Canary Grass, Grass-leaved Goldenrod, Wild Carrot (<i>Daucus carota</i>), Smooth Brome, Red Fescue, Redtop, Creeping Bentgrass, and Panicled Aster in descending order of density.
	A minor Fresh-Moist Deciduous Woodland (WODM5) inclusion measuring approximately 650m ² is located in the northern portion of the unit, and is directly connected to the adjacent SWDM2-2 and MAMM1-1/MASM1-2b wetland units. The woodland inclusion consists of low (<10m height) Green Ash, with a dense understory comprising Green Ash, Common Buckthorn, Red-osier Dogwood, and Hawthorn (<i>Crataegus spp.</i>).
CONSTRUCTED (CV)	Constructed features with anthropogenic histories.
CVC_1 (Business Sector)	This community includes the gravel pad established as a component of early works associated with a previous development. A pioneer meadow is located within the limits of the gravel pad area, with overall sparse vegetation growth.
	This community is open in character with no canopy or subcanopy later. A very sparse shrub layer (<<10% cover) consists of Balsam Poplar (<i>Populus balsamifera</i>), Eastern White Cedar, Siberian Elm, and Eastern White Cedar. The ground layer is moderately sparse (10-25% cover) and includes Wild Carrot, Tall Goldenrod, Garden Bird's-foot Trefoil, Wild Chicory (<i>Cichorium intybus</i>), Wild Basil (<i>Clinopodium vulgare</i>), and Wild Strawberry (<i>Fragaria virginiana</i>) in descending order of density.
CVR_4 (Rural Property)	This unit represents an occupied rural dwelling in the northwest corner of the property, with associated driveway, mowed/maintained lawn, gardening and landscaping.

AEC24-153 3 of 3

			Location	1,2				Conservation Rankings ³				
				1	nds							
FAMILY	SCIENTIFIC NAME	COMMON NAME	Visit 1	Visit 2	Adjacent Lands	Incidental	GRANK	SRANK	ESA	SARA	TRACK	
Alcedinidae	Megaceryle alcyon	Belted Kingfisher				✓	G5	S5B,S4N			N	
Ardeidae	Ardea herodias	Great Blue Heron			FO		G5	S4			N	
Ardeidae	Butorides virescens	Green Heron				✓	G5	S4B			N	
Charadriidae	Charadrius vociferus	Killdeer	FY/P/S	DD/A/H			G5	S4B			N	
Columbidae	Zenaida macroura	Mourning Dove		P/H			G5	S5			N	
Corvidae	Corvus brachyrhynchos	American Crow	Н		Н		G5	S5			N	
Fringillidae	Spinus tristis	American Goldfinch	S				G5	S5			N	
Icteridae	Agelaius phoeniceus	Red-winged Blackbird	FY/S	FY/S/H			G5	S5			N	
Icteridae	Quiscalus quiscula	Common Grackle		P/H			G5	S5			N	
Laridae	Larus delawarensis	Ring-billed Gull		FO	FO		G5	S5			N	
Paridae	Poecile atricapillus	Black-capped Chickadee				✓	G5	S5			N	
Parulidae	Geothlypis trichas	Common Yellowthroat		S			G5	S5B,S3N			N	
Parulidae	Setophaga petechia	Yellow Warbler	S	S			G5	S5B			N	
Parulidae	Setophaga ruticilla	American Redstart	S				G5	S5B			N	
Passerellidae	Melospiza melodia	Song Sparrow	S	S			G5	S5			N	
Passerellidae	Spizella passerina	Chipping Sparrow		S			G5	S5B,S3N			N	
Picidae	Colaptes auratus	Northern Flicker				✓	G5	S5			N	
Sturnidae	Sturnus vulgaris	European Starling	S				G5	SNA			N	
Troglodytidae	Troglodytes aedon	House Wren			S		G5	S5B			N	
Turdidae	Turdus migratorius	American Robin	Н	S	_		G5	S5			N	
Vireonidae	Vireo gilvus	Warbling Vireo	S	S			G5	S5B			N	

1 Visit 1: 6 June 2024, Observer: A. Pompilio-Grant, Temperature 10°C, Cloud Cover 50%, Wind: B1, Precipitation: Nil, Search Time 07:10 to 07:20; Visit 2: 10 June 2024, Observer: A. Pompilio-Grant, Temperature 12°C, Cloud Cover 50%, Wind: B0, Precipitation: Nil, Search Time 06:18 to 06:28

² Breeding Bird Evidence Codes: X - Species observed, C - Call heard, FO - Flyover (Species presence); H - Species observed in its breeding season in suitable nesting habitat, S - Singing male (Possible Breeding); P - Pair observed, T - Territorial behaviour, A - Agitated behaviour or anxiety calls of adult, V - Visiting a probably nest site, N - Nest building or excavation of nest hole (Probable Breeding); DD - Distraction display or injury feigning, NU - Used Nest or egg shells, FY - Recently fledged young, AE - Adult leaving or entering nest sites, FS - Adult carrying fecal sac, CF - Adult carrying food for young, NE - Nest containing eggs, NY - Nest with young seen or heard (Confirmed Breeding).

			Location ^{1,2}					Conserva	tion Ran	kings ³	
FAMILY	SCIENTIFIC NAME	COMMON NAME	Visit 1	Visit 2	Adjacent Lands	Incidental	GRANK	SRANK	ESA	SARA	TRACK

³ Conservation Rankings: From Ontario Ministry of Natural Resources, Natural Heritage Information Centre (https://www.ontario.ca/page/natural-heritage-information-centre)

Table 1.1 Seasonal Concentrations of Areas of Animals

Wildlife Habitat	Wildlife Species		Candidate SWH	Confirmed SWH	Assessment
		ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	
Waterfowl Stopover and Staging Areas (Terrestrial) Rationale: Habitat important to migrating waterfowl.	American Black Duck Wood Duck Green-winged Teal Blue-winged Teal Mallard Northern Pintail Northern Shoveler American Wigeon Gadwall	CUM1 CUT1 Plus evidence of annual spring flooding from melt water or run-off within these Ecosites.	 Fields with sheet water during Spring (mid-March to May). Fields flooding during spring melt and run-off provide important invertebrate foraging habitat for migrating waterfowl. Agricultural fields with waste grains are commonly used by waterfowl, these are not considered SWH unless they have spring sheet water available. Information Sources Anecdotal information from the landowner, adjacent landowners or local naturalist clubs may be good information in determining occurrence. Reports and other information available from Conservation Authorities Sites documented through waterfowl planning processes (e.g. EHJV implementation plan) Field Naturalist Clubs Ducks Unlimited Canada Natural Heritage Information Centre (NHIC) Waterfowl Concentration Area 	 Studies carried out and verified presence of an annual concentration of any listed species, evaluation methods to follow "Bird and Bird Habitats: Guidelines for Wind Power Projects" Any mixed species aggregations of 100 or more individuals required. The flooded field ecosite habitat plus a 100-300m radius area, dependant on local site conditions and adjacent land use is the significant wildlife habitat. Annual use of habitat is documented from information sources or field studies (annual use can be based on studies or determined by past surveys with species numbers and dates). SWHMiST Index #7 provides development effects and mitigation measures. 	Fields with sheet water not observed. No suitable habitat within the study area.
Waterfowl Stopover and Staging Areas (Aquatic) Rationale: Important for local and migrant waterfowl populations during the spring or fall migration or both periods combined. Sites identified are usually only one of a few in the eco- district.	Canada Goose Cackling Goose Snow Goose American Black Duck Northern Pintail Northern Shoveler American Wigeon Gadwall Green-winged Teal Blue-winged Teal Hooded Merganser Common Merganser Lesser Scaup Greater Scaup Long-tailed Duck Surf Scoter White-winged Scoter Black Scoter Ring-necked duck Common Goldeneye Bufflehead Redhead Ruddy Duck Red-breasted Merganser Brant Canvasback Ruddy Duck	MAS1 MAS2 MAS3 SAS1 SAM1 SAF1 SWD1 SWD2 SWD3 SWD4 SWD5 SWD6 SWD7	 Ponds, marshes, lakes, bays, coastal inlets, and watercourses used during migration. Sewage treatment ponds and storm water ponds do not qualify as a SWH, however a reservoir managed as a large wetland or pond/lake does qualify. These habitats have an abundant food supply (mostly aquatic invertebrates and vegetation in shallow water). Information Sources Environment Canada Naturalist clubs often are aware of staging/stopover areas OMNRF Wetland Evaluations indicate presence of locally and regionally significant waterfowl staging. Sites documented through waterfowl planning processes (e.g. EHJV implementation plan) Ducks Unlimited projects Element occurrence specification by Nature Serve: http://www.natureserve.org Natural Heritage Information Centre (NHIC) Waterfowl Concentration Areas 	 Studies carried out and verified presence of: Aggregations of 100 or more of listed species for 7 days, results in > 700 waterfowl use days. Areas with annual staging of ruddy ducks, canvasbacks, and redheads are SWH. The combined area of the ELC ecosites and a 100m radius area is the SWH. Wetland area and shorelines associated with sites identified within the SWHTG Appendix K are significant wildlife habitat. Evaluation methods to follow "Bird and Bird Habitats: Guidelines for Wind Power Projects". Annual Use of Habitat is Documented from Information Sources or Field Studies (Annual can be based on completed studies or determined from past surveys with species numbers and dates recorded). SWHMiST Index #7 provides development effects and mitigation measures. 	Shoreline wetlands with potential for abundant food supply not observed. No suitable habitat within the study area.

Wildlife Habitat	Wildlife Species		Candidate SWH	Confirmed SWH	Assessment AEC24-
Whante Habitat	whethe species	ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	. Assessment
Shorebird Migratory Stopover Area Rationale: High quality shorebird stopover habitat is extremely rare and typically has a long history of use.	Greater Yellowlegs Lesser Yellowlegs Marbled Godwit Hudsonian Godwit Black-bellied Plover American Golden-Plover Semipalmated Plover Solitary Sandpiper Spotted Sandpiper Semipalmated Sandpiper Pectoral Sandpiper White-rumped Sandpiper Baird's Sandpiper Least Sandpiper Purple Sandpiper Stilt Sandpiper Stilt Sandpiper Stilt Sandpiper Short-billed Dowitcher Red-necked Phalarope Whimbrel Ruddy Turnstone Sanderling Dunlin	BBO1 BBO2 BBS1 BBS2 BBT1 BBT2 SDO1 SDS2 SDT1 MAM1 MAM2 MAM3 MAM4 MAM5	 Shorelines of lakes, rivers and wetlands, including beach areas, bars and seasonally flooded, muddy and un-vegetated shoreline habitats. Great Lakes coastal shorelines, including groynes and other forms of armour rock lakeshores, are extremely important for migratory shorebirds in May to mid-June and early July to October. Sewage treatment ponds and storm water ponds do not qualify as a SWH. Information Sources Western hemisphere shorebird reserve network Canadian Wildlife Service (CWS) Ontario Shorebird Survey Bird Studies Canada Ontario Nature Local birders and naturalist clubs Natural Heritage Information Center (NHIC) Shorebird Migratory Concentration Area 	Studies confirming: Presence of 3 or more of listed species and > 1000 shorebird use days during spring or fall migration period. (shorebird use days are the accumulated number of shorebirds counted per day over the course of the fall or spring migration period) Whimbrel stop briefly (<24hrs) during spring migration, any site with >100 Whimbrel used for 3 years or more is significant. The area of significant shorebird habitat includes the mapped ELC shoreline ecosites plus a 100m radius area. Evaluation methods to follow "Bird and Bird Habitats: Guidelines for Wind Power Projects". SWHMiST Index #8 provides development effects and mitigation measures.	Beach areas, bars, and seasonally-flooded muddy shoreline habitat associated with shorebird migratory stopover areas not observed. No suitable habitat within the study area.
Raptor Wintering Area Rationale: Sites used by multiple species of individuals and used annually are most significant	Rough-legged Hawk Red-tailed Hawk Northern Harrier American Kestrel Snowy Owl Special Concern: Short-eared Owl Bald Eagle	Hawks/Owls: Combination of ELC Community Series; need to have present one Community Series from each land class; Forest: FOD, FOM, FOC. Upland: CUM; CUT; CUS; CUW. Bald Eagle: Forest community Series: FOD, FOM, FOC, SWD, SWM or SWC on shoreline areas adjacent to large rivers or adjacent to lakes with open water (hunting area).	 The habitat provides a combination of fields and woodlands that provide roosting, foraging and resting habitats for wintering raptors. Raptor wintering sites (hawk/owl) need to be > 20 ha with a combination of forest and upland. Least disturbed sites, idle/fallow or lightly grazed field/meadow (>15ha) with adjacent woodlands. Field area of the habitat is to be windswept with limited snow depth or accumulation. Eagle sites have open water, large trees and snags available for roosting. Information Sources: OMNRF Ecologist or Biologist Field Naturalist Clubs Natural Heritage Information Center (NHIC) Raptor Winter Concentration Area Data from Bird Studies Canada Results of Christmas Bird Counts Reports and other information available from Conservation Authorities. 	 Studies confirm the use of these habitats by: One or more Short-eared Owls or; One or more Bald Eagles or; At least 10 individuals and two of the listed hawk/owl species. To be significant a site must be used regularly (3 in 5 years) for a minimum of 20 days by the above number of birds. The habitat area for an Eagle winter site is the shoreline forest ecosites directly adjacent to the prime hunting area. Evaluation methods to follow "Bird and Bird Habitats: Guidelines for Wind Power Projects". SWHMiST Index #10 and #11 provides development effects and mitigation measures. 	Idle/fallow meadow (MEMM4, MEGM4) minimal and highly localized within the study area limits, significantly below the 15ha threshold required for consideration as Raptor Wintering Area. No woodlands located within the study area limits. No suitable habitat within the study area.

Wildlife Habitat	Wildlife Species		Candidate SWH	Confirmed SWH	Assessment AISC24-1
		ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	
Rationale: Bat hibernacula are rare habitats in all Ontario landscapes.	Big Brown Bat Tri-coloured Bat	Bat Hibernacula may be found in these ecosites: CCR1 CCR2 CCA1 CCA2 (Note: buildings are not considered to be SWH)	 Hibernacula may be found in caves, mine shafts, underground foundations and Karsts. Active mine sites should not be considered as SWH The locations of bat hibernacula are relatively poorly known. Information Sources OMNRF for possible locations and contact for local experts Natural Heritage Information Center (NHIC) Bat Hibernaculum Ministry of Northern Development and Mines for location of mine shafts. Clubs that explore caves (e.g. Sierra Club) University Biology Departments with bat experts. 	 All sites with confirmed hibernating bats are SWH. The habitat area includes a 200m radius around the entrance of the hibernaculum, for most development types and 1000m for wind farms Studies are to be conducted during the peak swarming period (Aug. – Sept.). Surveys should be conducted following methods outlined in the "Bats and Bat Habitats: Guidelines for Wind Power Projects. SWHMiST Index #1 provides development effects and mitigation measures. 	No caves, mine shafts, underground foundations and karsts. No suitable habitat within the study area.
Bat Maternity Colonies Rationale: Known locations of forested bat maternity colonies are extremely rare in all Ontario landscapes.	Big Brown Bat Silver-haired Bat	Maternity colonies considered SWH are found in forested Ecosites. All ELC Ecosites in ELC Community Series: FOD FOM SWD SWM	 Maternity colonies can be found in tree cavities, vegetation and often in buildings (buildings are not considered to be SWH). Maternity roosts are not found in caves and mines in Ontario. Maternity colonies located in Mature deciduous or mixed forest stands with >10/ha large diameter (>25cm dbh) wildlife trees. Female Bats prefer wildlife tree (snags) in early stages of decay, class 1-3 or class 1 or 2. Silver-haired Bats prefer older mixed or deciduous forest and form maternity colonies in tree cavities and small hollows. Older forest areas with at least 21 snags/ha are preferred. Information Sources OMNRF for possible locations and contact for local experts University Biology Departments with bat experts. 	 Maternity Colonies with confirmed use by; >10 Big Brown Bats >5 Adult Female Silver-haired Bats The area of the habitat includes the entire woodland or a forest stand ELC Ecosite or an Ecoelement containing the maternity colonies. Evaluation methods for maternity colonies should be conducted following methods outlined in the "Bats and Bat Habitats: Guidelines for Wind Power Projects". SWHMiST Index #12 provides development effects and mitigation measures. 	Wooded areas within the study area are limited to linear hedgerow units in accordance with provincial guidelines presented in the NHRM. A minor (0.13ha) unit of Deciduous Swamp (SWDM2-2) is illustrated throughout Figure 2 in the northeast portion of the property, however this community is below the minimum size threshold (>0.5ha) for consideration as a standalone vegetation community under the ELC system and is dominated by relatively immature Green Ash. This vegetation unit is not anticipated to be of sufficient size or maturity to support SWH for Bat Maternity Colonies. Based on the above assessment, no portion of the study area is anticipated to provide suitable habitat conditions for Bat Maternity Colonies.
Turtle Wintering Areas Rationale: Generally sites are the only known sites in the area. Sites with the highest number of individuals are most significant.	Midland Painted Turtle Special Concern: Northern Map Turtle Snapping Turtle	Snapping and Midland Painted Turtles; ELC Community Classes; SW, MA, OA and SA, ELC Community Series; FEO and BOO Northern Map Turtle; Open Water areas such as deeper rivers or streams and lakes with current can also be used as over-wintering habitat.	 For most turtles, wintering areas are in the same general area as their core habitat. Water has to be deep enough not to freeze and have soft mud substrates. Over-wintering sites are permanent water bodies, large wetlands, and bogs or fens with adequate Dissolved Oxygen. Man-made ponds such as sewage lagoons or storm water ponds should not be considered SWH. Information Sources EIS studies carried out by Conservation Authorities. Local field naturalists and experts, as well as university herpetologists may also know where to find some of these sites. OMNRF Ecologist or Biologist Field Naturalist clubs Natural Heritage Information Center (NHIC) 	 Presence of 5 over-wintering Midland Painted Turtles is significant. One or more Northern Map Turtle or Snapping Turtle over-wintering within a wetland is significant. The mapped ELC ecosite area with the over wintering turtles is the SWH. If the hibernation site is within a stream or river, the deep-water pool where the turtles are over wintering is the SWH. Over wintering areas may be identified by searching for congregations (Basking Areas) of turtles on warm, sunny days during the fall (Sept. – Oct.) or spring (Mar. – May) Congregation of turtles is more common where wintering areas are limited and therefore significant SWHMiST Index #28 provides development effects and mitigation measures for turtle wintering habitat. 	Permanent standing water within the study area is limited to a highly localized unit (236m2) within a partially-naturalized sedimentation pond in the northwest portion of the property, dug shallow at an estimated 20cm in depth. This unit is not anticipated to meet the necessary size and/or depth requirements to provide suitable overwintering habitat function for turtles. No other natural features within the study area are expected to provide candidate SWH as Turtle Wintering Areas.

Wildlife Habitat	Wildlife Species		Candidate SWH	Confirmed SWH	Assessment AEC24-1
		ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	
Reptile Hibernaculum Rationale: Generally sites are the only known sites in the area. Sites with the highest number of individuals are most significant.	Snakes: Eastern Gartersnake Northern Watersnake Northern Red-bellied Snake Northern Brownsnake Smooth Green Snake Northern Ring-necked Snake Special Concern: Milksnake Eastern Ribbonsnake Lizard: Special Concern (Southern Shield population): Five-lined Skink	ELC Ecosite Codes For all snakes, habitat may be found in any ecosite other than very wet ones. Talus, Rock Barren, Crevice, Cave, and Alvar sites may be directly related to these habitats. Observations or congregations of snakes on sunny warm days in the spring or fall is a good indicator. For Five-lined Skink, ELC Community Series of FOD and FOM and Ecosites: FOC1 FOC3	 Habitat Criteria and Information Sources For snakes, hibernation takes place in sites located below frost lines in burrows, rock crevices and other natural or naturalized locations. The existence of features that go below frost line; such as rock piles or slopes, old stone fences, and abandoned crumbling foundations assist in identifying candidate SWH. Areas of broken and fissured rock are particularly valuable since they provide access to subterranean sites below the frost line. Wetlands can also be important over-wintering habitat in conifer or shrub swamps and swales, poor fens, or depressions in bedrock terrain with sparse trees or shrubs with sphagnum moss or sedge hummock ground cover. Five-lined skink prefer mixed forests with rock outcrop openings providing cover rock overlaying granite bedrock with fissures. Information Sources In spring, local residents or landowners may have observed the emergence of snakes on their property (e.g. old dug wells). Reports and other information available from Conservation Authorities. Field Naturalists clubs University herpetologists Natural Heritage Information Center (NHIC) OMNRF ecologist or biologist may be aware of locations of wintering skinks 	Studies confirming: Presence of snake hibernacula used by a minimum of five individuals of a snake sp. or; individuals of two or more snake spp. Congregations of a minimum of five individuals of a snake sp. or; individuals of two or more snake spp. near potential hibernacula (e.g. foundation or rocky slope) on sunny warm days in Spring (Apr/May) and Fall (Sept/Oct) Note: If there are Special Concern Species present, then site is SWH Note: Sites for hibernation possess specific habitat parameters (e.g. temperature, humidity, etc.) and consequently are used annually, often by many of the same individuals of a local population (i.e. strong hibernation site fidelity). Other critical life processes (e.g. mating) often take place in close proximity to hibernacula. The feature in which the hibernacula is located plus a 30 m radius area is the SWH. SWHMiST Index #13 provides development effects and mitigation measures for snake hibernacula. Presence of any active hibernaculum for skink is significant. SWHMiST Index #37 provides development effects and mitigation measures for five-lined skink wintering habitat.	No features were identified on the property that could provide suitable reptile hibernacula. No suitable habitat within the study area.
Colonially -Nesting Bird Breeding Habitat (Bank and Cliff) Rationale: Historical use and number of nests in a colony make this habitat significant. An identified colony can be very important to local populations. All swallow population are declining in Ontario.	Cliff Swallow Northern Rough-winged Swallow (this species is not colonial but can be found in Cliff Swallow colonies)	Eroding banks, sandy hills, borrow pits, steep slopes, and sand piles. Cliff faces, bridge abutments, silos, barns. Habitat found in the following ecosites: CUM1 CUT1 CUS1 BLO1 BLS1 BLT1 CLO1 CLS1 CLT1	 Any site or areas with exposed soil banks, undisturbed or naturally eroding that is not a licensed/permitted aggregate area. Does not include man-made structures (bridges or buildings) or recently (2 years) disturbed soil areas, such as berms, embankments, soil or aggregate stockpiles. Does not include a licensed/permitted Mineral Aggregate Operation. Information Sources Reports and other information available from Conservation Authorities. Ontario Breeding Bird Atlas Bird Studies Canada; NatureCounts http://www.birdscanada.org/birdmon/ Field Naturalist Clubs. 	 Studies confirming: Presence of 1 or more nesting sites with 8or more cliff swallow pairs and/or rough-winged swallow pairs during the breeding season. A colony identified as SWH will include a 50m radius habitat area from the peripheral nests. Field surveys to observe and count swallow nests are to be completed during the breeding season. Evaluation methods to follow "Bird and Bird Habitats: Guidelines for Wind Power Projects". SWHMiST Index #4 provides development effects and mitigation measures. 	No exposed/eroding soil banks within the study area. No suitable habitat within the study area.

	T	T			AEC24-
Wildlife Habitat	Wildlife Species		Candidate SWH	Confirmed SWH	Assessment
		ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	
Colonially-Nesting Bird Breeding Habitat (Tree/Shrubs) Rationale: Large colonies are important to local bird population, typically sites are only known colony in area and are used annually.	Great Blue Heron Black-crowned Night- Heron Great Egret Green Heron	SWM2 SWM3 SWM5 SWM6 SWD1 SWD2 SWD3 SWD4 SWD5 SWD6 SWD7 FET1	 Nests in live or dead standing trees in wetlands, lakes, islands, and peninsulas. Shrubs and occasionally emergent vegetation may also be used. Most nests in trees are 11 to 15 m from ground, near the top of the tree. Information Sources Ontario Breeding Bird Atlas, colonial nest records. Ontario Heronry Inventory 1991 available from Bird Studies Canada or NHIC (OMNRF). Natural Heritage Information Center (NHIC) Mixed Wader Nesting Colony Aerial photographs can help identify large heronries. Reports and other information available from CAs. MNRF District Offices Local naturalist clubs 	 Studies confirming: Presence of 5 or more active nests of Great Blue Heron or other listed species. The habitat extends from the edge of the colony and a minimum 300m radius or extent of the Forest Ecosite containing the colony or any island <15.0ha with a colony is the SWH. Confirmation of active heronries are to be achieved through site visits conducted during the nesting season (April to August) or by evidence such as the presence of fresh guano, dead young and/or eggshells. SWHMiST Index #5 provides development effects and mitigation measures. 	Great Blue Heron and Green Heron were observed incidentally flying over the property, however no evidence of nesting activity by either species or another listed species was observed.
Colonially-Nesting Bird Breeding Habitat (Ground) Rationale: Colonies are important to local bird population, typically sites are only known colony in area and are used annually.	Herring Gull Great Black-backed Gull Little Gull Ring-billed Gull Common Tern Caspian Tern Brewer's Blackbird	Any rocky island or peninsula (natural or artificial) within a lake or large river (two-lined on a 1;50,000 NTS map). Close proximity to watercourses in open fields or pastures with scattered trees or shrubs (Brewer's Blackbird) MAM1 – 6; MAS1 – 3; CUM CUT CUS	 Nesting colonies of gulls and terns are on islands or peninsulas associated with open water or in marshy areas. Brewers Blackbird colonies are found loosely on the ground in low bushes in close proximity to streams and irrigation ditches within farmlands. Information Sources Ontario Breeding Bird Atlas, rare/colonial species records. Canadian Wildlife Service Reports and other information available from CAs. Natural Heritage Information Center (NHIC) Colonial Waterbird Nesting Area MNRF District Offices Field Naturalist clubs 	 Studies confirming: Presence of > 25 active nests for Herring Gulls or Ring-billed Gulls, >5 active nests for Common Tern or >2 active nests for Caspian Tern. Presence of 5 or more pairs for Brewer's Blackbird. Any active nesting colony of one or more Little Gull, and Great Black-backed Gull is significant. The edge of the colony and a minimum 150m radius area of habitat, or the extent of the ELC ecosites containing the colony or any island <3.0ha with a colony is the SWH. Studies would be done during May/June when actively nesting. Evaluation methods to follow "Bird and Bird Habitats: Guidelines for Wind Power Projects". SWHMiST Index #6 provides development effects and mitigation measures. 	No rocky island/peninsula observed. No suitable habitat within the study area.

Wildlife Habitat	Wildlife Species		Candidate SWH	Confirmed SWH	AEC24-
whome manitat	whome Species	ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	Assessment
Migratany	Painted Lady	Combination of ELC	A butterfly stopover area will be a minimum of 10 ha in	Studies confirm:	Not located within 5km of Lake Ontario.
Migratory Butterfly Stopover Areas Rationale: Butterfly stopover areas are extremely rare habitats and are biologically important for butterfly species that migrate south for the winter.	Red Admiral Special Concern Monarch	Community Series; need to have present one Community Series from each land class: Field: CUM CUT CUS Forest: FOC FOD FOM CUP Anecdotally, a candidate site for butterfly stopover will have a history of butterflies being observed.	 A butterfly stopover area will be a himilitum of 10 ha in size with a combination of field and forest habitat present, and will be located within 5 km of Lake Ontario. The habitat is typically a combination of field and forest, and provides the butterflies with a location to rest prior to their long migration south. The habitat should not be disturbed, fields/meadows with an abundance of preferred nectar plants and woodland edge providing shelter are requirements for this habitat. Staging areas usually provide protection from the elements and are often spits of land or areas with the shortest distance to cross the Great Lakes. Information Sources OMNRF (NHIC) Agriculture Canada in Ottawa may have list of butterfly experts. Field Naturalist Clubs Toronto Entomologists Association Conservation Authorities 	 The presence of Monarch Use Days (MUD) during fall migration (Aug/Oct). MUD is based on the number of days a site is used by Monarchs, multiplied by the number of individuals using the site. Numbers of butterflies can range from 100-500/day, significant variation can occur between years and multiple years of sampling should occur. Observational studies are to be completed and need to be done frequently during the migration period to estimate MUD. MUD of >5000 or >3000 with the presence of Painted Ladies or Red Admiral's is to be considered significant. SWHMiST Index #16 provides development effects and mitigation measures. 	Not located within 5km of Lake Ontario.
Landbird Migratory Stopover Areas Rationale: Sites with a high diversity of species as well as high numbers are most significant.	All migratory songbirds. Canadian Wildlife Service Ontario website. All migratory songbirds. Canadian Wildlife Service Ontario website:	All Ecosites associated with these ELC Community Series; FOC FOM FOD SWC SWM SWD	Woodlots need to be >10 ha in size and within 5 km of Lake Ontario. • If multiple woodlands are located along the shoreline those Woodlands <2km from Lake Ontario are more significant. • Sites have a variety of habitats; forest, grassland and wetland complexes. • The largest sites are more significant. • Woodlots and forest fragments are important habitats to migrating birds, these features located along the shore and located within 5km of Lake Ontario are Candidate SWH. Information Sources • Bird Studies Canada • Ontario Nature • Local birders and naturalist club • Ontario Important Bird Areas (IBA) Program	 Studies confirm: Use of the habitat by >200 birds/day and with >35 spp with at least 10 bird spp. recorded on at least 5 different survey dates. This abundance and diversity of migrant bird species is considered above average and significant. Studies should be completed during spring (Apr./May) and fall (Aug/Oct) migration using standardized assessment techniques. Evaluation methods to follow "Bird and Bird Habitats: Guidelines for Wind Power Projects". SWHMiST Index #9 provides development effects. 	Not located within 5km of Lake Ontario.

Wildlife Habitat	Wildlife Species		Candidate SWH	Confirmed SWH	Assessment
		ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	
Rationale: Winter habitat for deer is considered to be the main limiting factor for northern deer populations. In winter, deer congregate in "yards" to survive severe winter conditions. Deer yards typically have a long history of annual use by deer, yards typically represent 10-15% of an areas summer range.	White-tailed Deer	Note: OMNRF to determine this habitat. ELC Community Series providing a thermal cover component for a deer yard would include; FOM, FOC, SWM and SWC. Or these ELC Ecosites; CUP2 CUP3 FOD3 CUT	 Deer yarding areas or winter concentration areas (yards) are areas deer move to in response to the onset of winter snow and cold. This is a behavioural response and deer will establish traditional use areas. The yard is composed of two areas referred to as Stratum I and Stratum II. Stratum II covers the entire winter yard area and is usually a mixed or deciduous forest with plenty of browse available for food. Agricultural lands can also be included in this area. Deer move to these areas in early winter and generally, when snow depths reach 20 cm, most of the deer will have moved here. If the snow is light and fluffy, deer may continue to use this area until 30 cm snow depth. In mild winters, deer may remain in the Stratum II area the entire winter. The Core of a deer yard (Stratum I) is located within the Stratum II area and is critical for deer survival in areas where winters become severe. It is primarily composed of coniferous trees (pine, hemlock, cedar, spruce) with a canopy cover of more than 60%. OMNRF determines deer yards following methods outlined in "Selected Wildlife and Habitat Features: Inventory Manual". Woodlots with high densities of deer due to artificial feeding are not significant. 	 No Studies Required: Snow depth and temperature are the greatest influence on deer use of winter yards. Snow depths > 40cm for more than 60 days in a typically winter are minimum criteria for a deer yard to be considered as SWH. Deer Yards are mapped by OMNRF District offices. Locations of Core or Stratum 1 and Stratum 2 Deer yards considered significant by OMNRF will be available at local MNRF offices or via Land Information Ontario (LIO). Field investigations that record deer tracks in winter are done to confirm use (best done from an aircraft). Preferably, this is done over a series of winters to establish the boundary of the Stratum I and Stratum II yard in an "average" winter. MNRF will complete these field investigations. If a SWH is determined for Deer Wintering Area or if a proposed development is within Stratum II yarding area then Movement Corridors are to be considered as outlined in Table 1.4.1 of this Schedule. SWHMiST Index #2 provides development effects and mitigation measures. 	See Deer Winter Congregation Area assessment below. Not identified as a Deer Yarding Area by MNR.
Deer Winter Congregation Areas Rationale: Deer movement during winter in the southern areas of Ecoregion 6E are not constrained by snow depth, however deer will annually congregate in large numbers in suitable woodlands to reduce or avoid the impacts of winter conditions.	White-tailed Deer	All Forested Ecosites with these ELC Community Series; FOC FOM FOD SWC SWM SWD Conifer plantations much smaller than 50 ha may also be used.	 Woodlots will typically be >100 ha in size. Woodlots <100ha may be considered as significant based on MNRF studies or assessment. Deer movement during winter in the southern areas of Ecoregion 6E are not constrained by snow depth, however deer will annually congregate in large numbers in suitable woodlands. If deer are constrained by snow depth refer to the Deer Yarding Area habitat within Table 1.1 of this Schedule. Large woodlots > 100ha and up to 1500 ha are known to be used annually by densities of deer that range from 0.1-1.5 deer/ha. Woodlots with high densities of deer due to artificial feeding are not significant. Information Sources MNRF District Offices LIO/NRVIS 	 Studies confirm: Deer management is an MNRF responsibility, deer winter congregation areas considered significant will be mapped by MNRF. Use of the woodlot by white-tailed deer will be determined by MNRF, all woodlots exceeding the area criteria are significant, unless determined not to be significant by MNRF. Studies should be completed during winter (Jan/Feb) when >20cm of snow is on the ground using aerial survey techniques, ground or road surveys. or a pellet count deer density survey. If a SWH is determined for Deer Wintering Area or if a proposed development is within Stratum II yarding area then Movement Corridors are to be considered as outlined in Table 1.4.1 of this Schedule. SWHMiST Index #2 provides development effects and mitigation measures. 	

AEC24-153
Table 1.2.1 Rare Vegetation Communities

Rare Vegetation				Confirmed SWH	Assessment
Community	ELC Ecosite Code	Habitat Description	Detailed Information and Sources	Defining Criteria	
Cliffs and Talus Slopes Rationale: Cliffs and Talus Slopes are extremely rare habitats in Ontario.	Any ELC Ecosite within Community Series: TAO TAS TAT CLO CLS CLT	A Cliff is vertical to near vertical bedrock >3m in height. A Talus Slope is rock rubble at the base of a cliff made up of coarse rocky debris.	 Most cliff and talus slopes occur along the Niagara Escarpment. Information Sources The Niagara Escarpment Commission has detailed information on location of these habitats. OMNRF District Natural Heritage Information Center (NHIC) has location information available on their website Field Naturalist clubs Conservation Authorities 	 Confirm any ELC Vegetation Type for Cliffs or Talus Slopes SWHMiST Index #21 provides development effects and mitigation measures. 	No cliffs or talus slopes identified during the field program.
Rationale: Sand barrens are rare in Ontario and support rare species. Most Sand Barrens have been lost due to cottage development and forestry	ELC Ecosites: SBO1 SBS1 SBT1 Vegetation cover varies from patchy and barren to continuous meadow (SBO1), thicket-like (SBS1), or more closed and treed (SBT1). Tree cover always ≤ 60%.	Sand Barrens typically are exposed sand, generally sparsely vegetated and caused by lack of moisture, periodic fires and erosion. Usually located within other types of natural habitat such as forest or savannah. Vegetation can vary from patchy and barren to tree covered, but less than 60%.	A sand barren area >0.5ha in size. Information Sources MNRF Districts Natural Heritage Information Center (NHIC) has location information available on their website. Field Naturalist clubs Conservation Authorities	 Confirm any ELC Vegetation Type for Sand Barrens Site must not be dominated by exotic or introduced species (<50% vegetative cover are exotic sp.) SWHMiST Index #20 provides development effects and mitigation measures. 	No sand barrens identified during the field program.
Rationale: Alvars are extremely rare habitats in Ecoregion 6E. Most alvars in Ontario are in Ecoregions 6E and 7E. Alvars in 6E are small and highly localized just north of the Palaeozoic-Precambrian contact.	ALO1 ALS1 ALT1 FOC1 FOC2 CUM2 CUS2 CUT2-1 CUW2 Five Alvar Species: 1) Carex crawei 2) Panicum philadelphicum 3) Eleocharis compressa 4) Scutellaria parvula 5) Trichostema brachiatum These indicator species are very specific to Alvars within Ecoregion 6E.	An alvar is typically a level, mostly unfractured calcareous bedrock feature with a mosaic of rock pavements and bedrock overlain by a thin veneer of soil. The hydrology of alvars is complex, with alternating periods of inundation and drought. Vegetation cover varies from sparse lichen-moss associations to grasslands and shrublands and comprising a number of characteristic or indicator plants. Undisturbed alvars can be phytoand zoogeographically diverse, supporting many uncommon or are relict plant and animal species. Vegetation cover varies from patchy to barren with a less than 60% tree cover.	An Alvar site > 0.5 ha in size. Information Sources Alvars of Ontario (2000), Federation of Ontario Naturalists. Ontario Nature – Conserving Great Lakes Alvars. Natural Heritage Information Center (NHIC) has location information available on their website OMNRF Districts Field Naturalist clubs Conservation Authorities	 Field studies that identify four of the five Alvar Indicator Species at a Candidate Alvar site is Significant. Site must not be dominated by exotic or introduced species (<50% vegetative cover are exotic sp.). The alvar must be in excellent condition and fit in with surrounding landscape with few conflicting land uses. SWHMiST Index #17 provides development effects and mitigation measures. 	No alvar identified during the field program.

Dana Vasstatias		Co., 3:3-4- 6	NA/II	Configured CWII	Aggaggmant
Rare Vegetation	EL C E 24 - C - 1 -	Candidate S		Confirmed SWH	Assessment
Community	ELC Ecosite Code	Habitat Description	Detailed Information and Sources	Defining Criteria	N 11 1 6 1 11 1 1 1
Rationale: Due to historic logging practices, extensive old growth forest is rare in the Ecoregion. Interior habitat provided by old growth forests is required by many wildlife species.	Forest Community Series: FOD FOC FOM SWD SWC SWM	Old Growth forests are characterized by heavy mortality or turnover of over-storey trees resulting in a mosaic of gaps that encourage development of a multi-layered canopy and an abundance of snags and downed woody debris.	Woodland areas 30 ha or greater in size or with at least 10 ha interior habitat assuming 100 m buffer at edge of forest. Information Sources OMNRF Forest Resource Inventory mapping OMNRF Districts. Field Naturalist clubs Conservation Authorities Sustainable Forestry Licence (SFL) companies will possibly know locations through field operations. Municipal forestry departments	 Field Studies will determine: If dominant trees species are >140 years old, then the area containing these trees is Significant Wildlife Habitat. The forested area containing the old growth characteristics will have experienced no recognizable forestry activities (cut stumps will not be present). The area of forest ecosites combined or an ecoelement within an ecosite that contains the old growth characteristics is the SWH. Determine ELC vegetation types for the forest area containing the old growth characteristics. SWHMiST Index #23 provides development effects and mitigation measures. 	No old growth forest within the study area.
Savannah Rationale: Savannahs are extremely rare habitats in Ontario.	TPS1 TPS2 TPW1 TPW2 CUS2	A Savannah is a tallgrass prairie habitat that has tree cover between 25 – 60%.	No minimum size to site. Site must be restored or a natural site. Remnant sites such as railway right of ways are not considered to be SWH. Information Sources Natural Heritage Information Center (NHIC) has location information available on their website OMNRF Districts Field Naturalist clubs Conservation Authorities	Field studies confirm one or more of the Savannah indicator species listed in Appendix N should be present. Note: Savannah plant spp. list from Ecoregion 6E should be used. • Area of the ELC Ecosite is the SWH. • Site must not be dominated by exotic or introduced species (<50% vegetative cover are exotic sp.). • SWHMiST Index #18 provides development effects and mitigation measures.	No savannah identified during the field program.
Tallgrass Prairie Rationale: Tallgrass Prairies are extremely rare habitats in Ontario.	TPO1 TPO2	A Tallgrass Prairie has ground cover dominated by prairie grasses. An open Tallgrass Prairie habitat has < 25% tree cover.	No minimum size to site. Site must be restored or a natural site. Remnant sites such as railway right of ways are not considered to be SWH. Information Sources Natural Heritage Information Center (NHIC) has location information available on their website OMNRF Districts Field Naturalist clubs Conservation Authorities	 Field studies confirm one or more of the Prairie indicator species listed in Appendix N should be present. Note: Prairie plant spp. list from Ecoregion 6E should be used. Area of the ELC Ecosite is the SWH. Site must not be dominated by exotic or introduced species (<50% vegetative cover are exotic sp.). SWHMiST Index #19 provides development effects and mitigation measures. 	No tallgrass prairie identified during the field program.
Other Rare Vegetation Communities Rationale: Plant communities that often contain rare species which depend on the habitat for survival.	Provincially Rare S1, S2 and S3 vegetation communities are listed in Appendix M of the SWHTG. Any ELC Ecosite Code that has a possible ELC Vegetation Type that is Provincially Rare is Candidate SWH.	Rare Vegetation Communities may include beaches, fens, forest, marsh, barrens, dunes and swamps.	ELC Ecosite codes that have the potential to be a rare ELC Vegetation Type as outlined in appendix M The OMNRF/NHIC will have up to date listing for rare vegetation communities. Information Sources Natural Heritage Information Center (NHIC) has location information available on their website OMNRF Districts Field Naturalist clubs Conservation Authorities	 Field studies should confirm if an ELC Vegetation Type is a rare vegetation community based on listing within Appendix M of SWHTG. Area of the ELC Vegetation Type polygon is the SWH. SWHMiST Index #37 provides development effects and mitigation measures. 	No rare vegetation communities identified during the field program.

AEC24-153

1.2.2 Specialized Habitat for Wildlife

Wildlife Habitat	Wildlife Species		Candidate SHW	Confirmed SWH	Assessment
	_	ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria]
Waterfowl Nesting Area Rationale: Important to local waterfowl populations, sites with greatest number of species and highest number of individuals are significant.	American Black Duck Northern Pintail Northern Shoveler Gadwall Blue-winged Teal Green-winged Teal Wood Duck Hooded Merganser Mallard	All upland habitats located adjacent to these wetland ELC Ecosites are Candidate SWH: MAS1 MAS2 MAS3 SAS1 SAM1 SAF1 MAM1 MAM2 MAM3 MAM4 MAM5 MAM6 SWT1 SWT2 SWD1 SWD2 SWD3 SWD4 Note: includes adjacency to Provincially Significant	A waterfowl nesting area extends 120 m from a wetland (> 0.5 ha) or a wetland (>0.5ha) and any small wetlands (0.5ha) within 120m or a cluster of 3 or more small (<0.5 ha) wetlands within 120 m of each individual wetland where waterfowl nesting is known to occur. • Upland areas should be at least 120 m wide so that predators such as racoons, skunks, and foxes have difficulty finding nests. • Wood Ducks and Hooded Mergansers utilize large diameter trees (>40cm dbh) in woodlands for cavity nest sites. Information Sources • Ducks Unlimited staff may know the locations of particularly productive nesting sites. • OMNRF Wetland Evaluations for indication of significant waterfowl nesting habitat. • Reports and other information available from Conservation Authorities.	 Studies confirmed: Presence of 3 or more nesting pairs for listed species excluding Mallards, or; Presence of 10 or more nesting pairs for listed species including Mallards. Any active nesting site of an American Black Duck is considered significant. Nesting studies should be completed during the spring breeding season (April - June). Evaluation methods to follow "Bird and Bird Habitats: Guidelines for Wind Power Projects". A field study confirming waterfowl nesting habitat will determine the boundary of the waterfowl nesting habitat for the SWH, this may be greater or less than 120 m from the wetland and will provide enough habitat for waterfowl to successfully nest. SWHMiST Index #25 provides development effects and mitigation measures. 	Wetlands and open water features do not exceed the minimum 0.5ha size requirement. Two (2) wetlands <0.5ha are identified, however a cluster of three (3) or more smaller wetlands are required for consideration as candidate Waterfowl Nesting Areas.
Bald Eagle and Osprey Nesting, Foraging and Perching Habitat Rationale: Nest sites are fairly uncommon in Ecoregion 6E and are used annually by these species. Many suitable nesting locations may be lost due to increasing shoreline development pressures and scarcity of habitat.	Osprey Special Concern Bald Eagle	Wetlands ELC Forest Community Series: FOD, FOM, FOC, SWD, SWM and SWC directly adjacent to riparian areas – rivers, lakes, ponds and wetlands	Nests are associated with lakes, ponds, rivers or wetlands along forested shorelines, islands, or on structures over water. Osprey nests are usually at the top a tree whereas Bald Eagle nests are typically in super canopy trees in a notch within the tree's canopy. Nests located on man-made objects are not to be included as SWH (e.g. telephone poles and constructed nesting platforms). Information Sources Natural Heritage Information Center (NHIC) compiles all known nesting sites for Bald Eagles in Ontario. MNRF values information (LIO/NRVIS) will list known nesting locations. Note: data from NRVIS is provided as a point and does not represent all the habitat. Nature Counts, Ontario Nest Records Scheme data. OMNRF Districts Check the Ontario Breeding Bird Atlas or Rare Breeding Birds in Ontario for species documented Reports and other information available from Conservation Authorities.	 Studies confirm the use of these nests by: One or more active Osprey or Bald Eagle nests in an area. Some species have more than one nest in a given area and priority is given to the primary nest with alternate nests included within the area of the SWH. For an Osprey, the active nest and a 300 m radius around the nest or the contiguous woodland stand is the SWH, maintaining undisturbed shorelines with large trees within this area is important. For a Bald Eagle the active nest and a 400-800 m radius around the nest is the SWH. Area of the habitat from 400-800m is dependent on site lines from the nest to the development and inclusion of perching and foraging habitat. To be significant a site must be used annually. When found inactive, the site must be known to be inactive for > 3 years or suspected of not being used for >5 years before being considered not significant. Observational studies to determine nest site use, perching sites and foraging areas need to be done from mid March to mid August. Evaluation methods to follow "Bird and Bird Habitats: Guidelines for Wind Power Projects". SWHMiST Index #26 provides development effects and 	Large wetlands, rivers, lakes or similar open water features are not located within the study area limits. No active or inactive Osprey or Bald Eagle nests were observed during the field survey program.

Wildlife Habitat	Wildlife Species		Candidate SHW	Confirmed SWH	Assessment
	•	ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	1
Woodland Raptor Nesting Habitat Rationale: Nests sites for these species are rarely identified; these area sensitive habitats and are often used annually by these species.	Northern Goshawk Cooper's Hawk Sharp-shinned Hawk Red-shouldered Hawk Barred Owl Broad-winged Hawk	May be found in all forested ELC Ecosites. May also be found in SWC, SWM, SWD and CUP3	 All natural or conifer plantation woodland/forest stands >30ha with >10ha of interior habitat. Interior habitat determined with a 200m buffer Stick nests found in a variety of intermediate-aged to mature conifer, deciduous or mixed forests within tops or crotches of trees. Species such as Coopers Hawk nest along forest edges sometimes on peninsulas or small off-shore islands. In disturbed sites, nests may be used again, or a new nest will be in close proximity to old nest. Information Sources OMNRF Districts. Check the Ontario Breeding Bird Atlas or Rare Breeding Birds in Ontario for species documented. Check data from Bird Studies Canada. Reports and other information available from Conservation Authorities. 	 Studies confirm: Presence of 1 or more active nests from species list is considered significant. Red-shouldered Hawk and Northern Goshawk – A 400m radius around the nest or 28 ha area of habitat is the SWH. (The 28 ha habitat area would be applied where optimal habitat is irregularly shaped around the nest). Barred Owl – A 200m radius around the nest is the SWH. Broad-winged Hawk and Coopers Hawk– A 100m radius around the nest is the SWH. Sharp-Shinned Hawk – A 50m radius around the nest is the SWH. Conduct field investigations from mid-March to end of May. The use of call broadcasts can help in locating territorial. (courting/nesting) raptors and facilitate the discovery of nests by narrowing down the search area. SWHMiST Index #27 provides development effects and mitigation measures. 	No raptor nesting activity was observed during the field survey program. No portion of the study area occurs within interior forest located >200m from a woodland edge, or is connected to a woodland with interior habitat. No suitable habitat within the study area.
Turtle Nesting Areas Rationale: These habitats are rare and when identified will often be the only breeding site for local populations of turtles.	Midland Painted Turtle Special Concern Species Northern Map Turtle Snapping Turtle	Exposed mineral soil (sand or gravel) areas adjacent (<100m) or within the following ELC Ecosites: MAS1 MAS2 MAS3 SAS1 SAM1 SAF1 BOO1 FEO1	 Best nesting habitat for turtles are close to water and away from roads and sites less prone to loss of eggs by predation from skunks, raccoons or other animals. For an area to function as a turtle-nesting area, it must provide sand and gravel that turtles are able to dig in and are located in open, sunny areas. Nesting areas on the sides of municipal or provincial road embankments and shoulders are not SWH. Sand and gravel beaches adjacent to undisturbed shallow weedy areas of marshes, lakes, and rivers are most frequently used. Information Sources Use Ontario Soil Survey reports and maps to help find suitable substrate for nesting turtles (well-drained sands and fine gravels). Check the Ontario Herpetofaunal Summary Atlas records or other similar atlases for uncommon turtles; location information may help to find potential nesting habitat for them. Natural Heritage Information Center (NHIC) Field Naturalist clubs 	 Studies confirm: Presence of 5 or more nesting Midland Painted Turtles. One or more Northern Map Turtle or Snapping Turtle nesting is a SWH. The area or collection of sites within an area of exposed mineral soils where the turtles nest, plus a radius of 30-100m around the nesting area dependant on slope, riparian vegetation and adjacent land use is the SWH. Travel routes from wetland to nesting area are to be considered within the SWH as part of the 30-100m area of habitat. Field investigations should be conducted in prime nesting season typically late spring to early summer. Observational studies observing the turtles nesting is a recommended method. SWHMiST Index #28 provides development effects and mitigation measures for turtle nesting habitat. 	No exposed mineral soils within 100m of permanent or semi-permanent standing water that could be utilized for turtle nesting. No suitable habitat within the study area.

Wildlife Habitat	Wildlife Species		Candidate SHW	Confirmed SWH	Assessment
	•	ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	
Rationale: Seeps/Springs are typical of headwater areas and are often at the source of coldwater streams.	Wild Turkey Ruffed Grouse Spruce Grouse White-tailed Deer Salamander spp.	Seeps/Springs are areas where ground water comes to the surface. Often they are found within headwater areas within forested habitats. Any forested Ecosite within the headwater areas of a stream could have seeps/springs.	Any forested area (with <25% meadow/field/pasture) within the headwaters of a stream or river system. • Seeps and springs are important feeding and drinking areas especially in the winter will typically support a variety of plant and animal species. Information Sources • Topographical Map • Thermography • Hydrological surveys conducted by Conservation Authorities and MOE. • Field Naturalists clubs and landowners. • Municipalities and Conservation Authorities may have drainage maps and headwater areas mapped.	Field Studies confirm: Presence of a site with 2 or more seeps/springs should be considered SWH. The area of a ELC forest ecosite or an ecoelement within ecosite containing the seeps/springs is the SWH. The protection of the recharge area considering the slope, vegetation, height of trees and groundwater condition need to be considered in delineation the habitat. SWHMiST Index #30 provides development effects and mitigation measures.	No seeps and springs identified during Azimuth's field investigations.
Amphibian Breeding Habitat (Woodland). Rationale: These habitats are extremely important to amphibian biodiversity within a landscape and often represent the only breeding habitat for local amphibian populations.	Eastern Newt Blue-spotted Salamander Spotted Salamander Gray Treefrog Spring Peeper Western Chorus Frog Wood Frog	All Ecosites associated with these ELC Community Series; FOC FOM FOD SWC SWM SWD Breeding pools within the woodland or the shortest distance from forest habitat are more significant because they are more likely to be used due to reduced risk to migrating amphibians.	 Presence of a wetland, pond or woodland pool (including vernal pools) >500m² (about 25m diameter) within or adjacent (within 120m) to a woodland (no minimum size). Some small wetlands may not be mapped and may be important breeding pools for amphibians. Woodlands with permanent ponds or those containing water in most years until mid-July are more likely to be used as breeding habitat. Information Sources Ontario Herpetofaunal Summary Atlas (or other similar atlases) for records. Local landowners may also provide assistance as they may hear spring-time choruses of amphibians on their property. OMNRF District OMNRF wetland evaluations Field Naturalist clubs Canadian Wildlife Service Amphibian Road Call Survey Ontario Vernal Pool Association: http://www.ontariovernalpools.org 	 Studies confirm; Presence of breeding population of 1 or more of the listed newt/salamander species or 2 or more of the listed frog species with at least 20 individuals (adults or eggs masses) or 2 or more of the listed frog species with Call Level Codes of 3. A combination of observational study and call count surveys will be required during the spring (March-June) when amphibians are concentrated around suitable breeding habitat within or near the woodland/wetlands. The habitat is the wetland area plus a 230m radius of woodland area. If a wetland area is adjacent to a woodland, a travel corridor connecting the wetland to the woodland is to be included in the habitat. SWHMiST Index #14 provides development effects and mitigation measures. 	Refer to the amphibian habitat assessment described under Amphibian Breeding Habitat (Wetland) below.

Wildlife Habitat	Wildlife Species		Candidate SHW	Confirmed SWH	ASSESSMENT AEC2
		ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	
Amphibian Breeding Habitat (Wetlands) Rationale: Wetlands supporting breeding for these amphibian species are extremely important and fairly rare within Central Ontario landscapes.	Eastern Newt American Toad Spotted Salamander Four-toed Salamander Blue-spotted Salamander Gray Treefrog Western Chorus Frog Northern Leopard Frog Pickerel Frog Green Frog Mink Frog Bullfrog	ELC Community Classes SW, MA, FE, BO, OA and SA. Typically these wetland ecosites will be isolated (>120m) from woodland ecosites, however larger wetlands containing predominantly aquatic species (e.g. Bull Frog) may be adjacent to woodlands.	 Wetlands>500m² (about 25m diameter), supporting high species diversity are significant; some small or ephemeral habitats may not be identified on MNRF mapping and could be important amphibian breeding habitats. Presence of shrubs and logs increase significance of pond for some amphibian species because of available structure for calling, foraging, escape and concealment from predators. Bullfrogs require permanent water bodies with abundant emergent vegetation. Information Sources Ontario Herpetofaunal Summary Atlas (or other similar atlases) Canadian Wildlife Service Amphibian Road Surveys and Backyard Amphibian Call Count. OMNRF Districts and wetland evaluations Reports and other information available from Conservation Authorities 	 Studies confirm: Presence of breeding population of 1 or more of the listed newt/salamander species or 2 or more of the listed frog/toad species with at least 20 individuals (adults or eggs masses) or 2 or more of the listed frog/toad species with Call Level Codes of 3. or; Wetland with confirmed breeding Bullfrogs are significant. The ELC ecosite wetland area and the shoreline are the SWH. 	The evening amphibian breeding survey program (April, May, June 2024) was focused to the wetland unit in the northeast portion of the property. The results of the survey program identified breeding amphibians within the northeast unit as follows: • Gray Treefrog (3 individuals calling; May 2024) • Green Frog (3 individuals calling; June 2024) The minimum threshold for consideration as SWH requires demonstrated breeding by two (2) or more of the listed species with at least 20 breeding individuals documented. The survey program did not detect >20 breeding individuals of listed species and therefore is not considered Candidate SWH for Amphibian Breeding Habitat (Wetlands).
Woodland Area-Sensitive Bird Breeding Habitat Rationale: Large, natural blocks of mature woodland habitat within the settled areas of Southern Ontario are important habitats for area sensitive interior forest song birds.	Yellow-bellied Sapsucker Red-breasted Nuthatch Veery Blue-headed Vireo Northern Parula Black-throated Green Warbler Blackburnian Warbler Black-throated Blue Warbler Ovenbird Scarlet Tanager Winter Wren Special Concern: Cerulean Warbler Canada Warbler	All Ecosites associated with these ELC Community Series; FOC FOM FOD SWC SWM SWD	Habitats where interior forest breeding birds are breeding, typically large mature (>60 yrs old) forest stands or woodlots >30 ha. • Interior forest habitat is at least 200 m from forest edge habitat. Information Sources • Local bird clubs. • Canadian Wildlife Service (CWS) for the location of forest bird monitoring. • Bird Studies Canada conducted a 3-year study of 287 woodlands to determine the effects of forest fragmentation on forest birds and to determine what forests were of greatest value to interior species. • Reports and other information available from Conservation Authorities.	 Presence of nesting or breeding pairs of 3 or more of the listed wildlife species. Note: any site with breeding Cerulean Warblers or Canada Warblers is to be considered SWH. Conduct field investigations in spring and early summer when birds are singing and defending their territories. Evaluation methods to follow "Bird and Bird Habitats: Guidelines for Wind Power Projects". SWHMiST Index #34 provides development effects and mitigation measures. 	No portion of the study area occurs within interior forest located >200m from a woodland edge, or is connected to a woodland with interior habitat. No suitable habitat within the study area.

1.3 Habitat for Species of Conservation Concern (Not including Endangered or Threatened Species)

Wildlife Habitat	Wildlife Species		Candidate SHW	Confirmed SWH	Assessment
	_	ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	
Marsh Breeding	American Bittern	MAM1	Nesting occurs in wetlands.	Studies confirm:	One (1) Green Heron was observed
Rationale; Wetlands for these bird species are typically productive and fairly rare in	Virginia Rail Sora Common Moorhen American Coot Pied-billed Grebe Marsh Wren Sedge Wren	MAM2 MAM3 MAM4 MAM5 MAM6 SAS1 SAM1	 All wetland habitat is to be considered as long as there is shallow water with emergent aquatic vegetation present. For Green Heron, habitat is at the edge of water such as sluggish streams, ponds and marshes sheltered by shrubs and trees. Less frequently, it may be found in upland shrubs or forest a considerable distance from water. Information Sources 	 Presence of 5 or more nesting pairs of Sedge Wren or Marsh Wren or 1 pair of Sandhill Cranes; or breeding by any combination of 5 or more of the listed species. Note: any wetland with breeding of 1 or more Black Terns, Trumpeter Swan, Green Heron or Yellow Rail is SWH. Area of the ELC ecosite is the SWH. Breeding surveys should be done in May/June when these 	flying over the study area on July 31, 2024, however no evidence of nesting was detected throughout the course of the field program. No other listed species were detected throughout the course of the field program.
Southern Ontario landscapes.	Common Loon Sandhill Crane Green Heron Trumpeter Swan Special Concern: Black Tern Yellow Rail	SAF1 FEO1 BOO1 For Green Heron: All SW, MA and CUM1 sites.	 OMNRF District and wetland evaluations. Field Naturalist clubs Natural Heritage Information Center (NHIC) Records. Reports and other information available from Conservation Authorities. Ontario Breeding Bird Atlas 	 species are actively nesting in wetland habitats. Evaluation methods to follow "Bird and Bird Habitats: Guidelines for Wind Power Projects". SWHMiST Index #35 provides development effects and mitigation measures. 	
Open Country Bird	Upland Sandpiper	CUM1	Large grassland areas (includes natural and cultural fields and	Field Studies confirm:	The study area does not provide habitat
Breeding Habitat	Grasshopper	CUM2	meadows) >30 ha.	• Presence of nesting or breeding of 2 or more of the listed	for grassland birds exceeding the
Sources Defining	Sparrow		• Grasslands not Class 1 or 2 agricultural lands, and not being	species.	minimum 30ha threshold. No suitable
Criteria	Vesper Sparrow Northern Harrier		actively used for farming (i.e. no row cropping or intensive hay or livestock pasturing in the last 5 years).	• A field with 1 or more breeding Short-eared Owls is to be considered SWH.	habitat within the study area.
Rationale;	Savannah Sparrow		Grassland sites considered significant should have a history of	• The area of SWH is the contiguous ELC ecosite field areas.	
This wildlife habitat			longevity, either abandoned fields, mature hayfields and	• Conduct field investigations of the most likely areas in spring	
is declining	Special Concern		pasturelands that are at least 5 years or older.	and early summer when birds are singing and defending their	
throughout Ontario	Short-eared Owl		The Indicator bird species are area sensitive requiring larger	territories.	
and North America.			grassland areas than the common grassland species.	• Evaluation methods to follow "Bird and Bird Habitats:	
Species such as the			Information Sources	Guidelines for Wind Power Projects".	
Upland Sandpiper			Agricultural land classification maps, Ministry of Agriculture.	SWHMiST Index #32 provides development effects and	
have declined			• Local bird clubs.	mitigation measures.	
significantly the past			Ontario Breeding Bird Atlas		
40 years based on			Reports and other information available from Conservation		
CWS (2004) trend			Authorities.		
records.					
Shrub/Early	Indicator Spp:	CUT1	Large field areas succeeding to shrub and thicket habitats>10ha in	Field Studies confirm:	The study area does not provide habitat
Successional Bird	Brown Thrasher	CUT2	size.	• Presence of nesting or breeding of 1 of the indicator species	for shrub/early successional birds
Breeding Habitat	Clay-coloured	CUS1	• Shrub land or early successional fields, not class 1 or 2	and at least 2 of the common species.	exceeding the minimum 10ha threshold.
D 41 1	Sparrow	CUS2	agricultural lands, not being actively used for farming (i.e. no	A habitat with breeding Yellow-breasted Chat or Golden-	No suitable habitat within the study area.
Rationale;	Common Spp.	CUW1	row-cropping, haying or live-stock pasturing in the last 5 years).	winged Warbler is to be considered as Significant Wildlife	
This wildlife habitat	Field Sparrow	CUW2	• Shrub thicket habitats (>10 ha) are most likely to support and	Habitat.	
is declining	Black-billed	D (1 C 1 1	sustain a diversity of these species.	• The area of the SWH is the contiguous ELC ecosite	
throughout Ontario	Cuckoo	Patches of shrub	• Shrub and thicket habitat sites considered significant should have	field/thicket area.	
and North America. The Brown Thrasher	Eastern Towhee	ecosites can be	a history of longevity, either abandoned fields or pasturelands.	• Conduct field investigations of the most likely areas in spring	
	Willow Flycatcher	complexed into a	Information Sources	and early summer when birds are singing and defending their	
has declined	Special Concern:	larger habitat for some bird species	Agricultural land classification maps, Ministry of Agriculture.	territories.	
significantly over the past 40 years based	Yellow-breasted	some ond species	• Local bird clubs	• Evaluation methods to follow "Bird and Bird Habitats:	
on CWS (2004)	Chat		Ontario Breeding Bird Atlas	Guidelines for Wind Power Projects".	
trend records.	Golden-winged		Reports and other information available from Conservation	SWHMiST Index #33 provides development effects and	
della records.	Warbler		Authorities.	mitigation measures.	

Wildlife Habitat	Wildlife Species		Candidate SHW	Confirmed SWH	Assessment
,,	F	ELC Ecosite Codes	Habitat Criteria and Information Sources	Defining Criteria	
Terrestrial Crayfish Rationale: Terrestrial Crayfish are only found within SW Ontario in Canada and their habitats are very rare.	Chimney or Digger Crayfish; (Fallicambarus fodiens) Devil Crayfish or Meadow Crayfish; (Cambarus Diogenes)	MAM1 MAM2 MAM3 MAM4 MAM5 MAM6 MAS1 MAS2 MAS3 SWD SWT SWM CUM1 with inclusions of above meadow marsh or swamp ecosites can be used by terrestrial crayfish.	Wet meadow and edges of shallow marshes (no minimum size) should be surveyed for terrestrial crayfish. Constructs burrows in marshes, mudflats, meadows, the ground can't be too moist. Can often be found far from water. Both species are a semi-terrestrial burrower which spends most of its life within burrows consisting of a network of tunnels. Usually the soil is not too moist so that the tunnel is well formed. Information Sources Information sources from "Conservation Status of Freshwater Crayfishes" by Dr. Premek Hamr for the WWF and CNF March 1998.	Studies Confirm: Presence of 1 or more individuals of species listed or their chimneys (burrows) in suitable meadow marsh, swamp or moist terrestrial sites. Area of ELC ecosite or an ecoelement area of meadow marsh or swamp within the larger ecosite area is the SWH. Surveys should be done April to August in temporary or permanent water. Note the presence of burrows or chimneys are often the only indicator of presence, observance or collection of individuals is very difficult. SWHMiST Index #36 provides development effects and mitigation measures.	No crayfish chimneys were documented during Azimuth's field investigations.
Special Concern and Rare Wildlife Species Rationale: These species are quite rare or have experienced significant population declines in Ontario.	All Special Concern and Provincially Rare (S1-S3, SH) plant and animal species. Lists of these species are tracked by the Natural Heritage Information Centre.	All plant and animal element occurrences (EO) within a 1 or 10km grid. Older element occurrences were recorded prior to GPS being available, therefore location information may lack accuracy.	 When an element occurrence is identified within a 1 or 10 km grid for a Special Concern or provincially Rare species; linking candidate habitat on the site needs to be completed to ELC Ecosites Information Sources Natural Heritage Information Centre (NHIC) will have Special Concern and Provincially Rare (S1-S3, SH) species lists with element occurrences data. NHIC Website "Get Information": http://nhic.mnr.gov.on.ca Ontario Breeding Bird Atlas Expert advice should be sought as many of the rare spp. have little information available about their requirements. 	 Assessment/inventory of the site for the identified special concern or rare species needs to be completed during the time of year when the species is present or easily identifiable. The area of the habitat to the finest ELC scale that protects the habitat form and function is the SWH, this must be delineated through detailed field studies. The habitat needs be easily mapped and cover an important life stage component for a species <i>e.g.</i> specific nesting habitat or foraging habitat. SWHMiST Index #37 provides development effects and mitigation measures. 	Special Concern species including Monarch were detected during the site investigation.

1.4 Animal Movement Corridors

Wildlife Habitat Wildlife Species		Candidate SHW		Confirmed SWH	Assessment	
	_	ELC Ecosite	Habitat Criteria and Information Sources		Defining Criteria	
Amphibian Movement Corridors Rationale: Movement corridors for amphibians moving from their terrestrial habitat to breeding habitat can be extremely important for local populations.	Eastern Newt American Toad Spotted Salamander Four-toed Salamander Blue-spotted Salamander Gray Treefrog Western Chorus Frog Northern Leopard Frog Pickerel Frog Green Frog Mink Frog Bullfrog	Corridors may be found in all ecosites associated with water. Corridors will be determined based on identifying the significant breeding habitat for these species in Table 1.1	 Movement corridors between breeding habitat and summer habitat. Movement corridors must be determined when Amphibian breeding habitat is confirmed as SWH from Table 1.2.2 (Amphibian Breeding Habitat –Wetland) of this Schedule. Information Sources MNRF District Office Natural Heritage Information Center (NHIC) Reports and other information available from Conservation Authorities. Field Naturalist Clubs 	when spentering Corridor several Corridor and und Corridor both side woodlar Shorter corridor to and f SWHM	Studies must be conducted at the time of year species are expected to be migrating or ng breeding sites. lors should consist of native vegetation, with all layers of vegetation. lors unbroken by roads, waterways or bodies, ndeveloped areas are most significant. dors should have at least 15m of vegetation on ides of waterway or be up to 200m wide of and habitat and with gaps <20m. Exercorridors are more significant than longer ors, however amphibians must be able to get from their summer and breeding habitat. MIST Index #40 provides development effects itigation measures.	No significant Amphibian Breeding Habitat - Wetland function, therefore no potential Amphibian Movement Corridor function within study area.
Deer Movement Corridors Rationale: Corridors important for all species to be able to access seasonally important life-cycle habitats or to access new habitat for dispersing individuals by minimizing their vulnerability while travelling.	White-tailed Deer	Corridors may be found in all forested ecosites. A Project Proposal in Stratum II Deer Wintering Area has potential to contain corridors.	 Movement corridor must be determined when Deer Wintering Habitat is confirmed as SWH from Table 1.1 of this schedule. A deer wintering habitat identified by the OMNRF as SWH in Table 1.1 of this Schedule will have corridors that the deer use during fall migration and spring dispersion. Corridors typically follow riparian areas, woodlots, areas of physical geography (ravines, or ridges). Information Sources MNRF District Office Natural Heritage Information Center (NHIC). Reports and other information available from Conservation Authorities. Field Naturalist Clubs 	deer are concent Corrido be unbr Corrido <20m a 15m of Shorter corridor SWHM	es must be conducted at the time of year when re migrating or moving to and from winter intration areas. Hors that lead to a deer wintering habitat should broken by roads and residential areas. Hors should be at least 200m wide with gaps and if following riparian area with at least of vegetation on both sides of waterway. For corridors are more significant than longer fors. MiST Index #39 provides development effects itigation measures.	No Deer Wintering Habitat present, therefore no potential Deer Movement Corridor function within study area.

1.5 Exceptions for EcoRegion 6E

EcoDistrict	Wildlife Habitat and		Candidate		Confirmed SWH	Assessment
	Species	Ecosites	Habitat Description	Habitat Criteria and Information	Defining Criteria	
Rationale: The Bruce Peninsula has an isolated and distinct population of black bears. Maintenance of large woodland tracts with mast-producing tree species is important for bears.	Mast Producing Areas Black Bear	All Forested habitat represented by ELC Community Series: FOM FOD	 Black bears require forested habitat that provides cover, winter hibernation sites, and mast-producing tree species. Forested habitats need to be large enough to provide cover and protection for black bears. 	Woodland ecosites >30ha with mast-producing tree species, either soft (cherry) or hard (oak and beech). Information Sources Important forest habitat for black bears may be identified by OMNRF.	All woodlands > 30ha with a 50% composition of these ELC Vegetation Types are considered significant: FOM1-1 FOM2-1 FOM3-1 FOD1-2 FOD2-1 FOD2-2 FOD2-3 FOD2-4 FOD4-1 FOD5-2 FOD5-3 FOD5-7 FOD6-5	Site not located on Bruce Peninsula.
					SWHMiST Index #3 provides development effects and mitigation measures.	
Rationale: Sharp-tailed grouse only occur on Manitoulin Island in Eco-region 6E, Leks are an important habitat to maintain their population	Lek Sharp-tailed Grouse	CUM CUS CUT	 The lek or dancing ground consists of bare, grassy or sparse shrubland. There is often a hill or rise in topography. Leks are typically a grassy field/meadow >15ha with adjacent shrublands and >30ha with adjacent deciduous woodland. Conifer trees within 500m are not tolerated. 	Grasslands (field/meadow) are to be >15ha when adjacent to shrubland and >30ha when adjacent to deciduous woodland. • Grasslands are to be undisturbed with low intensities of agriculture (light grazing or late haying) • Leks will be used annually if not destroyed by cultivation or invasion by woody plants or tree planting Information Sources • OMNRF district office • Bird watching clubs • Local landowners • Ontario Breeding Bird Atlas	Studies confirming lek habitat are to be completed from late March to June. • Any site confirmed with sharp-tailed grouse courtship activities is considered significant • The field/meadow ELC ecosites plus a 200 m radius area with shrub or deciduous woodland is the lek habitat • SWHMiST Index #32 provides development effects and mitigation measures	Site not located on Manitoulin Island.



APPENDICES

Appendix A: Municipal Background and Correspondence **Appendix B:** Provincial Background and Correspondence

Appendix C: Nottawasaga Valley Conservation Authority Background

Appendix D: Photographic Record**Appendix E:** Butternut Documentation

Appendix F: 2004 Commercial Facility Drawings **Appendix G:** Proposed Development Concept



APPENDIX A

Municipal Background and Correspondence



SCHEDULE 5.1

To the County of Simcoe Official Plan LAND USE DESIGNATIONS

Designations Reference Data Settlement Area Boundary Settlements **Built Boundaries** Greenlands Special Development Area: Friday Harbour Resort Agricultural Greenbelt Plan - Protected Countryside (Refer to Schedule 5.3.3 For Details) Strategic Settlement Employment Niagara Escarpment Plan Area Areas and Economic Employment Districts (Refer to Schedule 5.3.1 For Details) Lands not subject to this plan Oak Ridges Moraine Conservation Plan Area (Refer to Schedule 5.3.2 For Details) Settlement Area Boundary Under Appeal Provincial Highway General Location of Site-Specific Appeals County Road Lands Subject to Non-Decision Trans Canada Pipeline - Lake Simcoe Protection Plan - Watershed Boundary * Greenbelt Plan - Protected Countryside, Oak Ridges Moraine Conservation Plan Area


and Niagara Escarpment Plan Area are included within the Greenbelt Plan Area

This schedule must be referred to in conjunction with the text of the County of Simcoe

Office Consolidation February 2023

Printed: 2023/02/1







SCHEDULE 5.2.2

To the County of Simcoe Official Plan STREAMS AND EVALUATED WETLANDS

Provincially Significant Wetland

Locally Significant Wetland

Watercourse


Lands not subject to this plan

This schedule must be referred to in conjunction with the text of the County of Simcoe Official Plan - November 25, 2008

Source: Midhurst District MNR Approved by OMB on May 9, 2016

Printed: 2016/05/19







SCHEDULE 5.2.3

To the County of Simcoe Official Plan AREAS OF NATURAL AND SCIENTIFIC INTEREST



ANSI - Provincial

ANSI - Regional

Lands not subject to this plan

This schedule must be referred to in conjunction with the text of the County of Simcoe Official Plan - November 25, 2008 Source: Ministry of Natural Resources

Approved by the OMB on April 19, 2013







Official Plan of the Town of Collingwood SCHEDULE 'A' - Land Use Plan



Legend



····· Industrial Fringe

----- Pretty River Flood Fringe

Secondary Plan Boundary

***** Waste Disposal Assessment Areas

///// Business Park

Downtown Commercial Core

Environment Protection

Highway Commercial

Industrial Park

Light Industrial

Mixed Use Commercial

Industrial

Recreation

//// Regional Commercial District

Residential

Resort Commercial

Restrictive Commercial

Rural

Rural Residential

Shipyards

Special Policy Area- Health

Well Head

Residential-Mixed Use





Official Plan of the Town of Collingwood SCHEDULE 'B' - Environmental Protection-Natural Heritage Resource Areas



Legend

- - - Fish

SCHEDULE B

NATURAL_FE



CATEGORY 1 WETLANDS


CATEGORY 1 WOODLAND

CATEGORY 2 WOODLAND

FISH SPAWNING & NURSERY HABITAT

— SCHEDULE B LINE


---- WATERSHED



County of Simcoe - Web Map



This map, either in whole or in part, may not be reproduced without the written authority from® The Corporation of the County of Simcoe. This map is intended for personal use, has been produced using data from a variety of sources and may not be current or accurate. Produced (in part) under license from: © His Majesty the King in Right of Canada, Department of Natural Resources: © King's Printer, Ontario Ministry of Natural Resources: © Teranet Enterprises Inc. and its suppliers: © Members of the Ontario Geospatial Data Exchange. All rights reserved. THIS IS NOT A





From: <u>Erin Bannon</u>

To: <u>Dan Stuart; Nathan Wukasch</u>

Cc: Meghan Douglas

Subject: Re: AEC24-153 Gateway Centre Collingwood EIS Terms of Reference REVISED (proj3287B)

Date: July 4, 2024 10:05:31 AM
Attachments: oaflcpkgefihkidk.png
bicmgabdieodbffb.png

bicmagbdieodbffb.png mhkjpaklcmpigkbf.png image001.png

Hi Dan.

We're happy to hear that consideration of both the additional background resources and review of EAME habitat will be included within the EIS. The early-June (spring) and late-July or early-August (summer) vegetation survey would also be acceptable assuming reasonable separation between survey dates to ensure capturing appropriate/separate seasonal growing conditions to satisfy a 2-season inventory, which it sounds like is what is planned. To confirm, NRSI is accepting of the ToR with these clarifications and happy to hear they're in the works!

Thanks!

Erin



Erin Bannon B.E.S. Certified Arborist

Terrestrial and Wetland Biologist

Natural Resource Solutions Inc. Proudly Indigenous-owned 415 Phillip Street, Unit C Waterloo, ON N2L 3X2

- (p) 519-725-2227 Ext. 242 (f) 519-725-2575
- (m) 519-998-6068
- (w) www.nrsi.on.ca (e) ebannon@nrsi.on.ca
- @nrsinews in Natural Resource Solutions Inc.

Over 25 years of environmental consulting excellence

On 2024-07-03 8:01 p.m., Dan Stuart wrote:

Hi Nathan,

Azimuth has received the Town's response (via NRSI) regarding our proposed Terms of Reference for the Gateway Centre lands, and generally accepts the comments/additions provided by NRSI. At this time we would like to confirm/clarify the following:

- Additional background resources listed in the first set of bullets (e.g. ORAA, OBBA) will be reviewed and referenced as part of the EIS.
- A two-season vascular plant inventory is proposed as requested in a Terms

of Reference received from NVCA during pre-consultation. In order to capture an adequate complement of vascular plant species throughout the growing season Azimuth intends to carry out vegetation surveys in early-June (already completed) to inventory early-mid season species, and late-July or early-August to inventory mid-late season species.

• Potential habitat function for Eastern Meadowlark will be reviewed as part of the Species at Risk assessment to be included in the EIS.

Please confirm that the Town is accepting of the provided ToR with the above clarifications.

Best regards,



Dan Stuart, M.Env.Sc.

Ecology Lead/Partner
Azimuth Environmental Consulting, Inc.
642 Welham Road Barrie, ON L4N 9A1

Office: 705-721-8451 x208

Cell: 705-794-0975

www.azimuthenvironmental.com

Providing services in hydrogeology, terrestrial and aquatic ecology, environmental engineering, and arborist assessments.

From: Dan Stuart

Sent: June 21, 2024 10:09 AM

To: 'Nathan Wukasch' < nwukasch@collingwood.ca>

Cc: Erin Bannon <u><ebannon@nrsi.on.ca></u>; Meghan Douglas <u><mdouglas@nrsi.on.ca></u> **Subject:** AEC24-153 Gateway Centre Collingwood EIS Terms of Reference REVISED

(proj3287B)

Hi Nathan,

Please see Azimuth's revised Terms of Reference regarding the Environmental Impact Study for the Gateway Centre property in the Town of Collingwood, that incorporates 3x evening amphibian breeding surveys (April, May, June), already completed.

Azimuth has been retained to complete an Environmental Impact Study (EIS) for The Gateway Centre located at the northeast corner of Hurontario Street and Poplar Sideroad in the Town of Collingwood, a component of which includes clearing of a Terms of Reference for our study.

It is understood that the proponent is considering construction of a commercial facility that will occupy the majority of the property. In accordance with preconsultation correspondence from the Nottawasaga Valley Conservation Authority (NVCA) we understand the requirement for a EIS has been triggered due to presence of mapped unevaluated wetland associated with the Pretty River Floodway located north of the property, and potentially two (2) other wetland units near the northern property boundary. Portions of the property are therefore located within NVCA's Regulation Limit per O. Reg. 41/24 under the *Conservation Authorities Act*. Azimuth's field program will focus on the proposed development envelope and adjacent lands (within 120m of the development limit; i.e. the "study area") in accordance with provincial standards.

The following Terms of Reference is proposed toward completion of the EIS:

- <!--[if !supportLists]-->• <!--[endif]-->Search the Town, County, Ministry of Natural Resources and Forestry (MNRF), Ministry of the Environment, Conservation and Parks (MECP), and Fisheries and Oceans Canada (DFO) records to obtain available background information and current data related to natural heritage features and functions in the area;
- Initiate consultation with the Town and NVCA to confirm the Terms of Reference for the scope of the EIS;
- Conduct a field study to document existing natural heritage features, functions, and species. Surveys include:
 - Evaluate/ map vegetation community types based on Ecological Land Classification methods (spring-summer 2024);
 - Two (2) vascular plant inventories (spring and summer 2024);
 - Three (3) amphibian breeding surveys (April, May, June 2024);
 - Two (2) dawn breeding bird surveys (May-July 2024);
 - Record all incidental wildlife observations during site visits.
- Attend one (1) wetland staking exercise with NVCA, the Town, and/or other stakeholders to delineate wetland boundaries should the vegetation inventory verify presence of wetland units on the property;
- Complete an assessment of potential Species at Risk and Significant Wildlife Habitat that could be present within the study area, including a screening for Butternut and Black Ash trees (Endangered);
- Assess the potential direct and indirect impacts of the proposed works on the natural heritage features and functions identified on or adjacent to the development parcel; and,
- Review conformity of the proposed development within the applicable municipal, provincial, and federal natural heritage policy framework.

At this time Azimuth requests that the Town/NVCA indicate concurrence with the above proposed Terms of Reference toward completion of the EIS. We would also like to take this opportunity to request any natural heritage background information from the Town/NVCA that may be helpful in completing the FIS.

Please feel free to contact me if you would like to discuss any aspects of the project.

Kind regards,



Dan Stuart, M.Env.Sc.

Ecology Lead/Partner
Azimuth Environmental Consulting, Inc.
642 Welham Road Barrie, ON L4N 9A1
Office: 705-721-8451 x208

Cell: 705-794-0975


www.azimuthenvironmental.com

Providing services in hydrogeology, terrestrial and aquatic ecology, environmental engineering, and arborist assessments.



APPENDIX B

Provincial Background and Correspondence





APPENDIX C

Nottawasaga Valley Conservation Authority Background

April 11, 2024 SENT BY EMAIL

Town of Collingwood 97 Hurontario Street Collingwood, ON L9Y 2L8

Attn: Nathan Wukasch

Senior Planner

nwukasch@collingwood.ca

Dear Nathan,

RE: Pre-consultation Comments for "The Gateway Centre – Phase Two and Three"
Town File No. D00224
869, 853, (portion of) 839 Hurontario Street and 7564 Poplar Sideroad (NE corner of Hurontario and Poplar Sideroad)
NVCA ID #27574

Nottawasaga Valley Conservation Authority [NVCA] staff has reviewed the above noted preconsultation application for a proposed redevelopment of the site for residential and commercial purposes. The applicant proposes the construction of commercial buildings located on the portion of the subject lands designated Residential and in a Deferred Residential Zone, and a proposed 12-storey mixed-use building on the portion of the lands designated Highway Commercial and located within the Highway Commercial C5 Zone. It is staffs understanding that OPA and ZBA's will be required for the proposed developments in Phase 2 and 3.

NVCA staff have received and reviewed the following documents submitted with this application:

DRAWING: Site Plan – Option C.01-D; Prepared by: Richard Ziegler Architects Inc.;
 Dated: January 9, 2024

Staff has reviewed this application as per our delegated responsibility from the Province to represent provincial interests regarding natural hazards identified in Section 3.1 of the Provincial Policy Statement (PPS, 2020) and as a regulatory authority under Ontario Regulation 41/24. The application has also been reviewed through our role as a public body under the Planning Act as per our CA Board approved policies. Finally, NVCA has provided comments as per our Municipal Partnership and Service Agreement with the Town of Collingwood.

Ontario Regulation 41/24

 The property falls partially within an area affected by Ontario Regulation 172/06 (the Authority's Development, Interference with Wetlands and Alterations to Shorelines and Watercourses Regulation) where a permit is required from the NVCA under the <u>Conservation Authorities Act</u> prior to development. The area is affected by the regulation due to the Pretty River Floodway, unevaluated wetland, floodplain, meander erosion hazard areas and associated buffers.

Natural Hazard - Regulatory Comments

- 2. Policies contained within the PPS restrict development to areas outside of hazardous lands adjacent to shorelines and large inland lakes as well as river, stream and small inland lake systems which are impacted by flooding hazards and/or erosion hazards.
- 3. A natural hazard study should be completed in support of the proposed development.
- 4. A geotechnical study will be required in support of the development application which outlines the following;
 - a. On-Site Soils;
 - b. The feasibility of the use of low impact development measures;
 - c. The feasibility of the stormwater detention design as per Section 2.3 of the NVCA SWM standards;
 - d. Confirmation as to whether there are any hazardous soils on site and any mitigation measures that may be required;
 - e. Identify the stable top-of-bank and confirmation of stable slopes.
- 5. In general, NVCA's Planning and Regulations Guidelines requires a 6 metre access allowance from natural hazard limits and valleylands top of bank.

Planning Ecology:

- 6. A various wetland features have been identified on the subject lands. Please see attached mapping which identifies the locations of the wetlands. NVCA's Planning and Regulations Guidelines stipulate a 30m setback to wetlands from development activities.
- 7. Due to the presence of confirmed natural heritage features within proximity to the proposed development, an EIS will be required to assess the potential impacts of development on such features, and evaluate conformity of the proposal with relevant natural heritage-related policies. The applicant will be required to retain a qualified ecologist to prepare this submission. Attached is a Terms of Reference identifying the studies and observations required as part of a complete EIS.

Stormwater Management:

8. A stormwater management report and associated plans will be required to current standards. More information can be found in the NVCA engineering guidelines available on our website at nvca.on.ca.

Hydrogeology

9. The applicant is encouraged to complete the Hydrogeological Assessment check List intended to support development applications, Found on Table 1 (page 6 and 7) of the document entitled "Hydrogeological Assessment Submissions, Conservation Authority Guidelines for Development Applications" June 2013 which is attached for reference.

Land Use Planning

- 10. In order to accurately determine the appropriate limits to development, NVCA staff request that a *scaleable* drawing be provided which illustrates the following items (as applicable):
 - i. The wetland/woodlot boundaries and width of buffers
 - ii. All applicable hazard limits (shoreline, erosion etc.) plus the 6 metre access allowance);
 - iii. The floodplain limit plus the 6 metre access allowance;
 - iv. The proposed site plan fabric.

This information should be accompanied by an appropriate and complete legend. Constraint lines, access allowances, and buffer setbacks should be labelled. Please confirm that all works are outside of the limits of development. (i.e. all natural hazards, access allowances, natural heritage features and associated buffers and setbacks).

The limits to development will be determined by the furthest extent of the hazard plus the required access allowance or the natural heritage feature and appropriate buffer; whichever is the greatest constraint.

11. Please provide copies of all draft by-law documents, including schedules for NVCA to review and provide comment.

Fees

NVCA will provide a formal request for fees upon submission and circulation of a Planning Act application.

Conclusion

NVCA staff appreciates the opportunity to comment at this stage in the process. These comments should be considered valid at the time of issuance and preliminary in nature. The information presented herein is based on a preliminary concept plan and should not be considered NVCA final comments at this time. We will require additional information (full application submission) in order to complete our review and additional comments may be provided in the future. The NVCA may at any point change our comments should new information become available which raises concerns pertaining to the NVCA core mandate.

Should you require any further information, please feel free to contact the undersigned.

Sincerely,

Davin Metheral

Planner



Terms of Reference

1.	General Information:
	Date: April 10, 2024
	Address: 853 and 869 Hurontario Street and 7564 Poplar Sideroad
	Proposed Development: The Gateway Centre
	Contact information:
2.	Identify all <u>potential</u> features in the study area (check all that apply): *The NVCA recognizes that this is a preliminary assessment to determine what studies may be suitable for the property. A site visit may be required to verify the presence/absence of features.
	 ✓ Wetlands ✓ Organic soils ☐ Dunes / parabolic dune outliers ☐ Karst topography ☒ Intermittent drainage features ☒ Lakes, ponds ☐ Watercourses ☐ Georgian Bay Shoreline ☒ Groundwater seeps and springs
3.	Activities to be undertaken and studies required for a complete EIS submission**: ** Some activities/studies are pre-selected (🗵) as they are a minimum requirement for EIS submissions.
	☑ Identify an appropriate study area - generally the area of anticipated disturbance plus 120 m.
	☑ Collect and include applicable background information and current environmental mapping for wetland and hydrologic features within and surrounding the study area.
	☑ Identify and provide detailed descriptions of hydrologic features in the study area, their function, and the broader sub-watershed that they are within.
	☑ Delineate existing vegetation communities using Ecological Land Classification (ELC) for Southern Ontario (Lee et al. 1998. Ecological Land Classification for Southern Ontario: first approximation and its applications. SCSS Field Guide FG-02) including the soils assessment . Provide a description of ELC communities in the study area. The EIS must classify the moisture regime of wetland soils in accordance with O. Reg. 41/24 to be deemed complete.
	☑ Conduct a two -season vegetation inventory in the late spring/summer/fall. Include the inventory categorized by ELC community as an appendix and denote any Species at Risk and/or provincially/locally rare species.
	☑ Provide a general description of the methodology, dates, timing, and locations of completed field surveys. Include all field sheets as an appendix.
	☑ Provide a detailed description of the proposed development.

Terms of Reference

	Complete an aquatic characterization for all drainage features/watercourses in the study area, including characterization of hydrologic features (i.e. permanent, intermittent, ephemeral, headwater drainage feature). Include a description of instream and riparian cover, bank stability, substrate composition, stream morphology, dimensions and gradient, thermal regime indicators, potential barriers, woody debris distribution, aquatic vegetation, groundwater seepage areas, etc.
✓	Complete a feature-based water balance for the study area to assess how existing drainage conditions and moisture regimes that support sensitive hydrologic features (e.g. wetland, watercourse) may be impacted by the proposed development. Demonstrate how current hydrologic inputs will be maintained post-development. Please note, the water balance assessment may also be a requirement under other provincial policies, therefore the EIS should coordinate with/summarize the water balance work undertaken by others.
√	Recommend the dimensions of an appropriate setback/buffer to wetland and hydrologic features required to mitigate impacts from the proposed development. Recommendations for restoration/plantings should be provided for all buffers.
<u>√</u>	Confirm the boundaries of any wetland feature on the property through a staking exercise with the NVCA. Boundary points must be surveyed with a high-accuracy GPS device (accurate to within 10 cm). A professional Ontario Land Surveyor (OLS) may be required to attend. Wetland staking exercises must be completed between June 15 and September 30 (exceptions may apply). Note that a site visit fee may apply.

- ☐ Map the following information separately on current high quality ortho-air photos:
 - 1) ELC vegetation communities, hydrologic features (including seeps and springs) and their associated buffers/setbacks, and the proposed development and anticipated limit of disturbance (e.g. grading limits); and,
 - 2) ELC vegetation communities, survey locations, incidental environmental features and existing structures and/or trails.
- Assess the potential direct, indirect, and cumulative impacts of the proposed development on hydrologic features, natural hazards and related ecological and hydrologic functions.
- ☑ Develop and provide an appropriate avoidance/mitigation/restoration strategy to address the potential impacts of the proposed development.
- ☑ Demonstrate how the proposed development is in conformity with all federal, provincial, regional, and municipal policies applicable in the study area.
- ☑ Complete one final report for circulation and approval, prepared by qualified professionals, in an electronic format.



Terms of Reference

Environmental Impact Study (EIS)


ł.	Additional studies or plans that may be required include:
	☐ Landscape/Restoration/Planting Plan
	☐ Edge Management Plan
	Hydrogeologic Study (Feature-based Water Balance)
	☐ Trails Impact Study
	■ Ecological Offsetting Strategy (if eligible under <u>NVCA's Ecological Offsetting Policy</u>)
	☐ Environmental Monitoring Plan/Report
	☐ OWES Evaluation (to determine wetland significance)
	☐ Natural Channel Design
5.	Additional notes and/or requirements:
	Updated NVCA wetland feature delineation has identified two wetlands within the subject sites which were not previously mapped. Wetland features are under NVCA regulation in accordance with O. Reg. 41/24. An EIS and feature-based water balance are required to support permit authorization from the NVCA for wetland interference.

Please note that changes to the study area, the proposed development, and/or policy changes may require additional information/studies. Please provide current field survey data in the EIS submission. Field survey data will be considered valid for five (5) years from the date the survey was conducted, except for Species at Risk screenings, which are valid for one (1) year. If outdated field data is provided, additional surveys may be required. Field data and reports by others referenced in any EIS must be appended for the EIS to be deemed complete.

NVCA Signature: Date: 10 April 2024

Reviewer: Emma Perry Title: Planning Ecologist







John Hix Conservation Administration Centre 8195 Concession Line 8, Utopia, Ontario L0M 1T0 Fax: 705.424.2115 Email: admin@nyca.on.ca

RECEIVED

November 08, 2007
PERMIT

#2007-8832

In accordance with Section 28 (1) of the Conservation Authorities Act, R.S.O. 1990 and Ontario Regulation 172/06, permission has been granted to the applicant, subject to the conditions below. If you do not agree with these conditions, you have a right to a Hearing under the Conservation Authorities Act. Please notify the Nottawasaga Valley Conservation Authority (NVCA) within 30 days of receipt of this permit to exercise your right to a Hearing. Should you fail to notify the NVCA within 30 days of receipt of this permit, you will agree to the conditions as set out below.

APPLICANT: Home Hardware Stores LTD

34 Henry Street W

St. Jacobs ON NOB 2NO

Centre for Conservation

Tiffin Conservation Area

Telephone: 705,424,1479

LOCATION: Part Lot 40, Concession 8, Town of Collingwood, County of Simcoe

869 Hurontario St SP-025-04 (Site Plan)

PROPOSAL: for the placement of fill / site alteration at the above noted location as indicated on the inoted on th

drawing(s)/report(s), subject to the following conditions:

This permit is valid from November 08, 2007 to November 08, 2009

SPECIAL PERMIT CONDITIONS

- That consent is given to NVCA, its employees and other persons as required by NVCA, to access the property for the purpose of inspection, obtaining information, and or monitoring any and all works, activities and or construction pertaining to the property in addition to the works as approved under cover of any permit issued by NVCA.
- 2) That the works be carried out in accordance with the following submissions:
 - All reports, drawings and correspondence, as previously approved by the NVCA (on file).
- 3) All materials and equipment used for the purpose of site preparation and project completion shall be operated and stored in a manner that prevents any deleterious substance from entering the water. Vehicular re-fuelling and maintenance should be conducted well away from the water.
- 4) That nothing herein authorizes any person to carry out any work or undertaking, which may result in harmful alteration, disruption or destruction of fish habitat or any fishery.
- 5) Please note that this permit is only valid if approvals, agreements or permits are received from all other agencies having jurisdiction.

STANDARD PERMIT CONDITIONS

That this permit does not confer upon you any right to occupy, develop or flood lands owned by other persons or agencies.

- That all development and site alteration is subject to all other applicable federal, provincial and municipal statutes, regulations and by-laws, such as the Municipal Act, Zoning and Tree-Cutting By-Laws, the Federal Fisheries Act, Navigable Waters Act, Public Lands Act, Lakes and Rivers Improvement Act, Drainage Act, Environmental Protection Act and the Ontario Water Resources Act.
- That appropriate erosion and sediment control measures are installed <u>prior to construction</u> and maintained until all disturbed areas are stabilized, to ensure that sediments do not enter any water-course, wetland, lake, pond or sensitive area within the development or adjacent properties. When an erosion and sediment control plan appears to be inadequate, the deficiencies must be addressed and additional measures or practices implemented as needed. It is the responsibility of the owner and the owner's representative (if contracted) to implement, monitor and maintain all erosion/sedimentation control structures and practices until vegetative cover has been successfully established.
- 9) That dewatering of the site (if any) must occur slowly and the pumped/drained water should be filtered by appropriate erosion control measures prior to entering any watercourse. Permission must be obtained from adjacent landowners prior to discharging overland water to their properties. Pumping shall be monitored and maintained on at least a daily basis.
- The natural drainage patterns beyond the immediate work site area are to remain in their natural state and existing vegetation shall not be removed.
- The soils disturbed during construction and access should be stabilized as soon as possible upon completion of work and restored to a pre-disturbed state or better. Disturbed areas should be revegetated/seeded when the growing season permits. From September 15th to April 30th, structural stabilization techniques (e.g. application of erosion control blankets) should be utilized.
- That the owner provides copies of this permit to any contracting or construction supervisor(s) who must have a copy of the permit available on-site for inspection by an officer when requested and that the owner ensure that all of the contractors and site supervisors are aware of the obligations under this permit including any obligations assigned by the owner to the contractors and supervisors. All contractors and site supervisors must be aware that they may also be held responsible for any violations in relation to the obligations outlined under this permit.

Note: It is the responsibility of the applicant to carry out the works in accordance with the above conditions. Failure to due so may result in cancellation of the permit and possible action in accordance with the *Conservation Authorities Act*.

Should you have any questions regarding this permit, please contact Karen Dykxhoorn - Environmental Officer at (705) 424-1479 extension 238.

Marilyn F.V. Eger, MES MCIP, RPP – Mrector of Planning

Karen Dykxhoorn, MLEO

Officer under the Conservation Authorities Act

Copy: Town of Collingwood – Planning Department Town of Collingwood – Building Department

Sheidel Construction Inc. Attn Fred Schiedel, 405 Queen St. W, Cambridge ON N3C 1G6

File (1)

Conserving Our Healthy Waters



APPENDIX D

Photographic Record



Photograph 1: Overview of vegetation composition in southern portion of MAMM1-2/MASM1-1a complex – August 22, 2024



Photograph 2: Overview of historical sedimentation pond feature (SAS_1 incl.) in northwest portion of property – August 22, 2024



Photograph 3: Ditch/drain along eastern "tail" of sedimentation pond, showing transition to adjacent upland zone – August 22, 2024



Photograph 4: Overview of central portion of MAMM1-2/MASM1-1b complex in northeast portion of property – August 22, 2024



Photograph 5: Standing water present in wettest portion of MAMM1-2/MASM1-1b complex in northeast portion of property – August 22, 2024



Photograph 6: Transition to meadow marsh and adjacent upland zone in southern portion of MAMM1-2/MASM1-1b complex – August 22, 2024



Photograph 7: Canopy/subcanopy composition (Green Ash dominated) in SWDM2-2 feature – August 22, 2024



Photograph 8: Representative ground cover and understory layers in SWDM2-2 feature – August 22, 2024



Photograph 9: Overview of MEGM4 and associated FODM11 (hedgerow) in northern portion of the property, from east edge facing west – July 31, 2024



Photograph 10: Representative ground cover and understory layers in FODM11 (hedgerow) feature – July 31, 2024



Photograph 11: Overview of MEMM4 community along Hurontario Street, from central area facing south – July 31, 2024



Photograph 12: Overview of THDM5/MEMM4 community in east portion of property, from southern area facing north – July 31, 2024



Photograph 13: Overview of CVC_1 (gravel pad) from northwest corner facing southeast toward Poplar Sideroad – July 31, 2024



Photograph 14: Main trunk of Butternut #001, located in close proximity to eastern property boundary – August 22, 2024



Photograph 15: Butternut #001 canopy overview, showing 100% live crown – August 22, 2024



Photograph 16: Butternut #002 located along northern property boundary; open canker (not pictured) documented on main stem – August 22, 2024





APPENDIX E

Butternut Documentation



Environmental Assessments & Approvals

September 5, 2024

Ministry of the Environment, Conservation and Parks Client Services and Permissions Branch

Report issued via e-mail

Re: Butternut Health Assessment Report # 609-010 for 869 Hurontario Street (Part Lot 40, Concession 8), Town of Collingwood

To Whom It May Concern:

Per the instructions of the amended Butternut Health Assessment (BHA) Guidelines (December 2021, Version 3) attached please find a BHA report (Report # 609-010) prepared in regard to the above noted property.

Should you have any questions or concerns, please do not hesitate to contact the undersigned.

Yours truly,

AZIMUTH ENVIRONMENTAL CONSULTING, INC.

Dan Stuart, M.Env.Sc.

Ecology Lead/Partner

BHA #609/Butternut Health Expert

Attached: BHA Report # 609-010

cc: David Finbow, Charis Developments Ltd.

BHA Report Template – Version March 2015

Note to BHAs:

This BHA Report template identifies where you need to insert customized text in blue. Do <u>not</u> edit or delete black text.

Insert your cover letter to the client here and include the list of enclosures.

Please enter the BHA Report number in the footer of this document (6 digits, to be assigned by BHA using format: 3 digit BHA ID#, followed by BHA's own 3 digit report numbering system).

Delete this instructional text and save document as a pdf when completed.

Enclosures:

- 1. Information from the Ministry of Natural Resources and Forestry about Butternut and the Endangered Species Act, 2007
- 2. Butternut Health Assessor's Report
- 3. Original data forms
- 4. Electronic and printed copies of the Excel data spreadsheet (BHA Tree Analysis)

Ministry of Natural Resources and Forestry

Species At Risk P.O. Box 7000, 300 Water Street Peterborough ON K9J 8M5 Ministère des Richesses naturelles et des Forêts

Espèces en péril C.P. 7000, 300, rue Water Peterborough ON K9J 8M5



The enclosed Butternut Health Assessor's Report documents the results of the Butternut health assessment that was conducted by the designated Butternut Health Assessor (BHA) identified in the top section of the report. If there are other Butternut trees (of any size or age) at the site that may be affected by the activity and they are not identified in the enclosed BHA Report, they too must be assessed by a designated BHA.

Butternut is listed as an endangered species on the Species at Risk in Ontario List, and as such, it is protected under the *Endangered Species Act, 2007* (ESA) from being killed, harmed, or removed. If you are planning to undertake an activity that may affect Butternut, you may be eligible to follow the requirements set out in section 23.7 of Ontario Regulation 242/08 under the ESA, or you may need to seek an authorization under the ESA (e.g., a permit).

Please visit e-laws at the link provided below for the legal requirements of eligible activities under section 23.7 of Ontario Regulation 242/08 and conditions that must be fulfilled. Information about Butternut is also available at: http://www.ontario.ca/environment-and-energy/butternut-trees-your-property.

If you are eligible to kill, harm or take Butternut under section 23.7 of the regulation, your first step is to submit the BHA Report and the original data forms enclosed in this package to the local Ministry of Natural Resources and Forestry (MNRF) District Manager. Note that MNRF cannot accept photocopies or scanned electronic copies of the data forms.

Note regarding changes:

If the enclosed BHA Report does not identify which Butternut tree(s) are proposed to be killed, harmed, or taken in Table 1 (i.e., if "unknown" is indicated in the second last column of Table 1), or, if the information in the last two columns of Table 1 has changed since the date this BHA Report was produced, **do not make any edits to the BHA Report**. Instead, please attach a cover letter that identifies which Butternut tree(s) are proposed to be killed, harmed, or taken (by referencing the tree identification numbers) when you submit the enclosed BHA Report to the local MNRF District Manager.

The BHA Report must be submitted at least 30 days prior to registering an eligible activity to kill, harm, or remove a Butternut tree. During this 30 day period, no Butternut trees (of any category) may be killed, harmed, or removed, and MNRF may contact you for an opportunity to examine the trees. If MNRF chooses to examine the trees, a representative of MNRF will contact you using the information you supplied when you submitted the BHA Report.

If you are eligible to follow the rules in regulation under section 23.7, you may register your activity using the "Notice of Butternut Impact" form on the MNRF Registry after the 30 day period has elapsed.

If you are <u>not</u> eligible to follow the rules in regulation under section 23.7, please contact the local MNRF district office to determine whether you will need to seek an authorization (e.g., a permit). A link to the directory of MNRF offices is provided below.

Note that municipal by-laws and legislation other than the ESA may also be applicable to the removal or harming of trees.

Please retain this information and a copy of the BHA Report (including copies of all data forms) for your records, along with any other documentation you may receive from MNRF should an examination of the trees occur. If you have any questions, please contact your local MNRF district office.

Links:

Endangered Species Act, 2007:

http://www.e-laws.gov.on.ca/html/statutes/english/elaws statutes 07e06 e.htm

Ontario Regulation 242/08 (refer to section 23.7):

http://www.e-laws.gov.on.ca/html/regs/english/elaws regs 080242 e.htm

MNRF Office Locations:

https://www.ontario.ca/government/ministry-natural-resources-and-forestry-regional-and-district-offices

Butternut Health Assessor's Report Number: 609-009 (6 digits, to be assigned by BHA using format: 3 digit BHA ID#, followed by BHA's own 3 digit report numbering system)

Dan Stuart, BHA#609/Butternut Health Expert 642 Welham Road Barrie, Ontario L4N 9A1 705.721.8451 x208 dstuart@azimuthenvironmental.com

David Finbow Charis Developments Ltd. 705.607.3620 Dfinbow8@gmail.com

Site location: 869 Hurontario Street (Part Lot 40, Concession 8), Town of Collingwood

Date(s) of Butternut health assessment: August 22, 2024

Date BHA Report prepared: September 5, 2024

Total number of trees assessed in this BHA Report: 2

The assessed trees were numbered on site using black/orange flagging tape labeled with marker. The numbers at the site correspond to the tree numbers referenced in this report.

This BHA Report includes the following tables:

- Table 1: Butternut Trees Assessed
- Table 2: Trees Determined by BHA to be Butternut Hybrids
- Table 3: Summary of Assessment Results

Table 1: Butternut Trees Assessed

	1. Batternat Trees 7.05e55ea					
Tree #	UTM coordinates	Category 1 (1, 2, or 3^2)	dbh³ (cm)	Cultivated? (Y/N)	Proposed to be: (enter one: unknown⁴, killed, harmed or taken)	If tree is proposed to be killed, harmed, or taken, indicate reason tree is proposed to be killed, harmed or taken:
001	17T 562826 4925502	2	33	Z	Harmed	Commercial Development
002	17T 562664 4925618	1	1	Z	N/A	N/A

_

¹ The extent to which the tree is affected by Butternut Canker is presented in the Excel document titled, "BHA Tree Analysis" that accompanies this BHA Report.

² Category 3 trees are not eligible to be killed, harmed or taken under section 23.7 of Ontario Regulation 242/08.

³ dbh: diameter at breast height, rounded to nearest cm (if tree is shorter than breast height, enter zero)

⁴ In this column, "unknown" indicates that at the time of assessment, there are no proposals to kill, harm or take this tree that are known to the BHA.

Table 2: Trees Determined by BHA to be Butternut Hybrids

Tree #	UTM coordinates	Method used (genetic testing or field identification):
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A

Table 3: Summary of Assessment Results

Result:	Total #:	Important information for persons planning activities that may affect Butternut:
Category 1	1	A Category 1 tree is one that is affected by butternut canker to such an advanced degree that retaining the tree would not support the protection or recovery of butternut in the area in which the tree is located; and is considered "non-retainable".
		 During the 30 day period that follows your submission of this BHA Report to the MNRF District Manager, no Butternut trees (of Category 1, 2, or 3) may be killed, harmed, or taken, and MNRF may contact you for an opportunity to examine the trees.
		Category 1 trees may be killed, harmed or taken <u>after</u> the 30 day period that follows submission of this BHA Report to the MNRF District Manager, unless the results of an MNRF examination indicate that the assessment has not been conducted in accordance with the document entitled "Butternut Assessment Guidelines: Assessment of Butternut Tree Health for the Purposes of the <i>Endangered Species Act, 2007</i> ".
Category 2	1	 A Category 2 tree is one that is not affected by Butternut Canker, or is affected by Butternut Canker but the degree to which it is affected is not too advanced and retaining the tree could support the protection or recovery of butternut in the area in which the tree is located, and is considered "retainable".
		 During the 30 day period that follows your submission of this BHA Report to the MNRF District Manager, no Butternut trees (of Category 1, 2, or 3) may be killed, harmed, or taken, and MNRF may contact you for an opportunity to examine the trees.
		 Activities that may kill, harm or take up to a <u>maximum of ten (10)</u> Category 2 trees may be eligible to follow the rules in section 23.7 of Ontario Regulation 242/08, in accordance with the conditions and requirements set out in the regulation.
		 Refer to e-Laws for the legal requirements of eligible activities under section 23.7 of Ontario Regulation 242/08 and conditions that must be fulfilled: http://www.e-laws.gov.on.ca/html/regs/english/elaws-regs-080242 e.htm
		 Activities that may kill, harm or take more than ten (10) Category 2 trees are not eligible to follow the rules in section 23.7 of Ontario Regulation 242/08. Contact the local MNRF district office for information on how to seek an ESA authorization (e.g., a permit) or consider an alternative that would be eligible for the regulation.
Category 3	0	A Category 3 tree is one that may be useful in determining sources of resistance to Butternut Canker, and is considered "archivable".
		 Category 3 trees are not eligible to be killed, harmed or taken under section 23.7 of Ontario Regulation 242/08.
		Contact the local MNRF district office for information on how to seek an ESA authorization, or consider an alternative that will avoid killing, harming or taking any Category 3 trees.
Cultivated	0	 An activity that involves killing, harming, or taking a cultivated Butternut tree that was not required to be planted to fulfill a condition of an ESA permit or a condition of a regulation, may be eligible for the exemption provided by subsection 23.7 (11) of O. Reg. 242/08.

Result:	Total #:	Important information for persons planning activities that may affect Butternut:
		 Prior to undertaking the activity, the owner or occupier of the land on which the Butternut is located (or person acting on their behalf) will need to determine whether the exemption for cultivated trees is applicable by determining whether or not the tree was cultivated as a result of the requirements for an exemption under O. Reg. 242/08 or a condition of a permit issued under the ESA. This information can be accessed by contacting the local MNRF district office.
		The owner or occupier of the land on which the Butternut is located (or person acting on their behalf) is encouraged to append the details regarding whether the tree was planted to satisfy a requirement (e.g., the permit number or registration number) to this BHA Report for their records.
Hybrid	0	Hybrid Butternut trees are not protected under the ESA, but their removal may be subject to municipal by-laws and other legislation.

Butternut Health Assessor's Comments:

Butternut stem #001 subject to Butternut hybrid testing via collection of leaf sample and genetic test. Results not yet received at time of BHA submission (September 5, 2024).

This concludes the summary of the BHA Report. A complete BHA Report must also include:

- 1. All original (hard copy) data forms (i.e., all completed sets of Form 1 and Form 2), and
- 2. Electronic and printed copies of the Excel data analysis spreadsheet.

Surveyor ID
Shaded fields are mandatory for Butternut Health Assessments Surveyor Contact First
Telephone
Property Owner Check if same as surveyor Email F N E N
Owner (check if same as surveyor) Company
Check if same as surveyor Email
Telephone Tele
Telephone (7 0 5) 6 0 7 3 6 2 0 Telephone Other ()
Address
Tree Location (if different from mailing address) Address/(911#)
Tree Location (if different from mailing address) Address/(911#)
Address/(911#)
Directions City (
Directions
Site visits OK? (prior arrangments will always be made for a site vist)
Site visits OK? (prior arrangments will always be made for a site vist)
Site visits OK? (prior arrangments will always be made for a site vist)
Cless than Closs than Close than Closs than Close than Clo
Tree Condition <3 cm 3-15 cm 16-30 cm >30 cm
Vigorous: > 50% Live Crown Minor or no cankers O O O O O O O O O O O O O O O O O O O
Poor Vigor: <50% Live Crown or >50% Live Crown + heavily cankered stem Dead O
Cankered stem □ DeciduousForest □ Quary Dead □ O O O O O O O O O O O O O O O O O O O
Dead
Estimated area containing butternut
Soil Drainage Soil Depth
Proximit 7 Unknown Som
Soil Texture Sold Texture In Clay In Sand In Inches
Clay Loam Variable
□ Loam □ Unknown □ Loamy Sand
Please enter matching numerical page link code on forms 1 and 2 Please return forms to: Forest Gene Conservation Association 49731

(PLEASE USE Fill when Form 1 indicates canker is well **Butternut Data Collection FORM 2 (2010 Edition) BLOCK LETTERS)** established. The information opn Form 2 Shaded fields are mandatory for Butternut Health Assessments must be filled out for all trees when doing a Butternut Health Assessment. Surveyor ID Site Code(A,B,...Z, AA...) 0 6 Date (dd/mm/yyyy) or BHA# Surveyor Last Name 57 U Tree ID Numbering: 1,2,3,...Starting from 1 for each site Tree # Zone Easting Northing Metres from badly cankered tree Assess below live crown 0 Ò 2 0 8 ☐ < 40 ☐ > 40 ☒ None Found #Epic-Live #Open #Sooty **Competing Species** Main Stem Length(m) Crown #Epic-Dead Crown % Below crown Class Seed Root MP Butternut Signs Male Flowers ☐ Twig Dieback Bark Type #Stems =<2n Origin ■ Branch Dieback ☐ Female Flowers ☐ Seed Set ☐ Natural # Callused ☐ Defoliation 0 了 DBH(cm) ☐ Planted >2m Wounds ☑ Discolouration ☑ Unknown ☑ None Tree # Zone Easting Northing Metres from badly cankered tree Assess below live crown ☐ < 40 ☐ > 40 ☒ None Found #Epic-Live #Open #Sooty Main Stem Length(m) **Competing Species** Crown l ive 0 C #Epic-Dead Class Crown % Below crown 0 Seed Root 0 Butternut Signs Male Flowers ☐ Twig Dieback Bark Type #Stems Origin ☐ Branch Dieback ☐ Defoliation ☐ Female Flowers ☐ Natural # Callused ☐ Seed Set 0 *O* Wounds ☐ Planted DBH(cm) ☐ Discolouration ☑ Unknown ☑ None Mechanical domale Stem moin Tree # **Easting** Zone Northing Metres from badly cankered tree Assess below live crown ☐ < 40 ☐ > 40 ☐ None Found #Epic-Live #Open #Sooty **Competing Species** Live Main Stem Length(m) Crown #Epic-Dead Class Crown % Below crown Seed Root Butternut Signs Male Flowers ☐ Twig Dieback Bark Type #Stems =<2m Origin Branch Dieback ☐ Female Flowers ☐ Seed Set ☐ Natural # Callused ☐ Defoliation >2n ☐ Planted DBH(cm) Wounds ☐ Discolouration ☐ Unknown ☐ None Tree # Zone Easting Northing Metres from badly cankered tree Assess below live crown ☐ < 40 ☐ > 40 ☐ None Found #Epic-Live #Open #Sooty **Competing Species** Live Main Stem Length(m) Crown #Epic-Dead Crown % Class Below crown Seed Root Butternut Signs Male Flowers ☐ Twig Dieback Bark Type #Stems Origin =<2n ☐ Branch Dieback ☐ Female Flowers ☐ Natural # Callused Defoliation Seed Set >2m □ Planted DBH(cm) Wounds ☐ Discolouration ☐ Unknown ☐ None Tree # Zone Easting Northing Metres from badly cankered tree Assess below live crown ☐ < 40 ☐ > 40 ☐ None Found #Epic-Live #Open #Sooty **Competing Species** Main Stem Length(m)

Please enter matching page link code on forms 1 and 2

DBH(cm)

Live

#Stems

Crown %

Page Link

Crown

Class

☐ Twig Dieback

Branch Dieback
Defoliation

Discolouration

(Contact Information follows all applicable privacy policies and guidelines)

Seed

☐ Female Flowers

Signs Male Flowers

☐ Seed Set

Below crown

Butternut

Origin

Natural

Planted

Unknown

None

Please return forms to: Forest Gene Conservation Association Suite 233, 266 Charlotte St. Peterborough, ON, K9J 2V4 www.fgca.net

#Epic-Dead

Callused

Wounds

Bark Type

Root

=<2n

>2n





BHA Tree Analysis (version: December 2013)

					Th	is table	e is to	be o	comple	eted by a	designate	d Butternu	t Health	Assesso	r (BHA).					
BHA Repor	't #	609-	-010 Assessment Date(s)				22-Aug-24 Total # Butternut Trees in BHA Report				2									
вна і	D#	60	9	ВНА	A Na	me			Daniel Stuart, Azimuth Environmental Consulting, Inc.											
Lando	wner	/ Clie	nt N	lame)							Chari	is Deve	elopme	nts Lto	d.				
Prope	rty Lo	ocatio	n			86	9 H	uror	ntario	Street	t (Part L	ot 40, C	onces	sion 8)	, Town	of Co	olling	woo	d	
		inp	ut fie	eld d	ata					auto	omatic c	alculatio	ns fror	n field	data			ego		
			#	# bole	canke	rs			or N)		total							on-ret etaina		ble,
				(=)		(=)			(Y or	Circ.	bole	total RF canker	bole	RF	total bole &			rchiva	,	
				:y (S) Il be	•	n (O) II be	# re	oot (RF)	, (a	(cm) =	canker width	width	canker	canker	root					FINAL
#	% uv	Tree dbh (cm)		gned	_	ned 5		kers	cankered tree?	Pi x dbh	(sooty x	(sooty x 2.5 +	% of circ.	% of circ.	canker % of		LC%	LC%	call	TREE
Tree	Live Crown %	dph:		m per ker)		per ker)			ıkere		2.5 + open x 5)	open x 5)			2xCirc	LC% >/=	>70	>70	tree	CALL
	Live	Tree		,		,			ı can							50 &	& BRC	& BC	ary (a Cat 2, dbh>20c
			s	s	0	0	חר	הר	m from	Circ	DC	DC.				BC% = 0	%	% <20	Preliminary	m <40m
			< 2	> 2	< 2	> 2	RF S	RF O	<40 m	Circ (cm)	BC (cm)	RC (cm)	вс%	RC%	BRC%		<20	<20	Pre	from a
			m	m	m	m			7>	, ,	` ,	, ,								Cat 1
1	100	33	2	0	1	0	2	1	N	103.6	10.0	10.0	9.7	9.7	9.7	1	2	2	2	2
2	100	1	0	0	1	0	0	0	N	3.14	5.0	0.0			79.6		1	1	1	1
										0	0.0		#####		#####	####	###	###	##	#DIV/0!
							H			0	0.0		#####		#####	####	###	###	##	#DIV/0!
										0	0.0	0.0	#####	#####	#####	####	###	###	##	#DIV/0! #DIV/0!
										0	0.0	0.0	#####	#####	#####	####	###	###	##	#DIV/0!
										0	0.0		#####	#####	#####	####	###	###	##	#DIV/0!
										0	0.0		#####		#####	####	###	###	##	#DIV/0!
										0	0.0	0.0	#####	#####	#####	####	###	###	##	#DIV/0!
										0	0.0	0.0	#####	#####	#####	####	###	###	##	#DIV/0!
										0	0.0	0.0	#####	#####	#####	####	###	###	##	#DIV/0!
										0	0.0	0.0	#####	#####	#####	####	###	###	##	#DIV/0!
										0	0.0			#####	#####	####		###		#DIV/0!
							$\vdash\vdash$			0	0.0		#####		#####	####	###	###	##	#DIV/0!
							$\vdash\vdash$			0	0.0		#####		#####		###	###	##	#DIV/0!
							\vdash			0	0.0		#####		#####	####	###	###	##	#DIV/0! #DIV/0!
							\vdash			0	0.0		#####		#####	####	###	###	##	#DIV/0!
							\vdash			0	0.0		#####	#####	#####	####	###	###	##	#DIV/0!
										0	0.0		#####		#####	####	###	###	##	#DIV/0!
										0	0.0	0.0	#####	#####	#####	####	###	###	##	#DIV/0!
										0	0.0	0.0	#####	#####	#####	####	###	###	##	#DIV/0!
										0	0.0	0.0	#####	#####	#####	####	###	###	##	#DIV/0!
							Щ			0	0.0		#####		#####		###	###	##	#DIV/0!
							\vdash			0	0.0		#####		#####	####	###	###	##	#DIV/0!
							$\vdash\vdash$			0	0.0		#####	#####	#####	####	###	###	##	#DIV/0!
										0	0.0		#####		#####	####	###	###	##	#DIV/0! #DIV/0!
							\vdash			0	0.0			#####		####	###	###	##	
										U	0.0	0.0	******	#####	#####	"""	###	###	11111	#DIV/U!



CANADIAN CENTRE FOR DNA BARCODING DNA Testing Laboratory Report

Page 1 of 8

Date of issue: September 6, 2024

CLIENT INFORMATION

Client Name: Alison Phillips

Client Address: Crozier Consulting Engineers

1 First Street, Suite 200

Collingwood, ON

L9Y 1A1

Contact Name: Alison Phillips (aphillips@cfcrozier.ca)

ITEMS

Description: One plant sample (fresh leaves) from putative butternut species submitted

for hybrid detection Sample ID: CCDBFR1478; Process ID: ABCBF1088-24

Dates Received: August 23, 2024

Dates of Analysis: August 26 – 30, 2024

Sample Received and Analyzed by: Nguyen NguyenTX. / Canadian Centre for DNA Barcoding, Biodiversity of

Ontario, University of Guelph, 50 Stone Road East, Guelph

METHODS

To ascertain the identity of the species from the submitted sample, an approximate 2mm by 2mm area of leave from sample was subsampled using sterile techniques. Sample was ground to a fine powder and then lysed. Total genomic DNA was extracted using validated spin column DNA extraction protocol. Two target genetic markers: the second internal transcribed spacer from the nuclear ribosomal DNA (ITS2), and an intergenic spacer between the chloroplast genes trnL and trnF (trnL-trnF) were amplified by using the Polymerase Chain Reaction (PCR) with the primers ITS S2F/ITS4 and trnLUAA-c/trnFGAA-f, respectively; followed by cycle sequencing with standardized commercially available BigDye Terminator v3.1 kit. Sequencing reactions were analyzed by highvoltage capillary electrophoresis using the automated ABI 3730xL DNA Analyzer. Bidirectional forward and reverse sequences were generated for each amplicon. Resulting trace files were assembled into contigs and consensus sequences, and then manually edited in CodonCode Aligner (version 9.1.1.) software. The sequences of ITS2 and trnL-trnF were compared against the BOLD reference libraries. Based on the percentage of nucleotide sequence divergence (a number of nucleotide substitutions) between sequences from the test samples and reference DNA barcodes, the closest match was used to infer species identity of the corresponding test sample provided by the contributor. The quality of the sequence traces for ITS2 was done by visual inspection to resolve hybridization. Images, sequences, and their associated trace files with quality scores were uploaded to the secure BOLD project called "CCDB forensic sampling [ABCBF]".

IMAGING

The items were photographed in the Photography Lab Area by Nguyen NguyenTX., using a Canon ELPH 300 HS, 12.1 megapixels. Pictures were uploaded to the BOLD website into a secure project called "CCDB forensic sampling [ABCBF]". See Appendix 1 for item images.

INTERPRETATION

The ITS2 marker demonstrates five nucleotide substitutions between *Juglans cinerea* (white walnut, commonly known as butternut) and *Juglans ailantifolia* (Japanese walnut) reference sequences across the amplified ~344 base pair length. Unlike the plastid genome, ribosomal nuclear DNA is inherited by both maternal and paternal organisms. Thus, hybridization events are reflected in the trace file chromatograms as mixed signals at the characteristic nucleotide positions.

The *trnL-trnF* marker demonstrates five nucleotide substitutions between *Juglans cinerea* (white walnut) and *Juglans ailantifolia* (Japanese walnut) reference sequences across the amplified ~950 base pair length. The marker is used as supplementary evidence to confirm species identity. The *trnL-trnF* marker is a part of the chloroplast genome and is inherited maternally. Therefore, this marker confirms the maternal lineage in a hybrid but on its own does not detect a hybridization event.

RESULTS

Sample ID	Process ID	Hybridity detected	Maternal organism
CCDBFR1478	ABCBF1088-24	Yes	Juglans ailantifolia (Japanese walnut)

ITS2 sequences of 344 base pairs were obtained for sample CCDBFR1478. Sample sequences were aligned against the known reference sequences for *Juglans cinerea* (white walnut), *Juglans ailantifolia* (Japanese walnut), and their hybrid *Juglans cinerea* x *Juglans ailantifolia*.

Across the amplified length of the ITS2 marker, five diagnostic nucleotide substitutions differentiate *Juglans cinerea* (white walnut) and *Juglans ailantifolia* (Japanese walnut). At these five nucleotide positions, sample CCDBFR1478 were identical to references for hybrid *Juglans cinerea x Juglans ailantifolia*. The chromatogram traces for these sequences showed evidence of mixed base calls at the diagnostic nucleotide positions, which confirms that sample CCDBFR1478 is of hybrid origin (Figures 1). The phylogenetic tree of the ITS2 marker for sample is shown in Figure 2.

trnL-trnF

Across the amplified length of the *trnL-trnF* marker, five diagnostic nucleotide substitutions differentiate *Juglans cinerea* (white walnut) and *Juglans ailantifolia* (Japanese walnut). At these five nucleotide positions, sample CCDBFR1478 was identical to references for *Juglans ailantifolia* (Japanese walnut). As the chloroplast genome is inherited maternally, our results indicate that *Juglans ailantifolia* (Japanese walnut) was the maternal organism for sample CCDBFR1478 (Figures 4). The phylogenetic tree of the *trnL-trnF* marker for this sample is shown in Figure 5.

CONCLUSIONS

The present testing has indicated that sample CCDBFR1478 is a hybrid between white and Japanese walnut species: *Juglans cinerea* x *Juglans ailantifolia*. The maternal organism belongs to *Juglans ailantifolia* (Japanese walnut).

Based on appropriate statistical BOLD match calculations and a reasonable degree of scientific certainty of the BOLD reference library, the taxonomic identity of the detected DNA source in these samples is considered practically proven.

RESULTS REPORTED BY:

Nguyen NguyenT.X., MSc; Wildlife Forensic Technician

RESULTS REVIEWED BY:

Maria Kuzmina, PhD; Plant Lead

300 S

Evgeny V. Zakharov, PhD; Director, CCDB

All inquiries pertaining to this report should be directed to Nguyen NguyenT.X. (n.nguyen@uoguelph.ca) and Evgeny V. Zakharov (zakharov@uoguelph.ca). This report should not be reproduced, except in full, without written approval of the CCDB.

DISCIDIANCE: "THIS REPORT AND ALL ATTACHMENTS HERETO ARE CONFIDENTIAL AND SUBJECT TO SOLICITOR-CLIENT PRIVILEGE. DO NOT FORWARD, CIRCULATE, DISTRIBUTE, COPY OR DUPLICATE THIS REPORT OR ANY ATTACHMENT HERETO WITHOUT WRITTEN AUTHORIZATION."

FIGURES




Figure 1 – ITS2 sequence comparison of sample CCDBFR1478 with references for *Juglans cinerea*, *Juglans ailantifolia*, and their hybrid *Juglans cinerea* x *Juglans ailantifolia*. Diagnostic nucleotide positions 3, 4 and 5 are shown.




Figure 2 – Neighbour joining phylogenetic tree of ITS2 sequences of the query sample CCDBFR1478, and their references: *Juglans cinerea*, *Juglans ailantifolia*, and hybrid *Juglans cinerea* x *Juglans ailantifolia*.




Figure 3 – trnL-trnF sequence comparison of sample CCDBFR1478 with references for *Juglans cinerea*, *Juglans ailantifolia*, *and* hybrid *Juglans cinerea* x *Juglans ailantifolia*. Diagnostic nucleotide positions 4 and 5 are shown.






Figure 4 – Neighbour joining phylogenetic tree of *trnL-trnF* sequences of the query sample CCDBFR1478, and their references: *Juglans cinerea*, *Juglans ailantifolia*, and hybrid *Juglans cinerea x Juglans ailantifolia*.



APPENDIX F

2004 Commercial Facility Drawings







APPENDIX G

Proposed Development Concept

PARKING - COMMERCIAL

Parking aisle minimum width of 6.0 metres Parking space minimum dimensions of 2.8 m x 6.0 m Accessible parking space minimum dimensions 4.5 m x 6.0 m Dual accessible parking spaces at 3.4 m x 6.0 m with 1.5 m shared aisle

Commercial							
Building	Rate	Gross Area	Gross Floor Area*	Parking Req'd	Parking Provided	Accessible Parking Req'd	Accessible Parking Prov'd
01 Restaurant	8/100 m2	225.5 m2	157.0 m2	13			
02 Commercial	3/100 m2	929.0 m2	836.1 m2	26	1		
03 Commercial	3/100 m2	847.8 m2	727.0 m2	22	1		
04 Commercial	3/100 m2	1,799.4 m2	1,619.5 m2	49	1		
Grocery Store	3/100 m2	4,576.0 m2	3,204.0 m2	97	1		
06 Commercial	3/100 m2	1,384.8 m2	1,246.3 m2	38			
07 Restaurant	8/100 m2	410.9 m2	287.0 m2	23			
Total				268	286	6	12

TRAIL CROSSWALK

*Gross Floor Area as defined by the Town of Collingwood Zoning By-law and is based on Gross Area –10% for general commercial uses and -30% for grocery store and restaurant uses.

DELIVERY / LOADING SPACES

1 Delivery Space for GFA between 460.0 m2 and 2,500.0 m2 1 Loading Space for GFA between 2,501.0 m2 and 7,000.0 m2 Delivery Spaces at 3.5 m (w) x 7.5 m (l) x 3.0 (v) Loading Spaces at 3.5 m (w) x 20.0 m (l) x 4.5 m (v)

Building	Use	Gross Area	Gross Floor Area	Type Required	Type Provided
Building 01	Restaurant	225.5 m2	157.0 m2	N/A	1 Delivery Space
Building 02	Commercial	929.0 m2	790.0 m2	1 Delivery Space	1 Delivery Space
Building 03	Mixed-Use	727.0 m2	618.0 m2	1 Delivery Space	1 Delivery Space
Building 04	Commercial	1,799.4 m2	1,619.5 m2	1 Delivery Space	1 Delivery Space
Grocery Store	Commercial	4,576.0 m2	3,204.0 m2	1 Loading Space	2 Loading Spaces
Building 06	Commercial	1,246.3 m2	1,060.0 m2	1 Delivery Space	1 Delivery Space
Building 07	Restaurant	410.0 m2	287.0 m2	N/A	1 Delivery Space

*Gross Floor Area as defined by the Town of Collingwood Zoning By-law and is based on Gross Area –10% for general commercial uses and -30% for grocery store and restaurant uses.

QUEUING AISLES

Parking space minimum dimensions of 2.8 m x 6.0 m

Building	Use	# of Spaces Required	# of Spaces Provided	Comments
Building 01	Restaurant	10	12	Addn'tl Spaces Beyond Pick-up Window
Building 07	Restaurant	10	14	Addn'tl Spaces Beyond Pick-up Window

BICYCLE SPACES

Mixed-Use Building: 0.7 spaces per dwelling unit to a total maximum of 15 bicycle spaces Non-Residential Buildings: 10% of the required parking spaces for motor vehicles but in no case shall shall the required bicycle spaces be less than 4

Building	Use	Parking Req'd	Bicycle Spaces Req'd	Bicycle Spaces Prov'd
Building 01	Restaurant	13	4	4
Building 02	Commercial	26	4	4
Building 03	Mixed-Use Comm.	20	4	16
Building 03	Mixed-Use Res.	207	15	15 (U/G)
Building 04	Commercial	49	5	4
Grocery Store	Commercial	97	10	8
Building 06	Commercial	34	4	4
Building 07	Restaurant	23	4	4
Total			49	59

THE GATEWAY CENTRE - ZONE PROVISIONS

Provision	C4 Zone Requirement	Proposed
Minimum Lot Area	1,000.0 m2	37,604.1 m2
Minimum Lot Frontage (Hurontario Street)	30.0 m	194.0 m
Minimum Front Yard (Hurontario Street)	6.0 m	7.5 m
Minimum Exterior Side Yard (Poplar Sideroad)	9.0 m	15.0 m
Minimum County Setback @ Poplar Sideroad	15.0 m	15.0 m
Minimum Interior Side Lot Line (East Lot Line)	9.0 m	9.0 m
Minimum Rear Yard (North Lot Line)	7.5 m	7.5 m
Maximum Height	15.0 m	42.5 m
Maximum Lot Coverage	40%	26%
Minimum Landscape Open Space	10%	34%
Minimum Hurontario Street CL Setback	15.0 m	29.3 m
Minimum Poplar Sideroad CL Setback	18.0 m	41.9 m
Minimum Parking Space Setback	6.0 metres	6.0 metres
Entrance Width	7.5 m to 15.0 m	9.0 m
Maximum Number of Dwelling Units	N/A	165 units

PARKING - RESIDENTIAL

Parking aisle minimum width of 6.0 metres Parking space minimum dimensions of 2.8 m x 6.0 m Accessible parking space minimum dimensions 4.5 m x 6.0 m Dual accessible parking spaces at 3.4 m x 6.0 m with 1.5 m shared aisle

Residential						
Building	Rate	# of Units	Resident Parking Required	Visitor Parking Required	Total Required	Total Provided
Building 03	1/unit + 0.25/unit for Visitors	165	165	42	207	297

03 MIXED-USE 04 RETAIL WITH OFFICES **BUILDING HEIGHT 42500mm BUILDING AREA BUILDING HEIGHT 11000mm** BUILDING AREA 599.8 m² (6,456 ft²) TOTAL GFA 1,490 m² (16,042 ft²) | GFA | 1,619.5 m² (17,438 ft²) COMMERCIAL GFA 727 m² (7,829 ft²) ROOFTOP AMENITY 684 m² (5,095 ft²) 3m CONCRETE SIDEWALK C.L. OF FIRE ROUTE 3m CONCRETE SIDEWALK PYLON SIGN 3M X 6.25M HIGH 02 RETAIL DOLLARAMA **GROCERY STORE BUILDING AREA SOBEY'S 1-STOREY BUILDING** 929.0 m² (10,000 ft²) **BUILDING AREA** GFA 836.1 m² 4,405.8 m² (47,424 ft²) **BUILDING HEIGHT 7163mm BUILDING HEIGHT** GFA (INCLUDING MEZZANINES) 4,576 m² (49,251 ft²) STARBUCKS
GFA 157 m² (1,690 ft²)


PLUI DING APEA

BUILDING PATIO
7000mm

930 SF GFA 157 m² (1,690 ft²) **BUILDING AREA** 225.5 m² (2,428 ft²) C.L. OF FIRE ROUTE 06 RETAIL 9,415.71 sf. **BUILDING AREA** 1,384.8 m² (14,906 ft²) PATIO 1,020 SF GFA 1,246.32 sm. (13,415.72 sf.) GFA 368 m² (3,963 ft²) 4,000 sf. **WELCOME TO BUILDING HEIGHT 7000mm** 410.9 m² (4,422 ft²) COLLINGWOOD **PARKETTE** 04 03 02 01 DESIGN TO BE COORDINATED WITH MUNICIPALITY **PYLON SIGN** 3M X 6.25M HIGH

HAMILTON DRAIN TRAIL

POPLAR SIDEROAD
















BARRIER FREE BARRIER FREE PARKING SPACE PARKING SPACE PARKING SPACE PARKING SPACE CONFIGURATIONS

THE GENERAL CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS AND REPORT ALL ERRORS AND OMISSIONS TO THE ARCHITECT. DO NOT SCALE THE DRAWINGS. DO NOT USE THIS DRAWING FOR CONSTRUCTION UNLESS SIGNED AND SEALED BY THE ARCHITECT






THE GATEWAY CENTRE


CHARIS DEVELOPMENTS HIGHWAY 124 & POPLAR SIDE ROAD COLLINGWOOD, ONTARIO

> SITE PLAN - OPTION C3 BRANDED

	SCALE	As indicated	PROJECT NUMBER
	DATE	2024-08-23 9:47:07 AM	00000
	DRAWN	SO	202022
	CHECKED	REZ	
•	SHEET		REVISION










THE GENERAL CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS AND REPORT ALL ERRORS AND OMISSIONS TO THE ARCHITECT DO NOT SCALE THE DRAWINGS. DO NOT USE THIS DRAWING FOR



THE GATEWAY CENTRE

CHARIS DEVELOPMENTS
HIGHWAY 124 & POPLAR SIDE ROAD
COLLINGWOOD, ONTARIO

SITE PLAN 3D VIEW

_			
-	DRAWN	ВВ	202022
_	DATE	2024-08-23 9:47:10 AM	
_	SCALE		PROJECT NUMBE